



THOMAS E. FERGUSON  
AUDITOR OF STATE  
COLUMBUS, OHIO 43216

DEPUTY AUDITORS:

JAMES A. BOLDEN  
Administration

RICHARD G. NUSS  
CPA  
Auditing Division

RUSSELL ROUCH  
Management Advising  
Service

CERTIFICATION

I, Thomas Aquinas Burke, Supervisor, Land Office of the Auditor of State, duly authorized to perform the duties of the Auditor of State prescribed in Section 115.21 of the Ohio Revised Code, hereby certifies that the enclosed field notes and plats are true copies taken from records in our office. These plats and field notes are for the following townships in the United States Military District:

1. Range 4, Townships 8, 9 and 10
2. Range 5, Townships 8, 9, and 10
3. Range 6, Townships 8, 9, and 10
4. Range 7, Townships 8, 9, and 10
5. Range 8, Townships 8 and 9
6. Range 9, Townships 8 and 9

and in the Ohio River Survey

1. Range 11, Townships 14 and 15
2. Range 12, Townships 14 and 15
3. Range 13, Townships 13 and 14
4. Range 14, Townships 17 and 18
5. Range 15, Townships 19 and 20

Witness my hand and seal of the Office of the Auditor of State, at Columbus, Ohio, this Twentieth-Nine day of November in the year of Our Lord Nineteen Hundred and Eighty-Three (1983).

Thomas Aquinas Burke  
Supervisor  
State Land Office



O R S  
R T  
11 14 & 15

## Towns 14 &amp; 15, Range 11.

On the 31<sup>st</sup> day of October, 1806, came to the corner of Town 15, of Range 11. Compared my compass and chain with Mr. Keatts. The compass on trying on the Range Line, it varied to the East, 3°. Set it to suit that variation, and run the line

- 14
- South Between Secs. No. 1 & 2, Range 11, Town 14.  
3.05 A sight W. Oak, 24 ins. diam. Good soil, Oak Timber.
- 23.50 Crossed a Stream, W.
- 32.50 To a Post on the Old Boundary Line: a W. Oak, 14 ins. diam. bears N. 88 W. 12 lbs.; and another W. Oak, 24 ins. diam. bears N. 84 E. 19 links distant. Then Return
- North And run between Secs. 35 & 36, R. 11, T. 15.  
30.75 A Run, N. W.
- 40.00  $\frac{1}{4}$  Post: a Maple, 12 ins. diam. bears S. 16 E. 19 lbs.; a Double Spruce bears N. 35 W. 20 links. At a large Spring crossing the line, 1 chain, N. W.
- 18.00 A Shell-barked Hickory, 15 ins diam. Bottom land; Timber Blk. Ash, Oak and Thorn.
- 33.50 Crossed a Creek, — lbs. wide. No. Post, where a Spruce.
- 40.00 Post: where a Hickory, 12 ins. diam. bears N. 19 W. 11 lbs.; a Sugar tree, 15 ins. diam. bears S. 7 E. 28 lbs. distant. Corner Secs. 25, 24, 35, 36.
- East Here Random East. 3 chains, crossed a Creek, 25 lbs. wide. 7 chains, to Hill foot; Then through thin W. Oak land, not steep. 40 chains, Set Post. Continue: at 70 chains, good land; Timber, Hickory, &c. At 80.52 Range Line; move S. to Post, 85 lbs. Then

## Town 15, Range 11

0.00	West	Run and marked between 36 & 25.
4.00		Crossed a Drain, in rich land, N.3 Timber, Hickory, Sugar, &c.; then 2 <sup>d</sup> quality Oak land.
19.15		A W. Oak, 30 inches diameter.
40.00		A Post: whence a W. Oak, 30 ins. diam. bears S. 85 E. 16 Mts; and a W. Oak, 12 ins. diam. bears S. 85 W. 30 links distant. $\frac{1}{4}$ Sec.
7.50		To top of ascending ground, then level; <sup>Timber</sup> W. Oak.
28.00		To descending, poor hill.
33.50		To Bottom; Timber, Sugar, Gum & Thorn.
37.00		Creek, 25 Mts. wide, N. E.
40.00		To Post.
	North	Between Secs. 25 & 26. Low wet Bottom; Timber, Crab, &c.
31.00		Crossed a Run, E., 6 Mts. wide; then dry thin land; W. Oak Timber.
40.00		Post, on top of a hill: a Beech, 6 ins. diam. bears S. 85 E. 18 Mts; a W. Oak, 15 ins. diam. bears N. 68 E. 26 Mts. distant; $\frac{1}{4}$ Sec.
10.00		To Stony ground, descending.
20.83		A W. Oak, 15 ins. diam. at hill foot; 2 <sup>d</sup> Bottom.
24.00		Cross a Drain, E.; Bushy Bottom.
28.00		Cross a Run, S. 20 E. " "
40.00		Post: whence a Hickory, 10 ins. diam. bears N. 88 W. 17 Mts; and a Sugar, 24 ins. diam. bears S. 16 E. 62 links distant; at corner of 23, 24, 25, 26.
	North	Beginning at corner of Secs. No. 34 & 35, R. 11, S. 15, and run through Bottom land.
3.00		Cross a creek, 25 Mts. wide, E.
25.50		A Hickory, 12 ins. diam. on flat brushy ground.

## Down 15, Range 11.

Mts. Mts.	
40:00	Post: a W. Oak, 36 ins. diam. bears S. 48 W. 24 Mts.; a Hickory, 10 ins. diam. bears N. 53 E. 12 links distant; $\frac{1}{4}$ Sec. 2 <sup>d</sup> rate soil; W. Oak Timber.
30:35	A W. Oak, 18 ins. diam. good Oak land.
40:00	Post: a Hickory, 24 ins. diam. bears N. 25 W. 29 Mts.; and a W. Oak, 18 ins. diam. bears S. 68 E. 16 Mts. distant; at Corner of 26, 27, 34, 35.
East	Then Random East. At 3 chains cross a Run, S.; flat land, Oak Timber. 81 chains, to corner, 51 Mts. S. of Post.
West	Then return through flat cold Bottom; Timber, brushy Oak, Thorn, &c.
10:00	To ascending ground; then through flat upland; Timber, W. Oak, &c.
40:50	Set Post, being average distance: a W. Oak, 18 ins. diam. bears S. 45 W. 12 Mts.; and an Ironwood, 8 ins. diam. bears N. 42 W. 24 Mts. distant.
10:50	Cross a Drain, S. Open woods; Dogwood saplings.
40:50	To Post
North	Then run between Nos. 26 & 27
7:00	A W. Oak, 15 ins. diam. Open woods.
32:75	Cross a Drain and deep Hollow, &c.; broken ground.
40:00	Post: where a W. Oak, 15 ins. diam. bears S. 38 E. 27 Mts.; and a Red Oak, 24 ins. diam. bears N. 53 W. 29 Mts. distant; $\frac{1}{4}$ Sec.
16:73	A W. Oak, 16 ins. diam. on point of hill.
25:00	Cross a Drain, &c. in Bottom.
30:00	A Sugar tree, 12 ins. diam. on Point.
40:00	Post at Section Corner: a Sugar tree, 16 ins. diam. bears S. 5 E. 9 Mts.; a W. Ash, 20 ins. diam. bears

## Towns 14 &amp; 15, Range 11.

Chs. M.

S. 20 W. 30 links distant, in a Bottom.

- South Beginning at corner between Secs. No. 2 & 3, and  
run through Town 14, R. 11. Bottom land, brushy.
- 20.75 A Sugar tree, 15 inches diameter.
- 40.00 Post; a W. Oak, 20 ins. diam. bears S. 64 E. 33 Mts.;  
a Hickory, 18 ins. diam. bears S. 71 W. 20 links  
distant; standing in open woods.
- 6.00 To Boundary Line. Post, where a W. Oak, 24  
ins. diam. bears N. 30 W. 20 Mts.; a Hickory, 12  
ins. diam. bears S. 30 E. 16 Mts. distant. Now  
repair—
- South To corner of 3 & 4, R. 11, T. 14. Run through  
brushy Bottom.
- 2.00 To easy ascent. Brushy, Hazel, and W. Oak  
Timber.
- 5.14 6.78 A Hickory, 14 ins. diam. On level land.
- 14.50 A Maple, 20 ins. diam. Very brushy.
- 25.50 Cross a Run, N. E.
- 40.00 Post; a W. Oak, 24 ins. diam. bears N. 43 E.  
55 Mts.; a W. Oak, 20 ins. diam. bears S. E. 38  
Mts. distant. Timber, Hazel bushes.
- 18.50 Post, where a Dogwood, 9 ins. diam. bears N.  
82 W. 22 Mts.; and a W. Oak, 11 ins. diam.  
bears N. 59 E. 32 Mts. distant; Corner 3 & 4, R. 11, T. 14
- North Returns To corner 33 & 34, R. 11, T. 15, on Town  
Line.
- 5.50 Cross a Brook, 12 Mts. wide, S. E.
- 20.00 In dry brushy ground; W. Oak Timber.
- 40.00 Post; a W. Oak, 18 ins. diam. bears S. 28 W. 10  
Mts.; a W. Oak, 14 ins. diam. bears N. 2 W.  
45 Mts. distant. On level land, soil 2<sup>d</sup> quality;

## Town 15, Range 11.

6th. 1a.

- Undergrowth, Maple, Dogwood, &c.  
 50.26 To a W. Oak, 36 ins. diam. in open wood—  
 large Timber; W. Oak and B. Oak; Under-  
 growth Dogwood.
- 80.00 Post: a Cherry tree, 10 ins. diam. bears S. 40  
 E. 9 Mts.; and an Elm, same size, bears N.  
 15 W. 6 Mts. distant; Corner 33, 34, 27, 28.
- East. Now Random East. Brushy, thorny land. 8  
 chains, to brushy Bottoms. 19 chains, to Run,  
 S. E. 25 chains, dry ground, W. Oak tim-  
 ber. 80.12 Mts. 1.09 N. of Post.
- West Returns between 27 & 34—correct.  
 1.50 Cross a brushy Swamp, 3 chains wide; W. Oak  
 land.
- 40.06 Post: a W. Oak, 42 ins. diam. bears N. 82 E.  
 42 Mts.; and a W. Oak, 15 ins. diam. bears  
 S. 60 W. 38 Mts. distant. Undergrowth, Thorn, &c.
- 56.00 To low thorny Bottom—Brushy, Brushy.
- 72.00 Cross a Brook, 10 Mts. wide, S. E.
- 80.12 To Post, at corner 27, 28, 33, 34. Run—
- North Between Secs. 27 & 28.  
 3.00 To low brushy Bottom.
- 10.00 A Run, 10 Mts. wide, S. E.
- 20.00 To dry ground; Timber, Black Jack, Thorn, &c.
- 40.00 Post, near a Drain, E., where a Maple, 13  
 ins. diam. bears N. 51 W. 13 Mts.; and an  
 other Maple, same size, bears S. 51 E. 12  
 links distant. S. 74. Woods more open; tim-  
 ber, W. Oak, Maple and Gum.
- 80.00 Post: where a Hickory, 16 ins. diam. bears  
 N. 20 W. 58 Mts.; and a B. Oak sapling.

## Township 14415, Range 11.

		6 ins. diam. bears S. 13 W. 34 links distant; Corner 21, 22, 27, 28
	South	Repair to Corner Secs. 32 & 33, R. 11, T. 15, and Corner Secs. 4 & 5, R. 11, T. 14, and run on clay poor ridge; Black Oak timber.
		20.00 To brow of steep Hill, thence down; stony.
2.14		30.00 To Bottom; brushy and wet.
		35.00 Cross a Run, N. E.
		40.00 Set Post; a Cherry tree, 12 ins. diam. bears N. 34 W. 37 lks.; and a Jack Oak, 12 ins. diam. bears S. 3 E. 50 lks. distant.
		45.00 To upland.
		70.75 To Indian Boundary; where a Quaking Asp, 18 ins. diam. bears N. 30 W. 22 links; and a W. Oak, 12 ins. diam. bears East 11 links distant.
	North	Return to Secs. 32 & 33, R. 11, T. 15, and Run - Down stony hill, 10 chains, to Bottom.
		16.00 Cross a Brook, N. E.
		28.00 To high ground; Blk. and W. Oak timber.
		40.00 Set Post; a Red Oak, 30 ins. diam. bears N. 9 W. 22 lks.; a Hickory, 18 ins. diam. bears S. 44 E. 50 lks. distant.
		49.72 A W. Oak, 24 ins. diam. Level; 2 <sup>d</sup> rate soil; W. Oak and B. Oak Timber
		80.00 Set Post; a B. Oak, 36 ins. diam. bears S. 70 E. lks.; a Hickory, 12 ins. diam. bears N. 19 W. lks. distant; on level ground here.
	East	Turn and Run East between Secs. 28 & 33; through level land; B. Oak, W. Oak, and Hickory, Dogwood, &c. 50.32 lks. N. of the Post 53 lks.

## Town 15, Range 11.

Chs. Sta.	
West	Dry farming land; W. Oak Timber.
40.00	Set Post, where a Hickory, 15 ins. diam., bears N. 55 E. 14 Mts.; a Maple, 12 ins. diam., bears S. 64 W. 25 Mts. distant.
70.50	Cross a Spring Drain, N.
80.00	Post, at Secs. 28, 29, 32, 33, R. 11, T. 15. Here runs
North	Descending ground, and more Brushy.
40.00	Sapling, 5 ins. diam.; where a Hickory, 8 ins. diam. bears S. 2 E. 50 Mts.; and a Hickory, same size, bears N. 5 W. 21 Mts. distant; $\frac{1}{4}$ Section.
60.00	To Bottom. Brushy.
66.00	Cross a Brook, N. E.
69.50	To hill foot, 2 chains, steep.
72.00	To top of hill; small W. Oak timber; Brushy.
80.00	Post, in edge of Brushy Swamp or Bottom; where a Cherry tree, 12 ins. diam. bears N. 67 W. 56 Mts.; and another Cherry tree, same size, bears S. 16 W. 25 Mts. distant.
North	Beginning at the corner of Secs. 31 & 32, R. 11, T. 15, and running through dry ground, ascending.
12.00	To where highest; Oak timber.
36.50	Cross a deep Hollow and Drain, E.; lushy banks.
40.00	Post, where a Maple, 12 ins. diam. bears N. 44 W. 49 Mts.; and a W. Oak, 15 ins. diam., bears S. 13 E. 53 Mts. distant; $\frac{1}{4}$ Sec. on a bank or bar.
37.00	Cross a Brook, E.; brushy and steep banks.
27.50	Cross a Drain, E. } Thin soil; W. Oak Timber.
6.00	Cross a Drain, E. }
80.00	Post, where a Beech, 16 ins. diam. bears



## Town 15, Range 11.

Chs. Lks.

- S. 85 W. 36 Mts.; and a W. Oak, 24 ins. diam. bears S 61 E. 17 links distant. In flat cold ground; Timber, Maple, Oak and Gum. Corner Secs. 29, 30, 31, 32, R. 11, T. 15.
- East Random Post; through flat wet land; Timber, W. Oak and Maple; Mudergrowth, Beech and Dogwood. 11.50, cross a Drain; thin Oak land. 80.55 - 68 Mts. N. of corner. - Then correct back -
- West Through 2<sup>d</sup> quality land; Timber; B. Oak, W. Oak, &c.; Mudergrowth, Dogwood, Maple bushes, &c.
- 40.00 Post, where a W. Walnut, 18 ins. diam. bears N. 83 E. 14 Mts.; and a W. Oak, 15 ins. diam. bears S. 69 W. 39 Mts. distant; 1/4 Sec.
- 69.00 Cross a small Drain, S.
- 80.00 To Post at corner of Secs. 29, 30, 31, 32.
- North Here turn and run North.
- 16.55 A W. Oak, 15 ins. diam. Level; Timber, Oak, Chestnut and Poplar; Mudergrowth, Maple, Chestnut, Dogwood and Oak.
- 40.00 Post, where a Poplar, 12 ins. diam. bears N. 77 W. 10 Mts.; and a Poplar, same size, bears N. 88 E. 12 Mts. distant. 1/4 Sec. Timber small; Poplar, Quaking Asp and Chestnut.
- 61.80 A W. Oak, 15 ins. diam.; poor bushy ground.
- 69.00 Cross a Brook, N. E., narrow, bushy Bottom; thin dry ground.
- 80.00 Post; a W. Walnut, 10 ins. diam. bears N. 53 W. 22 Mts.; a W. Oak, 12 ins. diam. bears S. 56 E. 49 Mts. distant. Now return to No. 29, 30, 31, 32, and run

## Tracing 14 &amp; 15, Range 14.

Obs. 211	
West	Wet cold land; Timber, Maple, Oak, Snow-wood.
4.25	Cross a Run, S. Beechy banks; then easy ascent.
22.87	A W. Oak, 30 ins. diam. Good ground; Timber, Oak and Chestnut.
	Through thin brushy ground; Oak bushes.
40.00	Post, where a Poplar, 24 ins. diam. bears N. 16 E. 42 lbs; and a Chestnut, 10 ins. diam. bears S. 33 W. 20 lbs. distant. $\frac{1}{4}$ Sec.
43.50	Cross a Run, S.
65.25	A B. Oak, 27 ins. diam. } Brush, Oak and Chestnut.
75.50	Cross a Drain, S. }
81.00	To Range Line, S. of Post 1.52 lbs. Set Post, where a Hickory, 20 ins. diam. bears S. 9 E. 20 lbs; a B. Oak, 48 ins. diam. bears N. 61 E. 41 lbs. distant; Corner of Secs. 30 & 31, R. 11, T. 15.
South	Beginning at the corner of Secs. 5 & 6, R. 11, T. 14, and run between.
1.00	Cross a Drain, S. 10 W. }
10.50	Cross the same, S. 10 E. } Brushy thin soil.
23.00	To thorny Bottom.
38.50	Cross a Run, S. E.
40.00	Post, where a Plum, 4 ins. diam. bears N. 2 W. 8 lbs; and an Elm, 10 ins. diam. bears S. 47 W. 28 lbs. distant; in brushy Bottom.
52.50	To low Bottom, swampy and brushy.
65.50	Cross a Brook, N. E., 6 lbs. wide, deep.
80.00	Post, on a dry point; where a W. Oak, 12 ins. diam. bears N. 17 W. 12 lbs; a W. Oak, 16 ins. diam. bears S. 81 E. 13 lbs. distant; R. 11, T. 14.
South	Continued. Dry ground; W. Oak timber.
2.14	To Boundary Line: a W. Oak, 15 ins. diam. bears

Towns 14 & 15, Range 11.

Chs. Mks.

N. 45 E. 30 Mks.; and a W. Oak, same size, bears S. 45 E. 31 Mks. distant.

West Then return to the corner of 5, 6, 7, 8, R. 11, T. 14, and Randon West. 10 chains, to Brushy wet ground. 63 chains, cross a Brook, N. E. 45 chs. to poor Oak land; thorny, brushy Oaks, &c. Strike the Post, all but 4 Mks.

East Between Secs. 6 & 7. Brushy woods; W. Oak timber.

35.00 To a Drain, S. 80 E.; thence down it, crossing several times; Brushy Bottom.

T. 14.

40.00 Post, where a W. Oak, 15 ins. diam. bears S. 61 W. 41 Mks.; and same size W. Oak, bears N. 12 E. 37 links distant; on bank of Run; brushy Bottom.

60.00 To Point of high ground; Ash Timber.

63.50 Cross a Brook, N. E.; thickety, thorny bank; Crab, &c. &c.

70.00 To where ground is dry; scrubby Oak timber.

80.50 Set Post, corner of Secs. 5, 6, 7, 8, Town 14, R. 11.

East Continue. Through wavy land; Oak timber.

T. 14.

16.00 Post, where a W. Oak, 18 ins. diam. bears N. 52 W. 13 Mks.; and another W. Oak, 22 ins. diam. bears S. 25 W. 8 Mks. distant; on the Boundary Line.

Nov. 3.

East Return to corner of Secs. No. 21, 22, 27, 28, R. 11, T. 15, and Randon East. Through Oak land, level; then small descent. 40 chains, set Post. 59.50, a Drain, N. Then through good land. 66.50, cross a Brook, S. E. <sup>Bottom</sup> 40.31-39 Mks. N. of Post.

## Down 15, Ridge 11.

Chs. & Lks.	
East	Ran down between Secs. 23 & 26, R. 11, T. 15. - 40 chains, Post. Through good soil, Oak timber, to top of hill, descending E. 57.50, to Bottom. 75.00, cross a Run, S. E. 81.54, to Line, 16 lks. S. of Post. From this Post-
East	Ran down between Secs. 24 & 25. 3.00, to as- cending ground; stony and rich; some fallen timber. 35.00, to descending ground; rich, stony hill side. Post at 40.00. 64.00, to thicket, brushy; descending a hill to edge of woods. 81.10, to Post, 4 lks. South.
West	Then run back.
16.00	Through brushy timber burn, to wood-land; stony.
20.00	To Run; Bottom.
22.00	Cross a Run, S. E.
25.00	To foot of hill; then through stony rich land.
40.55	Post: a Lym, 10 ins. diam. bears S. 82 W. 20 lks.; and a Gum, 14 ins. diam. bears N. 80 E. 17 links distant. Continue Oak land, stony, good soil.
81.00	To Post.
North	Thence run through rich ground.
10.00	Cross a Run, S. W. } Bottom; then ascend a hill.
13.37	A Hickory, 10 ins. diam. }
40.00	Post, on level flat; 1 lks. Oak and Hickory timber. A W. Oak, 24 ins. diam. bears S. 53 E. 28 lks.; and a W. Oak, 18 ins. diam. bears N. 40 W. 33 lks. distant. 1/4 Sec.
56.63	A B. Oak, 42 ins. diam.; on stony West hill side, thickly set with rocks; Timber, B. Oak and Hickory.

## Town 15, Range 11.

Chs. Hrs.	
81.00	Post, where a Chestnut, 24 ins. diam. bears S. 10 W. 37 lbs.; and a Chestnut, 48 ins. diam. bears N. 18 E. 60 lbs. distant. Corner to Secs. 13, 14, 23, 24, R. 11, T. 15.
West	Return to Post, 23, 24, 25, 26, and correct.
6.50	Cross a Run, S. E.; through Rich Bottom.
10.00	To hill foot, moderate ascent; large B. & W. Oak Timber.
40.75	Post: a W. Oak, 15 ins. diam. bears N. 73 E. 7 lbs.; a W. Oak, 24 ins. diam. bears N. 88 W. 19 lbs. distant. $\frac{1}{4}$ Sec. Arable land; Oak Timber.
81.53	A Post, set at corner of 22, 23, 26, 27, R. 11, T. 15.
North	Here run between 22 & 23.
17.00	A W. Oak, 22 ins. diam. Pleasant wood; Oak Timber.
31.08	A Maple, 9 ins. diam. Level land; Oak and Dogwood.
40.00	Post: a W. Oak, 18 ins. diam. bears S. 15 E. 10 lbs.; a W. Oak, 12 ins. diam. bears N. 42 W. 31 lbs. distant. $\frac{1}{4}$ Sec.
75.00	To brow of rich hill; down it obliquely.
80.00	Post: a W. Oak, 40 ins. diam. bears S. 20 W. 15 lbs.; a Sugar, 12 ins. diam. bears N. 20 E. 40 lbs. distant.
West	Return 1 mile South and correct between 22 & 27; through good open woods.
13.00	Cross a Brook, S. E.; then ascend a hill.
21.00	Cross a Drain, N. Level Oak land.
40.00	Post: a W. Oak, 24 ins. diam. bears N. 33 E. 18 lbs.; a W. Oak, 30 ins. diam. bears S. 5 W. 21 lbs. distant.

## Town 15, Range 11.

Ch. Sk.	
50.00	Post. Tolerable good land.
North	Run between Secs. 21 & 22, R. 11, T. 15.
12.60	A W. Oak, 18 ins. diam. Level land; Oak timber, and Dogwood Saplings.
40.00	Post: a Chestnut, 24 ins. diam. bears S. 72 G. 51 lbs.; and a W. Oak, 16 ins. diam. bears N. 72 W. 9 lbs. distant; in open woods.
55.00	A B. Oak, 30 ins. diam. Timber, Oak & Chestnut, and Poplar Saplings.
80.00	Post: a W. Oak, 20 ins. diam. bears S. 12 G. 27 lbs.; a W. Oak, 30 ins. diam. bears N. 12 W. 11 lbs. distant. In center of Townships.
West	Repair to corner of Secs. 21, 22, 27, 28, and Random West 36.50, cross a Run, S.; open woods, Oak timber. Post at 40.00. 75.00, to brushy Bottom. 79.00, cross a Brook, S. E. 81.50, to Post, 12 lbs. S. of Post.
West	Continue West between Secs. 20 & 29, through brushy Oak and Chestnut Timber. — 40.00, Post, in head of Hollow; Maple timber. Then down. — 52.00, cross a Brook, S.; then low land and Bottom. — 71.50, cross a Branch of East Run, N. E. — 80.77, 31 lbs. S. of Post.
West	Here run and mark. Good land.
12.62	A W. Oak, 15 ins. diam.; Timber, R. Oak, and W. Oak, Dogwood, &c.
22.80	A W. Oak, 24 ins. diam. in edge of stony ground; through it.
40.00	Post: a Poplar, 8 ins. diam. bears S. 88 G. 47 lbs.; a Hickory, 20 ins. diam. bears N. 51 W. 57 lbs. distant.

## Town 15, Range 11.

Chs. Mts.	
50.93	A Hickory, 12 ins. diam. in woods open; less stony.
80.13	Post, on Range Line, 2.69 S. of Post: a Poplar, 24 ins. diam. bears N. 77 E. 16 Mts.; a W. Oak, 12 ins. diam. bears S. 77 W. 9 Mts. distant; Corner of Secs. 19 & 30, R. 11, T. 15.
North	Repair back to corner of 19, 20, 29, 30, R. 11, T. 15, an Run—
10.00	To Bottom.
11.00	Cross a Run, S. E.
12.53	A W. Oak, 12 ins. diam.
16.00	To dry poor ground.
40.00	Post: a W. Oak, 24 ins. diam. bears S. 17 E. 47 Mts.; an Ironwood, 4 ins. diam. bears N. 28 E. 17 links distant. Poor & brushy.
57.90	A W. Oak, 16 ins. diam. on flat ground; Timber, Maple and W. Oak; level, poor and brushy; Oak and Chestnut bushes.
80.00	Post: a W. Oak, 30 ins. diam. bears S. 26 W. 13 Mts.; a Hickory, 12 ins. diam. bears N. 69 E. 17 Mts. distant; Corner 17, 18, 19, 20, R. 11, T. 15.
East	Return 1 mile S. and correct between 20 & 29; rich soil.
9.00	Cross a Run, N. 80 E.
29.00	Cross last Brook, aided by another from the North
40.35	Post, where a Sugar tree, 15 ins. diam. bears S. 80 W. 9 Mts.; a Maple, 12 ins. diam. bears S. 82 E. 35 Mts. distant.
80.40	To Post, at Secs. 20 & 21. This last half mile was thin soil; small scrubby W. Oak.

## Town 15, Range 11.

Chs. Sta.	
North	Here turn and run N. through Brushy Bottom.
6.00	Cross a Brook, N. E.; through brushy swampy Bottom, Thorn, &c.
30.71	A W. Oak, 4 ft. 6 in. diam.; Sugar tree Bottom.
32.50	Cross last Brook, S. W.
40.00	An Ironwood, 3 ins. diam.; from which a Maple, 12 ins. diam. bears S. 46. 26 Ms.; a Sugar tree, 18 ins. diam. bears N. 53 E. 40 Ms. dist.
53.50	To Maple Timber; Ironwood and Oak bushes; level.
72.00	To dry ascending ground
80.00	Post, at corner 16, 17, 20, 21: a W. Oak, 30 ins. diam. bears N. 82 E. 32 Ms.; a Hickory, 12 ins. diam. bears S. 63 W. 37 Ms. distant, on S. hill side.
East	Return 1 mile South and correct East.
2.00	Cross a Brook, S.
6.00	To scrubby upland.
40.50	Post: a W. Oak, 24 ins. diam. bears S. 83 E. 4 Ms.; a W. Oak, 16 ins. diam. bears N. 74 W. 10 Ms. distant. Oak land.
81.00	Post at corner. Blk. Oak timber.
Nov. East	Beginning at the corner of 15, 16, 21, 22, and Ransom. High brushy land; Oak bushes, grape vines, and green vines.
40.00	To better ground; Oak timber.
81.00	A corner of 14 & 23.
East	
3.50	Cross a Run, S. Brushy ground.
40.00	Post, temporary. Pretty good land.
81.00	Line, 5 lbs. N. of Post.



## Town 15, Range 11.

Chs. Mts.	
East	Between 13 & 24.
3:30	To top of a rocky ridge.
12:30	Deep Hollow, N. Steep banks.
24:00	To better land; Timber, Oak, Hickory & Chestnut.
40:00	Post, temporary.
55:00	Rich land; Timber, Poplar and Sugar trees.
80:83	Range line, 45 Mts. N. of Post.
West	Here correct.
5:00	To good meadow land.
20:00	Good upland
40:40	Post: a Maple, 10 ins. diam. bears N. 29 W. 14 Mts; a Chestnut, 36 ins. diam. bears S. 16 W. 7 links distant.
68:00	Cross a deep Hollow, N.; then Stony hill.
71:00	To top of hill. Chestnut Timber.
80:40	Post.
North	Here run North.
4:00	To top of a ridge. Chestnut timber; Stony.
15:00	Where less Stony; descending.
21:08	A Poplar, 24 ins. diam.
34:50	Cross a Brook, E.; narrow Bottom.
40:00	Post: a W. Oak, 28 ins. diam. bears N. 81 W. 9 Mts; and a Poplar, 12 ins. diam. bears S. 74 E. 29 links distant. Bushy; Oak bushes.
60:74	A B. Oak, 24 ins. diam. Good soil; Timber, B. Oak, W. Oak and Hickory.
80:00	Post: a Maple, 12 ins. diam. bears N. 14 E. 31 Mts; and a B. Oak, 22 ins. diam. bears S. 35 E. 8 Mts. distant. Corner of 11, 12, 13, 14.
West	Return to 13, 14, 23, 24.
5:00	To good land; Oak timber.

## Town 15, Range 11.

66. 1/2	
40.50	A Post: a Hickory, 10 ins. diam. bears S. 48 W. 12 Mts.; a W. Oak, 20 ins. diam. bears N. 19 E. 4 links distant. Undergrowth, Buck & Dogwood.
77.00	Cross a small Run, S.
80.50	Post, at 14, 15, 22, 23, R. 11, T. 15.
North	Between 14 & 15.
32.34	A Chestnut, 36 ins. diam. Soil 2 <sup>d</sup> quality.
40.00	Post: a Hickory, 11 ins. diam. bears N. 75 E. 15 Mts.; a B. Oak, 24 ins. diam. bears N. 88 W. 34 Mts. distant; on a ridge.
50.00	A Brushy Ridge; fallen timber.
70.00	To Timber, Oak and Chestnut.
75.61	A W. Oak, 18 ins. diam. Soil 2 <sup>d</sup> quality.
80.00	Post: a Chestnut, 30 ins. diam. bears N. 30 W. 3 Mts.; and a Hickory, 8 ins. diam. bears S. 75 E. 25 Mts. distant; at Secs. 14, 15, 10, 11.
West	Repair to Corner Secs. 14, 15, 22, 23, and correct. Through pretty good land; Oak timber.
40.50	Post: a W. Oak, 30 ins. diam. bears S. 60 E. 7 Mts.; a Dogwood, 8 ins. diam. bears N. 60 W. 3 Mts. distant. Then brushy ground; gum trees, &c.
81.00	To the corner.
North	Turn and run between Secs. 15 & 16.
40.00	Post, on brushy Ridge: a Gum, 10 ins. diam. bears S. 47 W. 18 Mts.; a W. Oak, 24 ins. diam. bears N. 13 E. 138 Mts. distant.
50.00	Where timbered; W. Oak and Maple.
71.50	Cross a Run, N. 10 E.
80.00	Post: a Spanish Oak, 24 ins. diam. bears N. 81 E. 37 Mts.; a Chestnut, 30 ins. diam. bears S. 10 W. 12 Mts. distant.

## Town 15, Range 11.

7 <sup>th</sup> Nov	Chk. No.	Random between 16 & 21.
	40.00	Set Post, temporary.
	52.00	Cross a Run, S.
	80.66	Line, 24 Mts. S. of Post.
		West Between Secs. 17 & 20.
	28.00	Cross a Run, S. Ground 2 <sup>d</sup> quality.
	40.00	Post, temporary.
	55.00	Brushy and poor.
	79.93	To Line, 6 Mts. S. of Post.
		West Continued. Brushy, chestnut and Oak timber; poor; Undergrowth, Green Briars.
	40.00.	A Post: a Chestnut, 12 ins. diam. bears S. 70 E. 35 Mts.; a B. Oak, 10 ins. diam. bears S. 78 W. 8 Mts. distant. Through poor soil; undergrowth Green Briars.
	80.30	Post on Range Line: a B. Oak, 18 ins. diam. bears N. 38 W. 23 Mts.; a Chestnut, 12 ins. diam. bears S. 78 E. 33 Mts. distant; corner of Secs. 18 & 19, 3.68 Mts. South of established Post.
		North Beginning at corner of Secs. 17, 18, 19, 20, & run
	23.00	Cross a Run, upon soil; Brushy.
	40.00	Post: a Hickory, 12 ins. diam. bears N. 67 W. 6 Mts.; and a W. Oak, same size, bears S. 50 E. 35 Mts. distant.
	54.90	A Hickory, 12 ins. diam. Woods more open.
	57.17	A W. Oak, 18 ins. diam. Timber, Maple, &c.
	60.17	A Swamp Oak, in Hollow, 30 ins. diam.
	80.00	Post, in rich ground: a W. Oak, 24 ins. diam. bears S. 50 E. 53 Mts.; a W. Oak, 30 ins. diam. bears S. 82 W. 32 Mts. distant. Pretty good soil.

## Town 15, Range 11.

Chs. Lks.	
West	
15.00	Meadow land; Timber, Maple.
31.43	An Elm, 12 ins. diam. in edge of swamp.
40.00	Post, at West side of Swamp, where a Hickory, 12 ins. diam. bears S. 50 E. 26 lks., an Elm, 12 ins. diam. bears N. 58 W. 30 lks. distant. Timber, Maple, &c.
65.50	A Gum, 12 ins. diam. Arable level land.
79.61	To Range Line; a W. Oak, 22 ins. diam. bears S. 42 E. 27 lks.; a W. Oak, same size, bears S. 82 W. 30 lks. distant. 3.72 South of Old Post.
East	Beginning at Secs. 17, 18, 19, 20, and run through Brushy-
15.00	To Timber land; W. Oak and B. Oak; soil 2 <sup>d</sup> quality.
40.00	Post; a Gum, 8 ins. diam. bears N. 25 W. 3 lks.; a W. Oak, 30 ins. diam. bears S. 35 W. 13 lks. distant.
52.00	cross a Run, S.
80.00	Post, at 16, 17, 20, 21, R. 11, T. 15.
North	
30.00	A W. Oak, 18 ins. diam. Thin soil; scrubby Timber.
40.00	Post; a Hickory, 24 ins. diam. bears S. 2 E. 51 lks.; a W. Oak, 22 ins. diam. bears S. 9 E. 35 lks. distant. Soil 2 <sup>d</sup> quality; Timber, Oak and Hickory; Undergrowth, Oak, &c.
80.00	A W. Oak, 30 ins. diam. bears N. 43 W. 40 lks.; a Hickory, 10 ins. diam. bears N. 8 E. 13 lks. distant; 8, 9, 16, 17.

## Town 13, Range 11.

Chs. 1/4s.

East Repair to 16, 17, 20, 21, and new East.  
 15.50 Cross a Run, S. Soil 2<sup>o</sup> quality.  
 40.30 Post: a Dogwood, 8 ins. diam. bears N. 45 E.  
 32 Mts.; a W. Oak, 30 ins. diam. bears S. 35 W.  
 28 Mts. distant. S. 1/4.

80.66

8<sup>th</sup> Nov.

East Begin at the corner of 8, 9, 16, 17, and R. 10 & 11.  
 40.00 Post, temporary. Brush; Oak timber.  
 80.86 To line, 65 Mts. N. of Post.

North Between Secs. 9 &amp; 10, R. 11, T. 15.

8.25 Cross a Run, N. 10 W. Bushy Points.

16.75 Cross the same, E, aided by another from West.

40.00 Post: a W. Oak, 16 ins. diam. bears N. 86 E. 33 Mts.;  
 and an Asp, 14 ins. diam. bears S. 64 W. 13 Mts.  
 distant.

72.00 A B. Oak, 36 ins. diam.

73.50 Cross a Run, E.

78.61 A W. Oak, 18 ins. diam.

80.00 Post: a W. Oak, 20 ins. diam. bears N. 53 E. 40  
 Mts.; and a Chestnut, 8 ins. diam. bears  
 S. 27 W. 37 Mts. distant. Corner of 3, 4, 9, 10,  
 R. 11, T. 15.

East Between Secs. 10 &amp; 15.

Cross a deep Gut, N.

80.40 Post, at corner 10, 11, 14, 15.

East Between 11 &amp; 14, R. 10 &amp; 11.

40.00 Post. Timber, B. Oak, W. Oak,

65.00 Cross a Spring, near head S. Poplar, &amp;c.; good soil.

81.11 To line, 12 Mts. N. of Post.

## Town 15, Range 11.

6 hrs. 1/2	
East	
40.00	Post. Pretty good land; B. Oak timber. Here ascending a stony hill.
50.00	To top.
55.00	To brow, descending.
81.40	To Range Line, 3 Mks. N. of Post.
West	Between Secs. 12 & 13. Ascend a hill; Chestnut Timber.
25.00	To top of hill.
35.00	To where exceeding stony and rocky.
40.70	Post: a B. Oak, 15 ins. diam. bears N. 74 E. 25 Mks.; and a Maple, 11 ins. diam. bears S. 58 W. 30 Mks. distant. 1/4 Sec. Descent continues.
81.40	Post, at corner of 11, 12, 13, 14, R. 11, T. 15.
North	Between Secs. 11 & 12. Timber, Poplar & Oak.
22.50	Cross a small Run, N. E.
40.00	Post: a W. Oak, 22 ins. diam. bears S. 20 W. 13 Mks.; a W. Oak, 26 ins. diam. bears N. 39 E. 53 Mks. distant. 1/4 Sec. Soil 2 <sup>d</sup> quality.
48.50	A B. Oak, 20 inches diameter.
55.00	Cross a Path.
80.00	Post: a W. Oak, 20 ins. diam. bears S. 19 E. 23 Mks.; and a W. m 12 ins. diam. bears N. 38 E. 20 Mks. distant. Timber, B. Oak, W. Oak and Chestnut.
East	Random.
1.75	Cross a Drain, N.
11.25	Cross a Run, N.
40.00	Post. Pretty good land.
66.00	Cross a Run, N.
79.50	Cross a Spring Run, N.
81.20	To Range Line, 12 Mks. N. of Post.

## Town 15, Range 11.

Chs. Chs.

West Corner back.

1.75 Cross a Spring Run, N. Meadow land; Timber,  
Hickory and Ash.

15.00 Cross a Run, N. at foot of hill; easy ascent.

40.00 Post: a W. Oak, 18 ins. diam. bears N. 25 W. 40  
ths; a W. Oak, 16 ins. diam. bears S. 55 E.  
18 links distant. Level land; W. Oak timber.

70.00 A Run, N.

79.50 Cross a Spring Run, N.

North Run between Secs. 1 & 2. Wet. Mostly ground  
22.00 To Bottom. Hickory, B. Ash and Swamp Oak  
Timber.

35.25 Cross a Brook, 20 ths. wide, S. E.

38.00 To arable ground; Timber, W. Oak; Undergrowth,  
Thorn.

40.00 Post: a W. Oak, 20 ins. diam. bears S. 32 E. 4

ths.; and a W. Oak, 16 ins. diam. bears N. E. 28  
ths. distant. S. 1/4. Undergrowth, Ironwood.80.37 To Town Line & Post, where a W. Oak, 20 ins. diam.  
bears N. 55 W. 28 ths.; and a Hickory, same size,  
bears S. E. 24 ths. distant; 93 ths. East of the Post  
already.

West Return to 11, 12, 13, 14, and correct.

16.50 Cross a Spring near head S. E. Arable land.

40.55 Post: a W. Oak, 18 ins. diam. bears S. 33 W. 8 ths.;  
and a Hickory, 12 ins. diam. bears N. 12 E. 8 ths.  
distant.

81.11 To Post at corner of Secs. 10, 11, 14, 15.

North Then run North.

15.26 A W. Oak, 36 ins. diam.

26.31 Cross a Run, N. E.

Town 15, Range 11.

Ch. No.	
32.50	To a Swamp, 1 Chain wide.
40.00	Post, in low wet ground: a W. Oak, 20 ins. diam. bears S. 41 E. 26 lbs.; and a Maple, 14 ins. diam. bears N. 27 W. 46 lbs. distant.
55.53	A W. Oak, 27 inches diameter.
61.00	Cross a Path.
80.00	Post: a Cherry tree, 8 ins. diam. bears S. 6 W. 18 lbs.; and a W. Oak, 20 ins. diam. bears N. 6 W. 38 lbs. distant. Return to 2, 3, 10, 11.
West	Between 10 & 15. Through good land.
40.20	A W. Oak, 18 ins. diam. bears N. 80 W. 23 lbs.; a Poplar, 10 ins. diam. bears S. 61 W. 14 lbs. dist.
48.50	Cross a deep Hollow, N. } A close thicket. Oak
77.25	Cross Drain, N. W. } Bushes, Grape Vines,
79.00	Cross a Drain, N. } Green Brier, &c.
80.40	To corner.
br. 9. West	Beginning at corner of Secs. 9, 10, 15, 16, and correct between 9 & 16. Good soil; Timber, B. Oak and W. Oak.
40.43	Post: a Spruce, 8 ins. diam. bears N. 48 E. 15 lbs.; and an Elm, 14 ins. diam. bears S. 84 W. 16 lbs. distant.
56.00	Cross a Drain, N. Soil 2 <sup>d</sup> quality.
80.40 [80.86?]	Post, at corner of 8, 9, 16, 17, R. 11, T. 15.
West	Random between 8 & 17.
40.00	Post, temporary. } Level. Timber, W. Oak and
53.50	Cross a Drain, S. W. } B. Oak; Undergrowth, Oak,
69.00	Cross a Run, S. } Dogwood, Green Brier.
79.84	To line, 25 lbs. N. of Post at 7, 8, 17, 18.
North	Between Secs. 7 & 8
6.25	A Run, E.



## Town 15, Range 11.

Chs. 7.

- 11.30 A Spanish Oak, 36 ins. diam. }  
 15.89 A Chestnut, 30 ins. diam. } Gumbo, Oak & Chestnut.
- 40.00 Post: a W. Oak, 24 ins. diam. bears S. 26 W.  
 31 lbs.; a W. Oak, 26 ins. diam. bears N. 7  
 W. 14 lbs. distant.
- 66.58 A W. Oak, 20 ins. diam.
- 80.00 Post: a Hickory, 24 ins. diam. bears S. 37 E.  
 25 lbs.; a W. Oak, 15 ins. diam. bears S. 81 W.  
 25 links distant; corner of Secs. 5, 6, 7, 8, R. 11,  
 T. 15.
- East Return 1 mile S. to corner of Secs. 7, 8, 17, 18, and  
 correct between Secs. 8 & 17.
- 11.00 To a Run, S.
- 26.00 Cross a Drain, S. W.
- 39.97 Post: a W. Oak, 12 ins. diam. bears S. 63 E. 40  
 lbs.; and a W. Oak, 24 ins. diam. bears N. 4  
 E. 35 lbs. distant,  $\frac{1}{4}$  Sec.
- 79.84 To Post at corner of Secs. 8, 9, 16, 17.
- North Between Secs. 8 & 9.
- 28.20 An Elm, 15 ins. diam.; head of a rich hollow.
- 40.00 Post: a Hickory, 12 ins. diam. bears S. 33 E. 12  
 lbs.; and a W. Oak, 30 ins. diam. bears N.  
 60 W. 26 lbs. distant; on West side of a steep  
 bank.
- 54.67 An Elm, 18 ins. diam. in head of hollow, leading E.
- 78.50 Cross a Run, E.
- 80.00 Post: a Hickory, 12 ins. diam. bears N. 63 E.  
 13 lbs.; and a Poplar, 10 ins. diam. bears S.  
 50 W. 45 lbs. distant; at 4, 5, 8, 9.
- West Random between Secs. 5 & 8.
- 40.00 Post, temporary.

## Town 15, Range 11.

Chs. Hrs.	
47.00	Cross a Run, N 85 E.
80.61	To line, 5 Hrs. N. of Post.
North	Between Secs. 5 & 6.
8.77	A Maple, 9 ins. diam.
40.00	Post: a W. Oak, 8 ins. diam. bears S. 53 W. 40 Hrs.; and a Chestnut, 22 ins. diam. bears N. 13 W. 37 Hrs. distant.
67.35	A Hickory, 20 inches diameter.
79.75	To the Town Line. A Post, where a W. Oak, (a former sight tree) 22 ins. diam. bears West 13 Hrs.; and a W. Oak, 18 ins. diam. bears S. 70 E. 33 Hrs. distant; Corner of Secs. 5 & 6, 5.30 West of the Town Stake.
West	Return S. 1 mile to Corner Secs. 5, 6, 7, 8, and run West.
27.61	A Hickory, 15 ins. diam.
40.00	Post: a Gum, 10 ins. diam. bears N. 86 E. 35 Hrs.; and a Hickory, 14 ins. diam. bears N. 44 W. 35 Hrs. distant.
65.00	To where poor and brushy, with Green trees, &c.
71.00	To thickety Swamp. This Swamp is inaccessible by angles. It is about
East	Beginning at the corner of 5, 6, 7, 8, and correct between Secs. 5 & 8.
33.00	A Run, N. 85 E.
40.30	Post: a Poplar, 20 ins. diam. bears N. 70 W. 27 Hrs.; and a Hickory, 12 ins. diam. bears S. 74 E. 28 Hrs. distant.

## Town 15, Range 11.

Chs. Mks.

East On Random between 10 & 3, Town 15, R. 11.  
 30.50 Cross Indian Tract, course S. E.  
 40.00 Set  $\frac{1}{4}$  Sec. Post, temporary. This  $\frac{1}{2}$  level W. Oak  
 land; Undergrowth, Dogwood; good soil.  
 65.00 Cross Stream, 5 Mks., N.  
 81.50 To N. & S. line, corner to Secs. 2, 3, 10, 11. Fell  
 N. of Post 4 Mks. Sand, as the first.

East On Random between Secs. 2 & 11.  
 39.61 Cross Stream, 4 Mks., course N.  
 40.00 Set  $\frac{1}{4}$  Sec. Post, temporary. Sand much as  
 the last.  
 82.18 To N. & S. line. Fell South 31 Mks. of Post, cor-  
 ner of Secs. 1, 2, 11, 12. Sand as the last.

West Corner between Secs. 2 & 11.  
 41.09 Set  $\frac{1}{4}$  Post at average distance; where a Beech,  
 12 ins. diam. bears S. 8 $\frac{1}{2}$  E. 30 Mks.; and a  
 W. Walnut, 13 ins. diam. bears North 4  
 Mks. distant.  
 82.18 To Post, corner to Secs. 10, 11, 14, 15, [2, 3, 10, 11?]

Monday, 10<sup>th</sup> Nov. 1806.

North Between Secs. 2 & 3.  
 7.67 W. Oak, 30 ins. diam.  
 19.50 Cross Stream, 4 Mks., West. Wet brushy Bottom.  
 25.50 Cross Stream, 6 Mks., course East.  
 36.12 Sugar tree. Brushy Bottom terminates.  
 40.00 Set  $\frac{1}{4}$  Sec. Post, where a Sugar, 5 ins. diam. bears  
 S. 7 $\frac{1}{2}$  W. 18 Mks.; a Dogwood, 4 ins. diam.  
 bears N. 61 E. 19 Mks. distant. This  $\frac{1}{2}$  part wet  
 marshy Bottom - balance good upland.  
 44.12 Cross Stream, 20 Mks., course N. W.; Deep slow  
 current, muddy banks and bottom.

Town 15, Range 11.

Chs. Lhs.

81.34 To Town Line. Fell East of Post, 17 Mts.  
Set Post, corner to Secs. 2 & 3, T. 15, R. 11;  
where a B. Oak, 20 ins. diam. bears S. 32  
W. 23 Mts.; and a Cherry, 15 ins. diam.  
bears S. 44 1/2 E. 39 Mts. distant. This 1/2 part  
low brushy, and part upland; thin soil;  
scrubby timber; undergrowth, Hazle and  
Ironwood.

West Corner between Secs. 3 & 10.

40.75 Set 1/4 Sec. Post at average distance; where a  
Beech, 10 ins. diam. bears N. 35 E. 38 Mts.;  
and a W. Oak, 24 ins. diam. bears S. 10 E.  
4 Mts. distant.

81.50 To Corner of Secs. 3, 4, 9, 10.

West On Random between Secs. 4 & 9.

27.40 A Steam, course N. 1/2 E.  
40.00 Set 1/4 Post, temporary. This 1/2 good soil;  
Timber, W. Oak, B. Oak; Undergrowth, Dogwood,  
Ironwood, &c.

81.44 To N. & S. line. Fell South of Post 77 Mts,  
corner to Secs. 4, 5, 8, 9. Land good soil;  
Timber, W. Oak, B. Oak, Sugar, W. Walnut, &c.

North Between Secs. 4 & 5.

4.50 Cross a Steam, 4 Mts., course East.

14.04 A Hickory, 25 ins. diam.

40.00 Set 1/4 Sec. Post, where a W. Oak, 10 ins.  
diam. bears S. 87 E. 15 Mts.; and a Dogwood,  
4 ins. diam. bears N. 78 W. 20 Mts. distant.

41.75 A W. Oak, 36 inches diameter.

56.13 A Hickory, 10 inches diameter.

64.50 Cross Indian Trail, course S. E.

72.90 Cross a Steam, 6 Mts., course East.

## Town 15, Range 11.

Chas. Ho.

- 80.48 To Town Line. Fell West of Post 4.17 Ms.  
Set Post, corner to Secs. 4 & 5; where a B.  
Oak, 20 ins. diam. bears S. 35 E. 27 Ms.;  
and a Gum, 15 ins. diam. bears S. 31 W.  
50 Ms. distant. This mile level land,  
good soil; Timber, B. Oak, W. Oak, Hick-  
ory, &c.; Undergrowth, Dogwood.
- East Correct between Secs. 4 & 9.
- 37.25 A Run, N.
- 39.00 Steep bank, ascending; Timber, W. Oak.
- 40.72 Post: a W. Oak, 24 ins. diam. bears N. 12 W.  
13 Ms.; a Beech, 9 ins. diam. bears S. 22  
W. 27 Ms. distant.
- 54.00 Cross a Brook, N. W.; narrow Bottom, steep  
banks; then through Oak land.
- 81.44 Post at corner of 3, 4, 9, 10.
- North From 3, 4, 9, 10, run N. between Secs. 3 & 4.
- 17.50 Cross a Path.
- 31.86 An Elm, 20 ins. diam. at Bottom land.
- 37.50 Cross a Brook, E.
- 40.00 Post: a Jack Oak, 18 ins. diam. bears  
N. 70 W. 13 Ms.; and a Cherry, 15 ins.  
diam. bears S. 74 E. 7 Ms. distant. Bottom
- 57.50 Cross a Brook, 10 Ms. wide, S. 10 E. Brushy,  
Thorny Bottom, and the higher part tim-  
bered with Jack Oak, Maple, &c.
- 80.00 Post on Town Line: a Maple, 8 ins. diam.  
bears S. 53 E. 18 Ms.; and an Asp, 18 ins.  
diam. bears N. 63 W. 30 Ms. distant 2.34  
Ms. West of Town Post.

Surveyed by John Beeve, 1806.