



**THOMAS E. FERGUSON**  
 AUDITOR OF STATE  
 COLUMBUS, OHIO 43216

DEPUTY AUDITORS:

JAMES A. BOLDEN  
 Administration

RICHARD G. NUSS  
 CPA  
 Auditing Division

RUSSELL ROUCH  
 Management Advising  
 Service

CERTIFICATION

I, Thomas Aquinas Burke, Supervisor, Land Office of the Auditor of State, duly authorized to perform the duties of the Auditor of State prescribed in Section 115.21 of the Ohio Revised Code, hereby certifies that the enclosed field notes and plats are true copies taken from records in our office. These plats and field notes are for the following townships in the United States Military District:

1. Range 4, Townships 8, 9 and 10
2. Range 5, Townships 8, 9, and 10
3. Range 6, Townships 8, 9, and 10
4. Range 7, Townships 8, 9, and 10
5. Range 8, Townships 8 and 9
6. Range 9, Townships 8 and 9

and in the Ohio River Survey

1. Range 11, Townships 14 and 15
2. Range 12, Townships 14 and 15
3. Range 13, Townships 13 and 14
4. Range 14, Townships 17 and 18
5. Range 15, Townships 19 and 20

Witness my hand and seal of the Office of the Auditor of State, at Columbus, Ohio, this Twentieth-Nine day of November in the year of Our Lord Nineteen Hundred and Eighty-Three (1983).

Thomas Aquinas Burke  
 Supervisor  
 State Land Office



USMD  
 R T  
 4 9

# West boundary of Township N<sup>o</sup> 9 Range N<sup>o</sup> 3

North

- 137.. - a white Oak 16" diamt-
- 151.. 26 a D<sup>o</sup> 3 feet D<sup>o</sup>
- 160.. - a small brook running N<sup>w</sup> good Land for last 30 chains
- 170.. 61 a white Oak 14" diamt-
- 200.. - Set Post at the Northwest corner of Town 9 and Southwest corner of T10 Range 3 and corner to Towns 9 & 10 Range 4 - a Maple 14" diamt bears S17<sup>o</sup> 30' E 70 links & a white Oak 15" diamt bears N39<sup>o</sup> 30' W 86 links marked per plan -

# North boundary of Township N<sup>o</sup> 9 Range N<sup>o</sup> 3

- June 15<sup>th</sup> Beginning at the Northeast corner of Town 9 and south east of Town 10 Range 3 - and corner to Town West - 9 & 10 Range 2 Run West -
- 22.. 57 a white Oak 18" diamt-
- 30.. 33 a D<sup>o</sup> 3 1/2 feet D<sup>o</sup>
- 38.. - to a brook running S<sup>w</sup> 20 links wide at foot of hill having descended for last 16 chains
- 49.. - to Sugar Creek running S50<sup>o</sup> E
- 51.. - Over the brook Lurranet Rapid
- 57.. 70 a white Walnut 2 feet diamt-
- 60.. - High bank over small brook running S20<sup>o</sup> W rich bottom Land for last 22 chains timber sugar tree Walnut hickory
- 77.. 95 a hickory 14" diamt-
- 80.. - flat Land nearly destitute of timber much black jack and white Oak brush -

West boundary of Township No. 9 Range No. 3

June 14<sup>th</sup> 1790 - Beginning at Southwest corner of T<sup>own</sup> 9 Range 3 and Southeast of Town 9 Range 4 - Run

10 <sup>..</sup> 76	a white oak 30 <sup>"</sup> diam <sup>t</sup>
15 <sup>..</sup> 62	a <sup>do</sup> 18 <sup>"</sup> <sup>do</sup>
25 <sup>..</sup> 20	a <sup>do</sup> 36 <sup>"</sup> <sup>do</sup>
25 <sup>..</sup> 75	a small brook running NW
41 <sup>..</sup> -	a Maple 14 <sup>"</sup> diam - good land from the corner timber white oak Black oak Hickory &c
43 <sup>..</sup> 25	a Brook 10 links wide runs west
50 <sup>..</sup> 19	a white oak 13 <sup>"</sup> diam <sup>t</sup>
61 <sup>..</sup> -	Sparks trail to Pittsburgh by Tuscaroras
61 <sup>..</sup> 00	a white oak 13 <sup>"</sup> diam <sup>t</sup>
77 <sup>..</sup> -	small brook running NW
78 <sup>..</sup> 00	white oak 15 <sup>"</sup> diam <sup>t</sup>
86 <sup>..</sup> 10	Brook 10 links wide running west
93 <sup>..</sup> 53	Forked white oak 2 <sup>1</sup> / <sub>2</sub> feet diam <sup>t</sup>
100 <sup>..</sup> 25	a Hickory 10 <sup>"</sup> diam <sup>t</sup>
126 <sup>..</sup> 61	a white oak 20 <sup>"</sup> diam <sup>t</sup>
134 <sup>..</sup> 09	a white oak 17 <sup>"</sup> <sup>do</sup> the line has run for last 46 chains west side of a ridge soil good timber white oak Hickory &c
146 <sup>..</sup> 50	a Brook 10 <sup>"</sup> links wide running west
150 <sup>..</sup> -	apend for last 42 chains to top of hill the soil good timber white oak Black oak Hickory &c
150 <sup>..</sup> 30	a Black Oak 18 <sup>"</sup> diam <sup>t</sup>
165 <sup>..</sup> 50	a small brook running west
173 <sup>..</sup> 50	white oak 2 feet diam <sup>t</sup>
178 <sup>..</sup> -	over a small <sup>brook</sup> running SW

West boundary of Township No. 9 Range No. 3 cont'd

North

- 180.. - Over a brook 10 links wide running S 30 W -  
 180.. 70 a white Oak 14" diam.  
 192.. - to top of hill having ascended for last 12 chains  
 200.. - Set post corner to Sections No. 2 & 3 Town 9 Range 3  
 and No. 194 Town 9 Range 4 - a white Oak 13" diam.  
 bears S 4 W 21 links & a white Oak 9" diam. bears  
 N 60 E 26 Links marked per plan -  
 Land broken for last 20 chains but the soil good  
 timber white Oak, Black Oak, Hickory &  
 underwood Oak Hickory &  
 2 1/2 Miles North -
- 10.. 12 a white Oak 13" diam.  
 23.. 50 to a small brook running N 30 W.  
 32.. - a small brook running west having ascended hill  
 obliquely for last 27 chains  
 45.. 92 a white Oak 14" diam. - rising hill for last 13 chains  
 66.. - a white Oak 10" diam.  
 76.. 50 small brook running N. W.  
 76.. 94 Hickory 10" diam.  
 80.. - Land somewhat broken for last 40 chains timber  
 white Oak Black Oak Hickory & some Chestnut -  
 93.. 91 a Hickory 10" diam.  
 106.. 01 a white Oak 14" diam.  
 108.. 50 a small brook  
 109.. - another small brook joins the other last noted  
 125.. - rising hill for last 16 chains Land stony on the  
 ascent -

North boundary of Township No. 9 Range No. 4

- West - From the Northeast corner of Town 9 and Southeast of Town 10 Range 4 - Run west -
- 17<sup>6</sup> 38 to a Black Oak 12" diam.
- 20<sup>11</sup> - Good level Land from the corner timber principally white Oak -
- 21<sup>11</sup> 50 some large rocks descending off of high bank onto bottom
- 26<sup>11</sup> 01 a Black Oak 18" diam. on the east side of a pond bearing South of N.W. 1.20 links wide
- 35<sup>11</sup> 50 to Sugar Creek running N.E. good Bottom Land for last 10 ch. timber sugar tree, Hickory, Walnut Elm bush &c
- 36<sup>11</sup> 50 Over the creek
- 37<sup>11</sup> 43 a branch of Sugar Creek 50 links wide from west 1.50 below of this creek runs apparently North
- 39<sup>11</sup> 00 a White Walnut 15" diam.
- 39<sup>11</sup> 15 an Elm 3 feet -
- 39<sup>11</sup> 05 the east noted branch of sugar creek the line running in bend of creek -
- 49<sup>11</sup> 30 Over the bend of the creek here coming from S25
- 50<sup>11</sup> - a White Oak 14 feet diam.
- 60<sup>11</sup> 91 a Maple 10" diam.
- 66<sup>11</sup> - a rocky nob or eminence 1 ch. North
- 70<sup>11</sup> 05 a sugar tree 14" diam.
- 74<sup>11</sup> - a Brook 20 links wide running into the other or last branch of sugar creek
- 75<sup>11</sup> 50 to last noted creek line crossing in a bend
- 76<sup>11</sup> 50 Over the bend of creek coming from the N.W.
- 84<sup>11</sup> 03 a hickory 12" diam.

North boundary of Township No. 9 Range No. 4 - cont.

- West -
- 90..70 a Red Oak 2 1/2 feet diam - Bottom land along the line for last 66 chains somewhat broken with gullies ponds &c but the soil is rich, timber sugar tree white walnuts white oak Red Oak Elm Hickory beech &c
- 99..50 to a rock 20 feet perpendicular
- 125.. - Land Rocky & stony for last 26 chains timber (with) White & Black Oak beech Maple &c small oaks & beech &c
- 126..04 a beech 13" diam -
- 133.. - Rising a hill for last 0 chains
- 136..20 a white oak 2 feet diam -
- 156..33 a " 2" 15" - 9" Land still rocky & stony & stony soil good timber the same as described
- 150..25 a small brook rising south
- 150..56 a Red Oak 2 1/2 feet diam -
- 166..70 " 2 1/2 " 8" - 8"
- 177..35 a sugar tree 14" diam -
- 184..70 a white oak 15" 8"
- 189.. - Rising hill for last 5 chains
- 193..71 a white oak 2 1/2 feet diam -
- 200..04 a " 14" 8"
- 200.. - Set post corner to Sections No. 1 & 2 Town 9 and 3 & 4 Range 10 - a white oak 2 1/2 feet diam - bears S 37 E 67 links of a Red Oak 14" diam - bears N 57 W 62 links marked per plan Rich Land for last 40 chains timber different kinds of Oak - Hickory sugar tree beech ash spire & Hazel bark
- 2 1/2 Miles West
- 7.. - a small brook rising south

North boundary of Township N<sup>o</sup> 9 Range N<sup>o</sup> 4. Cont.

West -

- 12..50 a White Oak 20" diam<sup>t</sup>
- 27.. - gently rising a hill for last 7 chains
- 34..50 a White Oak 13" diam<sup>t</sup>
- 39.. - The line has run on the south side of hill for last 12 chains
- 45.. - Descending off of hill for last 6 ch<sup>s</sup>
- 52..21 a White Oak 14" diam<sup>t</sup>
- 60.. - to top of hill having ascended for last 17 ch<sup>s</sup> - Land Rich timber White & black oak considerable Dogwood
- 65..00 a White Oak 17" diam<sup>t</sup>
- 71..10 a Hickory 12" diam<sup>t</sup> Rich Land but stony for last 20 chains
- 79..50 a White Oak 12" diam<sup>t</sup>
- 94..90 a D<sup>o</sup> 2 feet D<sup>o</sup>
- 102..00 a D<sup>o</sup> 2 1/2 feet D<sup>o</sup>
- 116..95 a D<sup>o</sup> D<sup>o</sup> D<sup>o</sup>
- 123..34 a D<sup>o</sup> 14" D<sup>o</sup>
- 135.. - Land good for last 19 chains timber White Oak Black Oak Chestnut &
- 140..24 a Gum 13" diam<sup>t</sup>
- 141..50 a small brook running North
- 147..77 a White Oak 2 feet diam<sup>t</sup>
- 160.. - Rocky stony Land for last 20 chains
- 162..50 a sugar tree 16" diam<sup>t</sup>
- 164..90 a small brook running North at foot of a hill having descended for last 8 chains
- 172..38 a Hickory 14" diam<sup>t</sup>
- 181..20 a brook 20 links wide running N 10 E

North boundary of Township No. 9 Range No. 4 - cont.

West

104#53 a sugar tree 12" diam.

194#36 an Elm 11" dia.

Post corner to Towns 9 & 10 Range 4 -

a Maple 16" diam. bears N 5° W 32 links and a  
White Oak 14" diam. bears S 29° E 40 links marked

per plan Surveyed June 16<sup>th</sup> 1798



# Description of Township N<sup>o</sup> 9 Range 4 -

Corner Posts bearings &c Distances quality of the Land

Order	Kind of Wood	Inches diam	Course	Links	Distance	Quality of the Land
A	White Oak	30	S 47 E	14	From A to B	Land of middling quality in general hills of easy aspect but stony in places timber Oak, Hickory, Chestnut some sugar tree &c
	White Oak	36	N 64 E	60	from B to C	Land rich but rather broken & stony, except the last mile is good farming land timber Oak, Hickory, sugar tree, &c
B	White Oak	30	S 31 E	67	from C to D	one half tolerable hill land the rest stony & rough mixed together timber Oak, Hickory, &c
	Red Oak	14	N 57 W	62	from D to E	good hill land timber, Oak, Hickory & undergrowth, Oak brush
C	Maple	14	S 17.30 E	70	from E to F	the first half creek bottom & the last good upland timber, Oak, Hickory, Cherry, Thorn, affinis nine bark Crab &c
	White Oak	15	N 39.30 W	86	from F to G	good hill land timber White Oak, Chestnut &c
D	White Oak	13	S 4 W	21	from G to H	good farming land meadow & upland in general, timber Oak, Hickory, Chestnut, sugar tree, cherry, B. ash, Thorn, plum, &c
	Do.	9	N 60 E	26	from H to A	Land rich but rather broken some good bottoms on the larger streams timber Oak, Hickory, B. ash, sugar tree, Poplar, spice bush &c
E	White Oak	12	N 64 W	27		
	Do.	14	S 9 W	37		
F	White Oak	36	N 5 W	39		
	Maple	10	S 71.15 E	31		
G	Affinis	5	S 9 W	10		
	Do.	4	N 5 E	12		
H	White Oak	36	S 15 W	60		
	Sugar tree	0	N 3 W	0		

\* this post stands 3<sup>o</sup> 32 south of the point of intersection or true corner

2<sup>d</sup> Section N<sup>o</sup>. 2  
acres 4.066 $\frac{4}{10}$

2<sup>d</sup> Section N<sup>o</sup>. 1  
acres 4.028

2<sup>d</sup> Section N<sup>o</sup>. 3  
acres 4.000

2<sup>d</sup> Section N<sup>o</sup>. 4  
acres 4.025

Sugar Creek

Shukelippee

203.32

200

611 2  
204.25

TOWNSHIP N<sup>o</sup>. IX }  
RANGE N<sup>o</sup>. IV }

MILITARY DISTRICT

SCALE of Fifty Chains to an Inch

West boundary of Township T<sup>o</sup> 9 Range N<sup>o</sup> 4

- June 17<sup>th</sup> 1790 - From corner of Towns 8 & 9 -  
 North Ranges 4 & 5 - Run North -  
 2...03 to a Red Oak 15" diam<sup>t</sup>  
 12...57 a Hickory 10" D<sup>o</sup>  
 41...50 a White Oak 2 1/2 feet diam<sup>t</sup>  
 45...50 a Hickory 2 feet D<sup>o</sup>  
 49...92 Red Oak 18" diam<sup>t</sup> - good land from the corner  
 timber white Oak, Black Oak, Hickory, &  
 50...59 a Red Oak 2 feet diam<sup>t</sup>  
 64...01 a White Oak 12" D<sup>o</sup>  
 82...04 a D<sup>o</sup> 11" D<sup>o</sup> at foot of hill having descent  
 down North part of the hill for last 24 chains  
 Land rich Timber White Oak Hickory Red Oak sugar tree  
 85... in middle of brook 25 links wide running East  
 103... through bottom land for last 20 chains Timber  
 Black ash, Thorns, Plum, sugar tree, Cherry, hickory  
 & land set of trees  
 107...12 a White ash 10" diam<sup>t</sup>  
 115...50 to a small brook running S E  
 121...79 a Hickory 10" diam<sup>t</sup> Rich Land for last 17 chains  
 Timber White Oak Black Oak Hickory &  
 143... rising hill for last 20<sup>th</sup> of a percent gentle side good cut stone lined with  
 144...00 a Hickory 10" diam<sup>t</sup> (= 18" D<sup>o</sup> 30 Hickory &  
 157...04 a D<sup>o</sup> 6" D<sup>o</sup> Descent hill for last 14 chains  
 the land rich Timbered with Casnut Sugar tree  
 Oak Hickory & the hill is not steep  
 164...50 a small brook running East  
 172...43 an Elm 16" diam<sup>t</sup> - through low bottom in which  
 grows no timber much Rose & Bramble bushes  
 willow, Thorns, & plum bushes

West boundary of Township No. 9 Range No. 4 Contd.

North  
 181.06  
 191.70  
 200.00  
 211.04  
 22.00  
 35.89  
 45.00  
 47.92  
 49.75  
 56.00  
 72.00  
 70.14

a white oak 18" diam -  
 " Do. 20" Do.  
 Set Post corner to Sections No. 2 & 3 Town 9 Range 4 and 1 & 4 Town 9 Range 5 -  
 a white oak 3 feet diam - bears S 15° W 60 links of a sugar tree 8" diam - bears N 31° W 8 links  
 Marked per plan - the line for last 27 chains has run on East side of hill not steep soil good timber white oak black oak Hickory sugar tree brush Dogwood & Spice  
 2 1/2 Miles North  
 a white oak 16" diam -  
 to top of hill having continued rising from the corner obliquely land some what stony soil good timber white oak black oak Hickory & Dogwood & Spice  
 a white 2 feet diam -  
 Descending off hill for last 23 chains obliquely by bottom -  
 a black jack 10" diam -  
 a brook 20 links wide running East  
 through <sup>rich</sup> bottom for last 11 chains timber white & black oak sugar tree black ash Elm &c  
 a Maple 13" diam -  
 white oak 2 feet diam - land some what broken soil good white & black oak Hickory &c  
 Dogwood &c

# West boundary of Township No 9 Range No 4 Co

North

- 04..50 Rising hill obliquely on west side for last 17 chains
- 05..62 a white Oak 10" diam-
- 100..53 Hickory 16" diam Rich Land timber Walnut, Oak &c
- 110.. - a white Oak 15" diam on bank of small brook runs S
- 121..40 a Maple 10" diam Land broken but Rich for last 11 chains timber white Oak hickory & undergrowth open
- 125..50 ascend hill from last small brook
- 130.. - a white Oak 2 feet diam-
- 141..30 a Black Oak 26" D<sup>o</sup>
- 143..36 a D<sup>o</sup> 2 1/2 feet D<sup>o</sup>
- 149.. - small brook running west
- 166..66 a white Oak 13" diam-
- 173..42 a Hickory 14" D<sup>o</sup>
- 175..02 a white Oak 14" D<sup>o</sup> stony Land (= begins)
- 183..50 a small brook running NW at foot of hill with hollow
- 184..70 a sugar tree 12" diam-
- 190.. - to a branch of sugar creek 25 links wide running E
- 203..32 Intersected 26 links west of Post corner to Town -
- at 200.. Post corner to Towns 9 & 10 Range 5 - a white Oak 2 1/2 feet diam - S 47 E 14 links another white Oak 3 feet diam - N 64 E 60 links -