



THOMAS E. FERGUSON
 AUDITOR OF STATE
 COLUMBUS, OHIO 43216

DEPUTY AUDITORS:

JAMES A. BOLDEN
 Administration

RICHARD G. NUSS
 CPA
 Auditing Division

RUSSELL ROUCH
 Management Advising
 Service

CERTIFICATION

I, Thomas Aquinas Burke, Supervisor, Land Office of the Auditor of State, duly authorized to perform the duties of the Auditor of State prescribed in Section 115.21 of the Ohio Revised Code, hereby certifies that the enclosed field notes and plats are true copies taken from records in our office. These plats and field notes are for the following townships in the United States Military District:

1. Range 4, Townships 8, 9 and 10
2. Range 5, Townships 8, 9, and 10
3. Range 6, Townships 8, 9, and 10
4. Range 7, Townships 8, 9, and 10
5. Range 8, Townships 8 and 9
6. Range 9, Townships 8 and 9

and in the Ohio River Survey

1. Range 11, Townships 14 and 15
2. Range 12, Townships 14 and 15
3. Range 13, Townships 13 and 14
4. Range 14, Townships 17 and 18
5. Range 15, Townships 19 and 20

Witness my hand and seal of the Office of the Auditor of State, at Columbus, Ohio, this Twentieth-Nine day of November in the year of Our Lord Nineteen Hundred and Eighty-Three (1983).

Thomas Aquinas Burke
 Supervisor
 State Land Office



USMD
 R T
 4 9

Township 9, Range 4, U.S. Military District, Ohio. 43.

Monday, November 21, 1803.

Began at the South East corner of the Township, at which is a post from which a W. Oak 16 ins. diamt. bears N 63 W. 28 links distant, and a W. Oak 18 ins. diamt. bears S 10 W. 37 links distant; and ran

North, on First Mile, East Boundary of Section 21. Var. $0^{\circ} 55' E$.

1.42 To the corner of Townships 8 and 9 in Range 3.

1.50 A brook 5 links wide - course West.

12.44 A W. Oak 36 ins. diamt.

27.20 A W. Oak 40 ins. diamt.

28.00 A brook 2 links wide - course West.

45.50 A brook 6 links wide - course West.

52.65 A W. Oak 16 ins. diamt.

70.00 A new road.

80.00 Set post corner of Sections 20 and 21, from which a Spruce 16 ins. diamt. bears S 8 E. 9 links distant, and a Hickory 16 ins. diamt. bears N 5 E. 37 links distant.

Generally good level Oak land.

North, on Second Mile, East Boundary of Section 20.

10.00 A brook 5 links wide - course West.

16.80 A W. Oak 36 ins. diamt.

33.85 A Hickory 8 ins. diamt.

50.60 A W. Oak 24 ins. diamt.

59.10 A W. Oak 20 ins. diamt.

71.00 A Brook 5 links wide - course West.

80.00 Set post corner of Sections 11 and 20, from which a W. Oak 20 ins. diamt. bears S 62 E. 11 links distant, and a W. Oak 18 ins. diamt. bears N 26 W. 27 links distant.

The former part of this mile is good level Oak land -
The remainder, generally poor Oak land.

West, on First Mile, South Boundary of Section 21. Var. $0^{\circ} 50' E$.

16.50 A Maple 14 ins. diamt.

22.00 A creek 40 links wide - course North.

27.30 A W. Oak 36 ins. diamt.

ch. l. l.

40.00 A W. Oak 14 ins. diam. corner of half Sections 1 and 2 T. 8. R. 4, and half Sections 41 and 42, T. 9. R. 4, from which a W. Oak 17 ins. diam. bears S 85 E, 29 links dist. and a W. Oak 15 ins. diam. bears West, 68 links distant.

Level land. Timber, Oak, Hickory, Elm.

40.68 A W. Oak 15 ins. diam. [This distance is marked 0.68 in original].

48.00 A Creek 50 links wide - Course North.

52.00 A Creek 50 links wide. Course S. E.

56.50 A Creek 50 links wide. Course North.

65.69 A Hickory 12 ins. diam.

80.00 Set post corner of Sections 1 and 2, T. 8. R. 4 [and Sec. 21 and 22, T. 9. R. 4] from which a Cherry 12 ins. dia. bears S 58 W, 28 links distant, and a Blk. Jack 10 ins. diam. bears N 12 E, 61 links distant. [See 736 for this same corner].

Bottom land - Timber, Oak, Blk. Jack, Cherry &c

North, between Sections 21 and 22.

8.40 A W. Oak 16 ins. diam.

22.40 A Elm 6 ins. diam.

31.00 A Hickory 8 ins. diam.

56.25 A Hickory 6 ins. diam.

72.00 A brook 3 links wide - Course East.

80.00 Set Temporary Section post.

Level, good Oak land.

East, random, between Sections 20 and 21.

80.00 Fell 10 links North of the corner of Sections 20 and 21 in the Range line.

West, corrected, between Sections 20 and 21.

13.37 A W. Oak 6 ins. diam.

22.00 A Creek 60 links wide - Course North.

37.20 A Black Jack 12 ins. diam.

40.00 Set post corner of half sections 39, 40, 41, 42, from which a Hickory 16 ins. diam. bears S 52 W, 12 lks. distant, and an Elm 16 ins. diam. bears N 84 E, 26 links distant.

6th. 2nd.

- Bottom land. Timber, Oak, B. Jack, Elm, Cherry &c.
- 48.00 A W. Oak 14 ins. diam.
- 80.00 Set post corner of Sections 19, 20, 21, 22, from which a Double W. Oak ins. diam. bears N 65 E, 11 links distant, and a Gum 7 ins. diam. bears S 61 W, 19 links distant.
- Level land. Timber, Oak, B. Jack, Cherry &c.

North, between Sections 19 and 20.

- 17.80 A W. Oak 24 ins. diam.
- 36.73 An Aspen 12 ins. diam.
- 51.00 A brook 3 links wide. Course East.
- 52.40 A W. Oak 18 ins. diam.
- 60.00 A looped creek links wide.
- 67.50 A Creek 60 links wide - Course N. W.
- 73.00 A Creek 60 links wide - Course N. E.
- 80.00 Set Temporary Section post.
- Bottom land. Timber, Oak, Cherry, B. Jack, Thorn &c.

Tuesday, November 22, 1803.

West, on Second mile, South Boundary of Section 22.

- 1.00 A brook 15 links wide - Course S. E.
- 12.15 A W. Oak 24 ins. diam.
- 39.30 A W. Oak 17 ins. diam.
- 40.00 Set post corner of half Sections 43 and 44, T. 9, and half Sections 3 and 4, T. 8, R. 3, from which a W. Oak 30 ins. diam. bears N 15 E, 21 links distant, and a Fr. Oak 30 ins. diam. bears S 30 E, 37 links distant.
- Level land - part bottom - Timber, Oak, Hickory, Cherry &c.
- 52.69 A W. Oak 25 ins. diam.
- 64.80 A Maple 6 ins. diam.
- 72.00 A B. Oak 30 ins. diam.
- 80.00 To the corner of Sections 2 and 3 in T. 8, R. 4, [and of sections 22 and 23, T. 9, R. 4. Set post, from which a Fr. Oak 24 ins. diam. bears S 14 E, 31 links distant,

and a W. Oak 30 ins. diam., bears N 19 W, 40 links distant.

Level land. Timber, Oak, Dogwood &c

North, between Sections 22 and 23.

- 19.50 A W. Oak 12 ins. diam.
 27.50 A brook 10 links wide - Course East.
 39.50 An Aspen 14 ins. diam.
 44.50 A brook 3 links wide - Course S. E.
 60.90 A W. Oak 16 ins. diam.
 80.00 Set Temporary Section post.

Level, thin land. Timber, Oak, Dogwood &c.

West, on Third Mile, South Boundary of Section 23.

- 41.04 A W. Oak 18 ins. diam.
 12.74 A W. Oak 28 ins. diam.
 32.00 A. W. Oak 16 ins. diam.
 40.00 Set post corner of Half Sections 45 and 46, T. 9, R. 4, and half Sections 5 and 6, T. 8, R. 4, from which a W. Oak 18 ins. diam., bears S 76 W, 11 links distant, and a W. Oak 18 ins. diam., bears N 70 E, 61 links distant.

Good level Oak land.

- 43.00 Corner of Quarter Townships 3 and 4.
 43.50 A brook 4 links wide - Course North.
 62.50 A Chestnut 18 ins. diam.
 75.00 A brook 2 links wide - Course North.
 80.00 Set post corner of Sections 23 and 24, T. 9, and sections 3 and 4, T. 8, R. 4, from which a Maple 15 ins. diam., bears N 69 W, 11 links distant, and a Hickory 8 ins. diam., bears S 82 E, 20 links distant.

Good level Oak land.

North, between Sections 23 and 24.

- 4.50 A brook 4 links wide - Course East.
 18.29 A B. Oak 24 ins. diam.
 43.00 A brook 6 links wide - Course East.

Chs. Chl.

47.00 A brook 3 links wide - course East.

48.00 A Maple 14 ins. diam.

80.00 Set post corner of Sections 17, 18, 23, 24, from which a Hickory 6 ins. diam. bears N 15 W, 10 links distant, and a Hickory 9 ins. diam. bears S 34 E, 27 links distant.
Level land - Good soil - Timber, Oak, Hickory, Dogwood &c.

East, on random line between Sections 18 and 23.

80.25 Sell 15 links South of the post.

East, on random line, between Sections 19 and 22.

80.30 Sell 10 links North of the corner.

West, connected, between Sections 19 and 22.

7.75 A W. Oak 16 ins. diam.

40.15 Set post corner of half Sections 37, 38, 43, 44, from which a W. Oak 10 ins. diam. bears S 38 W, 19 lks. distant, and a W. Oak 13 ins. diam. bears N 38 E, 50 links distant.
Good Oak land.

50.50 A brook 2 links wide - course North.

58.64 A W. Oak 36 ins. diam.

72.00 A W. Oak 18 ins. diam.

80.30 Set post corner of Sections 18, 19, 22, 23, from which a W. Oak 18 ins. diam. bears N 32 W, 18 links distant, and a W. Oak 16 ins. diam. bears S 66 E, 24 lks. distant.

Generally good Oak land.

North, between Sections 18 and 19.

12.35 A W. Oak 12 ins. diam.

24.60 A W. Oak 30 ins. diam.

42.30 A Hickory 15 ins. diam.

55.00 A brook 10 links wide - course East.

68.40 A W. Oak 30 ins. diam.

80.00 Set Temporary Section post.

Pretty good Oak land.

Chs. Lks.

- West, corrected, between Sections 18 and 23.
- 13.50 A brook 2 links wide - course South.
- 30.00 A Hickory 10 ins. diam.
- 33.00 A brook 2 links wide - course South.
- 40.12 Set post corner of half Sections 35, 36, 45, 46, from which a Hickory 8 ins. diam. bears N 30 W, 3 lks. distant and a Hickory 12 ins. diam. bears S 30 E, 19 lks. distant.
Good level Oak land.
- 44.35 A W. Oak 30 ins. diam.
- 75.00 A W. Oak 18 ins. diam.
- 76.00 A brook 2 links wide - course South.
- 79.00 A brook 2 links wide - course South.
- 80.25 To the corner of Sections 17, 18, 23, 24, before established.
Level Oak land - Poor soil.

North, between Sections 17 and 18.

- 28.00 A Chestnut 14 ins. diam.
- 37.00 A brook 2 links wide - course East.
- 52.90 A B. Oak 24 ins. diam.
- 60.70 A B. Oak 24 ins. diam.
- 80.00 Set Temporary Section post.
Level land - poor soil - Timber, Oak, Chestnut, Dogwood, etc.

Wednesday, November 23, 1805.

West, on Fourth Mile, South Boundary of Section 24.

- 24.65 A Chestnut 48 ins. diam.
- 30.95 A W. Oak 15 ins. diam.
- 40.00 Set post corner of half Sections 47 and 48 T. G. and half Sections 7 and 8, T. 8, R. 4, from which, a Chestnut 13 ins. diam. bears N 57 W, 19 lks. distant and a B. Oak 36 ins. diam. bears East, 26 lks. distant.
Level land - good soil - Timber, Oak, Hickory &c.
- 48.93 A W. Oak 16 ins. diam.
- 61.50 A W. Oak 16 ins. diam.
- 68.75 A Chestnut 40 ins. diam.

Chs. 1st

80.00 To the corner of Sections 4 and 5 in T. 8 [and Sections 24 and 25, T. 9, R. 4] from which a Chestnut 36 ins. diamt. bears East, 20 links distant, and a Hickory 6 ins. diamt. bears N 41 W. 26 links distant.
Level, good Oak land.

North, between Sections 24 and 25.

18.68 A B. Oak 16 ins. diamt.

45.95 A B. Oak 24 ins. diamt.

72.60 A W. Oak 15 ins. diamt.

79.50 A brook 3 links wide - Course N. E.

80.00 Set post corner of Sections 16, 17, 24, 25, from which a Hickory 15 ins. diamt. bears N 21 E, 6 links distant, and a W. Oak 8 ins. diamt. bears S 42 W, 17 links distant.
Level land - rich soil - Timber, Oak, Hickory &c

East, on random line, between Sections 17 and 24.

80.30 Fell 6 links North of the corner.

West, corrected, between Sections 17 and 24.

15.16 A W. Oak 32 ins. diamt.

19.38 A W. Oak 16 ins. diamt.

35.00 A Hickory 9 ins. diamt.

40.15 Set post corner of half sections 33, 34, 47, 48, from which a Hickory 12 ins. diamt. bears S 45 E, 31 lks. distant, and a Hickory 12 ins. diamt. bears N 56 W, 32 lks. distant.

Good level Oak land.

50.38 A W. Oak 18 ins. diamt.

61.25 A W. Oak 24 ins. diamt.

66.50 A brook 3 links wide - Course NW.

79.00 A brook 3 links wide - Course North.

80.30 To the corner -

Generally good Oak land.

North, between Sections 16 and 17.

11.60 An Elm 18 ins. diamt.

Chp. Skl.

- 19.50 A brook 4 links wide - course N. W.
 26.00 A Maple 24 ins. diam.
 44.00 An Ash 12 ins. diam.
 58.60 A brook 30 links wide - course East.
 80.00 Set Temporary Section post.

Three fourths of this mile is rich Bottom land -
 Timber, Ash, Elm &c.

West, on Fifth Mile, South Boundary, of Section 25.

- 9.00 A W. Oak 14 ins. diam.
 31.60 A W. Oak 18 ins. diam.
 40.00 Set post corner of half Sections 49 and 50, T. 9. R. 4,
 and half Sections 9 and 10, T. 8. R. 4, from which
 a Hickory 12 ins. diam. bears S 16 W. 10 links distant,
 and a Hickory 7 ins. diam. bears N 26 E. 13 links distant.

Good level Oak land.

- 40.50 A brook 3 links wide - course North.
 58.80 A W. Oak 12 ins. diam.
 60.50 A brook 3 links wide - course North.
 69.00 A brook 2 links wide - course North.
 74.00 A hicknut 30 ins. diam.
 86.00 To the S. W. corner of the Township. The post is
 already established - hilly land - Good soil - Timber, Oak, Hickory &c.

North, on First Mile, West Boundary, of Section 25.

- 12.70 A Hickory 10 ins. diam.
 42.15 A W. Oak 30 ins. diam.
 46.30 A Hickory 30 ins. diam.
 59.55 A R. Oak 30 ins. diam.
 79.20 Buckingham's corner.
 80.00 Set post corner of Sections 16 and 25, from which a
 Hickory 7 ins. diam. bears N 29 W. 11 links distant,
 and a Hickory 14 ins. diam. bears S 56 E. 31 links distant.

Level land - Good soil - Timber, Oak, Hickory

&c.

ch^d lks

East, on random line, between Sections 16 and 25.
86.00 Fell 10 links north of the corner.

West, connected, between Sections 16 and 25.
20.00 A brook 2 links wide - Course S. W.
22.75 A Sugar 24 ins. diam.
24.00 A brook 3 links wide - Course North.
40.00 Set post corner of half Sections 31, 32, 49, 50, from
which a W. Oak 16 ins. diam., bears N 56 W, 13 lks. distant,
and a Ch. Oak 15 ins. diam., bears S 27 E, 24 lks. distant.
Good land - Timber, Oak, Hickory &c.
56.50 A brook 5 links wide - Course North.
58.90 A Cherry 12 ins. diam. — 72.80 A Cherry 12 ins. diam.
86.00 To the corner.
Rich level land. Timber, Oak, Hickory, Cherry &c.

North, on Second Mile, West Boundary of Section 16.
6.00 A brook 20 links wide - Course East.
30.30 An Ash 12 ins. diam.
34.00 A brook 3 links wide - Course S. E.
43.35 A Hickory 12 ins. diam.
80.00 Set post corner of Sections 15 and 16, from which, a
W. Oak 15 ins. diam., bears S 15 W, 4 links distant, and
a Hickory 8 ins. diam., bears North, 17 links distant.
One half of this mile is good bottom - Timber, Oak,
Ash, Sugar &c. The remainder is hilly Oak land.

North, on Third Mile, West Boundary of Section 15.
.30 Buckingham's corner.
3.00 A brook 10 links wide - Course East.
23.30 A W. Oak 30 ins. diam.
42.25 Quarter Township corner.
78.60 A W. Oak 30 ins. diam.
80.00 Set Temporary Mile post.
One third of this mile is rich land. Timber, Ash, Sugar,
Hickory - Remainder, hilly Oak land.

Chk. Lks.

East, on Random line, between Sections 15 and 16.
86.00 Fell 10 links North of the corner.

East, on random line, between Sections 14 and 17.
80.00 Fell 8 links North of the corner.

East, on random line, between Sections 13 and 18.
80.00 To the corner.

East, on random line, between Sections 12 and 19.
80.30 Fell 20 links South of the corner.

East, on random line, between Sections 11 and 20.
80.00 Fell 5 links South of the corner.

North, on Third mile, East Boundary of Section 11.

3.17 A B. Oak 20 ins. diamt.

18.68 A W. Oak 30 ins. diamt.

25.00 A brook 3 links wide. Course S. W.

45.50 Set post corner of Quarter Townships 1 and 4, from which a W. Oak 16 ins. diamt. bears S 4 W. 21 links distant, and a W. Oak 8 ins. diamt. bears N 60 E. 26 links distant.

Generally pretty good Oak land.

Thursday, November 24, 1803

West, between Sections 11 and 20, on true line.

12.00 A brook 3 links wide - Course South.

17.00 A brook 2 links wide - Course South.

23.40 A W. Oak 18 ins. diamt.

40.00 Set post corner of half Sections 21, 22, 39, 40, from which a W. Oak 18 ins. diamt. bears S 27 W. 6 lks. distant, and a W. Oak 24 ins. diamt. bears N 22 E. 33 lks. distant.

Poor hilly white Oak land.

46.00 A brook 6 links wide - Course N. W. kept down it.

55.00 Left brook to the right.

old 111

- 64.60 A maple 16 ins. diam.
 74.50 A brook 60 links wide - course North.
 80.00 Set post corner of Sections 11, 12, 19, 20, from which a
 W. Oak 10 ins. diam. bears N 80 E, 37 links distant, and
 a Hickory 12 ins. diam. bears N 55 W, 50 links distant.
 Brushy bottom. Timber, Oak, Thorn &c

North, between Sections 11 and 12.

- 4.50 A brook 10 links wide - course East.
 27.67 A W. Oak 12 ins. diam.
 40.00 Set Temporary half mile post.
 Level White Oak land.

Creek between Sections 12 and 19, on true line.

- 4.50 A brook 10 links wide - course North East.
 6.00 A brook 10 links wide - course S. E.
 19.50 A W. Oak 12 ins. diam.
 28.00 A brook 10 links wide - course N. E.
 40.15 Set post corner of half Sections 23, 24, 37, 38, from
 which a W. Oak 9 ins. diam. bears N 6 W, 6 links distant,
 and a W. Oak 9 ins. diam. bears S 6 W, 26 links distant.
 Brushy bottom. Timber, Oak, Crab Apple &c
 50.15 A Hickory 12 ins. diam.
 53.00 A brook 3 links wide - course South.
 66.25 A W. Oak 30 ins. diam.
 80.30 Set post corner of Sections 12, 13, 18, 19, from which a
 W. Oak 16 ins. diam. bears South, 16 links distant, and a
 B. Oak 14 ins. diam. bears N 16 W, 23 links distant.
 Level land. Timber, Oak, Hickory &c

North, between Sections 12 and 13.

- 19.50 A brook 2 links wide - course East.
 21.60 A Hickory 14 ins. diam.
 39.25 A Chestnut 40 ins. diam.
 40.00 Set Temporary half mile post.
 Hilly, poor, Oak land.

Ch^o 1k^o

- West, between Sections 13 and 18, on true line.
- 22.25 A R. Oak 28 ins. diam.
- 28.00 A brook 2 links wide - Course South.
- 39.50 A brook 4 links wide - Course S. E.
- 40.00 Set post corner of half Sections 25, 26, 35, 36, from which a W. Oak 14 ins. diam. bears S 85 W, 24 lks. distant and a R. Oak 36 ins. diam. bears N 60 E, 18 links distant.
- Generally poor Oak land.
- 44.30 A R. Oak 24 ins. diam.
- 63.40 A Hickory 18 ins. diam.
- 80.00 Set post corner of Sections 13, 14, 17, 18, from which a W. Oak 16 ins. diam. bears S 75 W, 25 links distant, and a W. Oak 8 ins. diam. bears N 88 E, 44 links distant.
- Generally good Oak land.

North, between Sections 13 and 14.

- 8.79 A R. Oak 16 ins. diam.
- 26.68 A R. Oak 30 ins. diam.
- 63.75 A R. Oak 24 ins. diam.
- 80.00 Set Temporary Section post.
- Level good Oak land.

West, between Sections 14 and 17, on true line.

- 17.30 A W. Oak 20 ins. diam.
- 25.00 A brook 2 links wide - Course North.
- 27.00 A Double Maple ins. diam.
- 40.00 Set post corner of half Sections 27, 28, 33, 34, from which a W. Oak 16 ins. diam. bears S 77 W, 12 lks. distant, and a Hickory 14 ins. diam. bears N 83 E, 18 lks. distant.
- Shilly, stony, poor land. Timber, Oak, Dogwood &c.
- 57.00 A creek 40 links wide - Course N. E.
- 59.90 An Elm 16 ins. diam.
- 80.00 Set post corner of Sections 14, 15, 16, 17, from which a Gum 10 ins. diam. bears S 18 E, 20 links distant, and a Hickory 7 ins. diam. bears N 72 W, 17 links distant.
- One half, rich bottom - The remainder, Shilly, stony

Chs lks

land. Timber, Oak, Hickory &c

North, between Sections 14 and 15.

- 8.34 A W. Oak 18 ins. diam.
- 27.50 A brook 3 links wide - course East.
- 28.60 A Hickory 10 ins. diam.
- 40.60 A R. Oak 36 ins. diam.
- 80.00 Set Temporary Section post.
10 chains of this mile, rich Sugar land - The remainder, thin Oak land.

West, between Sections 15 and 16, on true line.

- 18.00 A Sugar 12 ins. diam.
- 38.00 A W. Oak 30 ins. diam.
- 40.00 Set post corner of half sections 29, 30, 31, 32, from which a Maple 15 ins. diam. bears S 83 E, 13 links distant, and a Maple 12 ins. diam. bears N 42 W, 18 links distant.
Rich land. Timber, Oak, Sugar, Hickory &c
- 58.00 A brook 15 links wide - course South East.
- 65.54 A W. Oak 16 ins. diam.
- 82.68 A W. Oak 16 ins. diam.
- 86.00 To the corner of Sections 15 and 16.
Good bottom land. Timber, Oak, Elm, Hickory, Sugar.

East. from the corner of Quarter Townships 2 and 3, on random line, through the Township - Var. 0° 50' E.

Miles. Chains. Links.

2. 40.00 Set Temporary Centre post.

Continued, on Friday, November 25, 1803.

Miles. Chains. Links.

5. 06.00 To the corner of Quarter Townships 1 and 4, and fell 3.25 chains South of the corner.

West. on the North Boundary of [Fractional] Section 11 -
Variation, 1° 17' East.

- 18.15 A Hickory 12 ins. diam.
- 32.06 A W. Oak 24 ins. diam.

Chas. S. H.

40.00 Set post corner of [Fractional] half Sections 21 and 22, from which a W. Oak 18 ins. diamt. bears N 56 E, 49 lks. distant, and a W. Oak 18 ins. diamt. bears N 74 W, 52 lks distant.

Pretty good Oak land.

56.00 A Black Jack 12 ins. diamt.

64.00 A brook 60 links wide course North.

80.00 An Ironwood 3 ins. diamt. corner of Sections 11 and 12, from which a W. Oak 17 ins. diamt. bears S 29 W, 14 links distant, and a Walnut 9 ins. diamt. bears N 37 E, 27 links distant.

Continued the North line [between Sections 11 and 12] 4.75 lks. further North.

Good bottom land. Timber, Oak sugar, Ash &c.

West, on North Boundary of [Fractional] Section 12.

23.30 A R. Oak 24 ins. diamt.

27.85 A Hickory 15 ins. diamt.

40.00 Set post corner of [fractional] half Sections 23 and 24, from which a W. Oak 30 ins. diamt. bears N 86 W, 35 links distant, and a W. Oak 3 ins. diamt. bears S 73 E, 47 links distant.

Good level Oak land.

61.44 A R. Oak 9 ins. diamt.

73.27 A W. Oak 15 ins. diamt.

80.00 Set post corner of Sections 12 and 13, from which a Hickory 10 ins. diamt. bears S 84 W, 11 links distant, and a Chestnut 14 ins. diamt. bears S 78 E, 43 lks. distant.

Continued the North line [between Sections 12 and 13] 4.10 lks. further. — Good level Oak land.

West, on North Boundary of Section 13.

16.39 A R. Oak 18 ins. diamt.

27.60 A Hickory 14 ins. diamt.

40.00 Set post corner of half Sections 25 and 26, from which a W. Oak 16 ins. diamt. bears S 31 E, 26 links distant,

Chs. lks.

and a W. Oak 16 ins. diam. bears N 50 W. 44 links distant.
 Good level Oak land.

North, from the corner of Quarter Townships 3 and 4, on
 random line through the Township. Variation 0° 55' E.

Miles - Chains - Links.

5. 08. 50 Set 50 links East of the corner of Quarter Townships
 1 and 2. Set post, from which a W. Oak 34 ins. diam.
 bears S 30 E, 78 lks. distant, and a R. Oak 18 ins. diam.
 bears N 59 W. 63 links distant.

West, (Continued), from the corner of half Sections 25 and 26.

3. 25 Set post [corner of Quarter Townships 1, 2, 3, 4] from
 which a B. Oak 9 ins. diam. bears N 10 W. 33 links dist.,
 and a W. Oak 16 ins. diam. bears S 18 E, 57 links distant.

North, on East Boundary of Half Section 26. Var. 5° 00' E.

21. 10 A Chestnut 36 ins. diam.

33. 15 A B. Oak 12 ins. diam.

36. 15 Set post corner of half Sections 15 and 26, from which
 a B. Oak 18 ins. diam. bears East, 37 links distant, and
 a B. Oak 18 ins. diam. bears N 55 W. 38 links distant.

Level, good Oak land.

North, on East Boundary of Half Section 15.

11. 75 A W. Oak 18 ins. diam.

28. 00 A W. Oak 14 ins. diam.

45. 00 A Hickory 12 ins. diam.

74. 80 A Chestnut 50 ins. diam.

80. 00 Set post corner of half Sections 6 and 15, from which a
 Hickory 4 ins. diam. bears N 74 E, 6 links distant, and a
 Hickory 6 ins. diam. bears S 59 W, 11 links distant.

Level, poor Oak land.

North, on East Boundary of half Section 6.

26. 30 A W. Oak 30 ins. diam.

46. 00 A Sugar 9 ins. diam.

Ch^l Lks.

- 48.50 A brook 50 links wide - course N.E.
 63.20 A R. Oak 30 ins. diam.
 70.00 A brook 3 links wide - Course East.
 88.50 To the corner of (fractional) section 3.

One half of this mile is good bottom - Timber, Beech, Sugar &c. The remainder, hilly oak land.

West, between sections 8 and 13.

- 11.14 A Hickory 10 ins. diam.
 21.60 A W. Oak 18 ins. diam.
 37.00 Set post corner of sections 13 and 14, from which a Hickory 18 ins. diam. bears S 17 E, 10 links distant, and a B. Oak 8 ins. diam. bears N 17 W, 30 links distant.
 Level land. Timber, Oak, Hickory &c.

West, continued, from the corner of sections 13 and 14.

- 3.00 Set post corner of sections 7 and 8, from which a Gum 14 ins. diam. bears S 33 W, 16 links distant, and a W. Oak 24 ins. diam. bears N 2 W, 33 links distant.

North, between sections 7 and 8.

- 14.85 A W. Oak 18 ins. diam.
 21.00 A brook 3 links wide - course West.
 37.00 A brook 4 links wide - Course West.
 44.50 A Sugar 16 ins. diam.
 67.00 A Looped Creek, links wide.
 73.00 A Creek 50 links wide - Course N.E.
 80.00 Set Temporary Section post.
 Part hilly land, and part rich bottom. Timber, Oak, Sugar, Hickory &c.

West, between sections 7 and 14.

- 14.07 A R. Oak 30 ins. diam.
 27.50 A Maple 12 ins. diam.
 37.00 Set post corner of half sections 27 and 28, from which a Beech 12 ins. diam. bears North, 3 links distant.

Chs. 562

and a Sugar 14 ins. diamt. bears East, 11 links distant.

Generally good land - Timber, Oak, Hickory &c.

38.00 A Creek 50 links wide - Course North.

40.00 Set post corner of half sections 13 and 14, from which
a Beech 24 ins. diamt. bears S W, 26 links distant,
and a Beech 16 ins. diamt. bears N 44 E, 53 links distant.

49.47 A Hickory 12 ins. diamt.

72.00 A Walnut 36 ins. diamt.

77.00 Set post corner of Sections 14 and 15, from which, an
Ironwood 7 ins. diamt. bears N 60 E, 22 links distant,
and an Ironwood 8 ins. diamt. bears S 82 W, 29 links
distant.80.00 Set post corner of Sections 6 and 7, from which, a
Sugar 17 ins. diamt. bears N 45 W, 19 links distant, and
a Hickory 12 ins. diamt. bears S 34 E, 55 lks. distant.

Rich Bottom land. Timber, Sugar, Walnut, Ash.

North, between Sections 6 and 7.

10.00 A brook 15 links wide - Course East.

14.73 A W. Oak 30 ins. diamt.

39.48 A W. Oak 18 ins. diamt.

63.40 A Maple 7 ins. diamt.

71.50 A brook 3 links wide - Course East.

80.00 Set Temporary Section post.

Hilly land - rich soil - Timber, Oak, Sugar, Hickory

&c.

West, between Sections 6 and 15.

14.38 A Hickory 12 ins. diamt.

16.50 A brook 2 links wide - Course North.

37.00 Set post corner of half sections 29 and 30, from which a
W. Oak 15 ins. diamt. bears N 80 E, 29 links distant, and a
W. Oak 15 ins. diamt. bears S 43 W, 30 links distant.40.00 Set post corner of half sections 11 and 12, from which a
Hickory 6 ins. diamt. bears S 7 W, 6 links distant, and a
W. Oak 6 ins. diamt. bears N 27 E, 26 links distant.

chk. Lk.

Level, rich land. Timber, Oak, Sugar, Hickory &c.

47.50 A brook 2 links wide - Course North

49.35 An Ash 16 ins. diam.

62.33 A W. Oak 24 ins. diam.

83.00 Set post in Range line, corner of Sections 6 and 15, from which a W. Oak 18 ins. diam., bears S 58 E, 12 links distant, and a W. Oak 15 ins. diam., bears N 89 W, 30 lks. distant.

Sloping ground, and stony. Timber, Oak, Dogwood &c.

North, on Fourth Mile. West Boundary, of Section 6.

11.64 A R. Oak 24 ins. diam.

12.50 A brook 10 links wide - Course East.

36.00 A Maple 15 ins. diam.

50.00 A W. Oak 24 ins. diam.

67.50 A brook 3 links wide - Course S. E.

74.60 A W. Oak 18 ins. diam.

80.00 Set post corner of Sections 5 and 6, from which, a W. Oak 30 ins. diam., bears S 65 E, 7 links distant, and a Maple 12 ins. diam., bears N 47 W, 27 lks. distant.

Hilly land - rich soil - Timber, Oak, Sugar, Hickory etc.

East, on random line, between Sections 5 and 6.

83.00 Fell 5 links South of the corner.

East, on random line, between Sections 4 and 7.

80.25 Fell 25 links South of the corner.

East, on random line, between Sections 3 and 8.

39.90 Fell 10 links South of the corner.

West, connected, between Sections 3 and 8.

10.30 A W. Oak 20 ins. diam.

30.00 A Maple 12 ins. diam.

35.00 A brook 50 links wide - Course North.

39.90 Set post corner of Sections 3, 4, 7, 8, from which an

ch. Lks.

Nash 16 ins. diam. bears S 40 E, 10 links distant, and an Elm 13 ins. diam. bears N 40 W, 44 links distant.

Willy, stony, poor land - Lumber, Oak, Dogwood &c

North, between sections 3 and 4.

17.90 A W. Oak 36 ins. diam.

38.10 A W. Oak 36 ins. diam.

44.00 A brook 6 links wide - Course East

65.50 A W. Oak 30 ins. diam.

78.00 A brook 3 links wide - Course East.

88.75 Set post in Township line, corner of sections 3 and 4, from which a Hickory 12 ins. diam. bears S 69 W, 6 links distant, and a Hickory 6 ins. diam. bears N 1 E, 17 links distant.

Willy stony land - Lumber, Oak, Dogwood &c

West, on North Boundary of Section 3.

7.00 A brook 2 links wide - Course South.

12.80 A W. Oak 30 ins. diam.

35.30 A W. Oak 18 ins. diam.

39.75 To the corner of sections 3 and 4.

Willy, poor land. Lumber, Oak, Dogwood &c

West, on North Boundary of Section 4.

13.50 A W. Oak 18 ins. diam.

27.40 A W. Oak 24 ins. diam.

40.00 Set post corner of half sections 7 and 8, from which a Maple 12 ins. diam. bears N 61 E, 10 links distant, and a Maple 13 ins. diam. bears S 74 W, 14 links distant.

Willy, poor Oak land.

57.00 A W. Oak 30 ins. diam.

65.00 A W. Oak 36 ins. diam.

80.25 Set post corner of sections 4 and 5, from which a Gum 12 ins. diam. bears N 85 E, 47 links distant, and a Fr. Oak 18 ins. diam. bears N 87 W, 47 links distant.

Willy poor Oak land.

Chs. 1st.

- West, between Sections 4 and 7.
 14.00 An Elm 8 ins. diam.
 22.00 A brook 3 links wide - Course S. E.
 40.12 Set post corner of half Sections 7, 8, 13, 14, from which
 a Fr. Oak 10 ins. diam., bears S 12 W, 20 links distant, and
 a Fr. Oak 14 ins. diam., bears N 43 E, 30 links distant.
 Rich land & level. Timber, Oak, Sugar, Elm, Ash &c.
 54.40 A Sugar 12 ins. diam.
 68.00 A Maple 14 ins. diam.
 70.00 A brook 8 links wide - Course S. E.
 80.25 Set post corner of Sections 4, 5, 6, 7, from which a Fr. Oak
 18 ins. diam., bears S 65 W, 22 links distant, and a Maple 14
 ins. diam., bears N 63 E, 34 links distant.
 Level, rich land. Timber, Oak, Sugar &c.

- North, between Sections 4 and 5.
 5.50 A brook 8 links wide - Course East.
 7.83 A Sugar 16 ins. diam.
 34.18 A W. Oak 16 ins. diam.
 55.70 A Chestnut 30 ins. diam.
 89.00 To the corner of Sections 4 and 5.
 Poor hilly Oak land

- West, between Sections 5 and 6.
 19.74 A W. Oak 30 ins. diam.
 40.00 Set post corner of half Sections 9, 10, 11, 12, from which a
 Hickory 8 ins. diam., bears S 81 E, 11 links distant, and a
 Fr. Oak 7 ins. diam., bears S 64 W, 35 links distant.
 Poor Oak land.
 61.10 A W. Oak 30 ins. diam.
 66.00 A brook 3 links wide - Course South
 75.50 A W. Oak 24 ins. diam.
 83.00 To the corner of Sections 5 and 6.
 Hilly land - Rich soil - Timber, Oak, Hickory
 etc.

chs. lbs.

North, on Fifth Mile, West Boundary, of Section 5.

- 14.75 A W. Oak 34 ins. diamt.
 28.25 A B. Oak 36 ins. diamt.
 34.00 A Spring 2 links wide Course West.
 60.45 A W. Oak 18 ins. diamt.
 76.00 A brook 20 links wide - Course East.
 89.55 Corner of Townships 9 and 10 in Range 5.
 89.25 Set post corner of Townships 9 and 10 in Range 4, from
 which a Maple 24 ins. diamt. bears N 5 W. 31 links distant,
 and a W. Oak 18 ins. diamt. bears S 28 E, 40 links distant.
 Part hilly Oak land, and part rich Sugar Bottom.

West, on Fifth mile, North Boundary of Section 5.

- 5.15 A W. Oak 24 ins. diamt.
 29.46 A Gum 15 ins. diamt.
 40.00 Set post corner of half Sections 9 and 10. From which a
 W. Oak 36 ins. diamt. bears S 45 E. 9 links distant, and a
 W. Oak 30 ins. diamt. bears N 57 W. 49 links distant.
 Stony land - Timber, Oak, Maple &c.
 44.97 A Sugar 24 ins. diamt.
 65.00 A brook 20 links wide - Course N. E.
 67.30 A Sugar 18 ins. diamt.
 88.00 To the North West Corner of the Township.

Rich Bottom land - Timber, Sugar, Ash, Elm &c.

Surveyed in the year 1803, by

Alexander Holmes,

Deputy Surveyor.