



THOMAS E. FERGUSON
 AUDITOR OF STATE
 COLUMBUS, OHIO 43216

DEPUTY AUDITORS:

JAMES A. BOLDEN
 Administration

RICHARD G. NUSS
 CPA
 Auditing Division

RUSSELL ROUCH
 Management Advising
 Service

CERTIFICATION

I, Thomas Aquinas Burke, Supervisor, Land Office of the Auditor of State, duly authorized to perform the duties of the Auditor of State prescribed in Section 115.21 of the Ohio Revised Code, hereby certifies that the enclosed field notes and plats are true copies taken from records in our office. These plats and field notes are for the following townships in the United States Military District:

1. Range 4, Townships 8, 9 and 10
 2. Range 5, Townships 8, 9, and 10
 3. Range 6, Townships 8, 9, and 10
 4. Range 7, Townships 8, 9, and 10
 5. Range 8, Townships 8 and 9
 6. Range 9, Townships 8 and 9
- and in the Ohio River Survey
1. Range 11, Townships 14 and 15
 2. Range 12, Townships 14 and 15
 3. Range 13, Townships 13 and 14
 4. Range 14, Townships 17 and 18
 5. Range 15, Townships 19 and 20

Witness my hand and seal of the Office of the Auditor of State, at Columbus, Ohio, this Twentieth-Nine day of November in the year of Our Lord Nineteen Hundred and Eighty-Three (1983).

Thomas Aquinas Burke
 Supervisor
 State Land Office



US MD
 R T
 5 9

West boundary of Township No. 9 Range No. 5 -

- North From the South ^(east) corner of Town 9 Range 6 Run Nor
- 12..61 a white Oak 14" diam^d
- 17..63 a Do 13" Do good Land from the corner
timber white Oak cherry Plum & thorn
- 20.. - a white Oak 2 feet diam^d
- 31.. - descending off of ridge for last 4 chains
- 36..50 a Brook 10 links wide running west through bottom for
last 5 chains covered with thorn plum &
- 39..54 a Black Jack 14" diam^d
- 50.. - rising hill for last 11 chains Land stony
- 53..87 a white Oak 3 1/2 feet diam^d
- 74..50 good Land for last 24 chains timber white Oak Black
Oak Hickory & some Oak & hickory brush
- 77..40 a white Oak 2 1/2 feet diam^d - Land still rich
- 83..50 Descending hill for last 10 chains not steep Land Rich
- 87.. - over Brook running west 10 links wide
- 97..71 forked white Oak 2 feet diam^d
- 107.. - a Do 14" Do rising hill for last 20
the ascent easy soil good timber principally with white
- 123..11 a Sugar tree 14" diam^d - descend Hill obliquely for last 16
Land and timber as last described
- 124.. - Brook 10 links wide running west
- 140..02 a white Oak 18" diam^d - rising hill obliquely for last
24 chains Land stony timber white Oak Black Oak
Hickory some Chestnut &
- 185..94 a hickory 15" diam^d
- 194..50 small brook running west descending off of hill
obliquely for last 25 N. Land stony but Rich

West boundary of Township No. 9 Range No. 5 - Contin

North	
197.50	Over a brook 10 links wide running S W
200. -	Set Post corner to sections No. 2 & 3 Town 9 Range 5 - and 1 & 4 Town 9 Range 6 - a White Oak 3 feet diam. - bears S 16.30 W 4.1 links - and D. 16 diam. bears N 26 E 57 links Rising hill from last brook -
2 1/2 Miles North	
6. 2	
8. 59	a Black Oak 17 diam.
23. -	a D. 15 D.
39. 75	a Chestnut 20 D.
46. 91	a D. 2 1/2 feet D.
50. 04	a Sugar tree 15 diam.
64. 00	a small brook running N 20 W
68. 20	a Brook 15 links wide running west
76. 50	Enter marsh covered with grass flag & pin willows
87. -	Enter a grove of aspen Spruce & Cherry tree
99. 50	through marsh into good bottom land
108. 50	a small brook running S 20 W
114. 35	a White Oak 12 diam. - Bottom good timber Black Oak White Oak app. S E
116. 40	a White Oak 14 diam. - good upland for last 3 chains
129. -	a D. 14 D.
142. 54	a D. 15 D.
150. 82	a D. 17 D.
168. 85	a D. 30 D. through marsh 6 ft wide
180. 90	through marshy swamp 5 ft wide much grass willow elder flag S E

West boundary of Township No. 9 Range No. 5 - Corn

North	
188.05	Through another marsh 4.50 ^u wide
190.25	a white Oak 14" diam -
200.00	Set Post for corner of Towns 8 & 10 Ranges 5 & 9 a white Oak 16" diam - bears S 17° 30' W 13 links another white Oak 14" diam - bears N 48° E 13 links Marked per plan - Note - This post stands 1.50 th North of end of 5 Miles & 1.26 South of point of Intersection - E - Surveyed June 19 th 1790

North boundary of Township No. 9 Range No. 5

From Post at the Northeast corner of T9 and South
West of Town 10 Range 5 - Run West

3.50	a white Oak 2 feet diam -
7.60	" " 19 ⁱⁿ " 8 ^o
15.20	a small brook running S & E
10.85	a Red Oak 15" diam -
28.45	Rising hill for last 14 chains to top a black Oak 20" diam - Land rocky & stony
41.60	a Hickory 14" diam - Land good last 14 chains
53.35	a white Oak 14" diam -
54.60	a small brook running south at foot of hill having descended for last 10 chains Land stony
57.20	White Oak 2 1/2 feet diam -
57.70	a small brook running S - E -
65.52	Red Oak 14" diam -
73.59	Black Oak 2 feet diam - ascending hill for last 9 ch
84.74	a white Oak 2 feet diam -

North boundary of Township No. 9 Range No. 5. Cont.

West

- 92..40 a spring running south, for last 9 chains the land stony
- 96..00 a bush 12" diam.
- 96..90 a spring running S 20° W
- 104..15 a brook 15 links wide running S. E. - Land good last 7 ch
- 119..20 Black Walnut 14" diam. - Rich Land
- 130.. - Rising Hill obliquely to top from last brook
- 136..05 a white Oak 16" diam.
- 152..25 a small brook running S. E. at foot of a hill bearing
around for last 22 chains obliquely Land stony
& broken - white Oak Black Oak Hickory &
- 154..50 a white Oak 3 feet diam.
- 170.. - a thicket for last 10 chains fire having destroyed
the timber Land poor & stony
- 177..57 a white Oak 18" diam.
- 178.. - a small brook running S. E.
- 196.. - Hickory 13" diam.
- 197..44 a white Oak 10" diam.
- 200.. - Set Post Corner to Sections No. 1 & 2 Town 9 and
3 & 4 Town 10 Range 5 - a Chestnut 2 feet diam
bears S 5° W 60 links and a Black Oak 16" diam.
bears N 22° E 38 links Marked per plan
good Land & level enough for cultivation
white Oak Black Oak Hickory &
- 2 1/2 Miles West
- 12..72 a white Oak 17" diam.
- 24..60 a D. 10" D.
- 33..06 a Chestnut 2 feet D.

North boundary of Township N^o 9 Range N^o 5 - Co.

West -	
46 ^u 66	a Red Oak 2 1/2 feet diam -
60 ^u 43	a White Oak 18 ^u diam -
69 ^u 17	a D ^o 14 ^u D ^o
70 ^u 10	a D ^o 20 ^u D ^o
71 ^u 13	a forked D ^o 15 ^u D ^o
73 ^u 55	a Chestnut 2 1/2 feet D ^o
85 ^u 25	a White Oak 15 ^u D ^o
89 ^u 50	small Brook running North -
102 ^u	Good Land for last 10 ^u miles timber different kinds of Oak, Chestnut Hickory &c
106 ^u 00	a white Oak 14 ^u diam - Land Rich
116 ^u 10	a Hickory 2 1/2 feet diam -
130 ^u 92	a white Oak 10 ^u diam -
144 ^u 62	a D ^o 11 ^u D ^o
152 ^u 73	a D ^o 13 ^u D ^o Land still good & level with timber with white & black Oak Chestnut Hickory &c
157 ^u	a forked Chestnut 3 feet diam -
176 ^u 50	a white Oak 14 ^u diam -
189 ^u 10	" D ^o 14 ^u D ^o
192 ^u 67	a forked D ^o 3 feet D ^o Rich level Land timber principally white Oak -
192 ^u 75	a white Oak 2 1/2 feet diam -
200 ^u	Set Post at point of intersection, with west boundary line of Range 5 -

Description of Township No. 9 Range No. 5

Corner Posts bearing trees & Distance quality of the Land &

Point of Wood	Inch diam	Course	Links	Distance	quality of the Land &
White Oak	16	N 17.30 W	13		From A to B generally good farming Land timber Oak, Hickory, Chestnut &
D ^o	14	N 48. E	13		
Chestnut	14	S 5. N	60		from B to C generally broken stony Land
Black Oak	16	N 22 E	30		timber. Oak, Hickory &
White Oak	30	S 47 E	14		from C to D Land rich but rather broken some good bottom on the larger creeks, timber Oak Hickory, Ash, sugar tree Dogwood, pine, bush &
D ^o	36	N 64 E	60		
White Oak	36	S 15 W	60		from D to E good farming Land in general med dow & upland timber Oak, Hickory Chestnut sugar tree Cherry, Bush, thorn, plum &
Sugar tree	8	N 3. W	8		
Black Oak	36	S 62. E	15		from E to F low hills & wet swaily Land
Hickory	4	N 26 W	25		timber. Oak, Hickory & much black Oak brush &
White Oak	18	S 45 E	64		from F to G Land rich hills moderate except the first 20 N. which is stony & poor timber, Oak, Hickory &
a Cherry	12	N 27 W	41		
White Oak	20	N 6 E	35		from G to H first half good farming Land
D ^o	16	S 17.30 E	57		remainder rich but stony timber. Oak, Hickory Cherry plum &
White Oak	36	S 16.30 W	41		from H to A some good upland and bottom with flat & marshy swamps, timber. Oak Chestnut sugar tree, cherry, apple &
D ^o	16	N 26. E	57		

B & D
* this post stands 1.5 c. south of the point
of Intersection or true Corner

2nd Section N^o. 2
acres 4,030

2nd Section N^o. 1
acres 4,000

2nd Section N^o. 3
acres 4,000

2nd Section N^o. 4
acres 4,000

TOWNSHIP N^o. IX }
RANGE N^o. V } MILITARY DISTRICT

SCALE of Fifty Chain to an Inch

