Description 13.032 acre parcel

Being part of Lot 4, First Quarter, T-9 N, R-6 W, Berlin Township, Holmes County, Ohio, also known as part of the lands conveyed to Eleanor E. Mitten, Co-Trustee and Robert Sapiro, Co-Trustee in Official Record vol. 272 page 2532, PN 0100052000.

Described as follows:

Commencing at a 5/8 inch rebar found marking the southwest corner of Lot 4, thence S 88 degrees 37' 24" E 722.19 feet along the lot line to a point in a pond the TRUE POINT OF BEGINNING, witnessed by an iron pin set S 88 degrees 37' 24" E 184.04 feet, also witnessed by an iron pin set N 01 degree 35' 52" E 268.47 feet.

thence with the following NINE (9) COURSES:

- 1) N 01 degree 35' 52" E 318.81 feet along Jonas R. Troyer and Rebecca Ruth Troyer's (O.R. 233 page 946) east line to a 5/8 inch rebar found;
- 2) N 29 degrees 28' 21" E 232.15 feet along said Troyer's east line to an iron pin set;
- 3) S 89 degrees 12' 38" E 893.12 feet through the lands of said Mitten and Sapiro to an iron pin set;
- 4) S 00 degrees 14' 52" E 276.91 feet through the lands of said Mitten and Sapiro to a point in a creek, witnessed by an iron pin set N 86 degrees 00' 45" E 4.84 feet;
- 5) N 86 degrees 00' 45" E 913.80 feet through the lands of said Mitten and Sapiro to a point on the lot line and in C.R. 207, witnessed by an iron pin set S 86 degrees 00' 45" W 28.99 feet;
- 6) S 00 degrees 14' 52" E 50.11 feet along the lot line and along C.R. 207 to a point, witnessed by an iron pin set S 86 degrees 00' 45" W 26.84 feet;
- 7) S 86 degrees 00' 45" W 913.80 feet through the lands of said Mitten and Sapiro to an iron pin set;
- 8) S 00 degrees 14' 52" E 205.95 feet through the lands of said Mitten and Sapiro to an iron pin set on the lot line;
- N 88 degrees 37' 24" W 1018.74 feet along the lot line to the TRUE POINT OF BEGINNING.

This parcel contains 13.032 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83 (2011 adjustment).

See Holmes County Plat Book_______ page_____4868____ for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. October 25, 2022

Donald C. Baker

Donald C. Baker

Donald C. Baker

Donald C. Baker

BAKER

6938

G/STERE

ONAL SUMMER

ONAL S

P.S. 6938

THE THE PARTY OF T

Parcel Number: 0100052006

FILE DESCRIPTION Holmes County Map Office 11/30/2022