Description 0.750 acre parcel

Being part of the southwest quarter of Section 6, T-9 N, R-5 W, Berlin Township, Holmes County, Ohio, also known as part of the lands conveyed to Albert D. Miller and Anna Miller in Official Record vol. 34 page 765, PN 0100382000.

Described as follows:

Commencing at a stone found marking the northeast corner of the southwest quarter of Section 6, thence N 88 degrees 18' 36" W 247.50 feet along the quarter section line to a 5/8 inch rebar found, thence S 01 degree 21' 59" W 24.00 feet along Kaitlyn R. Kauffman's (O.R. 282 page 6556) west line to a point in the center of T.R. 363, thence S 74 degrees 56' 37" W 189.25 feet along the centerline of T.R. 363 to a point the TRUE POINT OF BEGINNING, witnessed by a 5/8 inch rebar found S 01 degree 21' 59" W 27.34 feet.

thence with the following SIX (6) COURSES:

- 1) S 01 degree 21' 59" W 207.00 feet along Ura D. Miller and Amanda Miller's (D.V. 241 page 701) west line to a 5/8 inch rebar found;
- 2) S 88 degrees 38' 01" E 181.53 feet along said Miller's south line to a 5/8 inch rebar found on said Kauffman's west line;
- 3) S 01 degree 21' 59" W 133.57 feet along said Kauffman's west line to an iron pin set;
- 4) N 88 degrees 38' 01" W 206.53 feet through the lands of said Albert D. Miller and Anna Miller to an iron pin set;
- 5) N 01 degree 21' 59" E 333.21 feet through the lands of said Miller to a point in the center of T.R. 363, witnessed by an iron pin set S 01 degree 21' 59" W 22.24 feet;
- 6) N 74 degrees 56' 37" E 26.06 feet along the centerline of T.R. 363 to the TRUE POINT OF BEGINNING.

This parcel contains 0.750 acres, but subject to all highways and easements of record. To go to adjoiner.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

19 See Holmes County Plat Book , page 5264 for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. December 11, 2023

P.S. 6938

DONALY
BAKY
69

BAKY
69

Parcel Number: 0100382002