Description 4.814 acre parcel

Being a part of the southwest quarter of Section 4, Berlin Township, T-9 N, R-5 W, Holmes County, Ohio.

Described as follows:

Commencing at a 5/8 inch rebar found marking the southwest corner of the southwest quarter of Section 4, thence S 89 degrees 01' 32" E 1557.94 feet along the section line to an iron pin set the TRUE POINT OF BEGINNING.

thence with the following FIVE (5) COURSES:

- 1) N 17 degrees 27' 22" E 698.55 feet to an iron pin set;
- 2) S 58 degrees 44' 58" E 428.50 feet to a point in the center of U.S. 62, witnessed by an iron pin set N 58 degrees 44' 58" W 34.59 feet;
- 3) S 33 degrees 03' 50" W 472.58 feet along the centerline of U.S. 62 to a point;
- 4) S 32 degrees 58' 28" W 63.00 feet along Wayne R. Miller and Sarah R. Miller's (D.V. 205 page 659) west line and along U.S. 62 to a point on the section line, witnessed by an iron pin set N 89 degrees 01' 32" W 66.34 feet;
- 5) N 89 degrees 01' 32" W 283.80 feet along the section line to the TRUE POINT OF BEGINNING.

This parcel contains 4.814 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings assumed.

See Holmes County Plat Book______, page_____4506____ for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. June 4, 2021

Donald C. Baker

P.S. 6938

DONALD **

BAKER 6938

ONAL SURING

Parcel Number: 0100773001