

Description 1.043 acre parcel

Being part of the southeast quarter of Section 21, T-8 N, R-5 W, Clark Township, Holmes County, Ohio, also known as part of the lands conveyed to Harvey A. Troyer and Edna R. Troyer in Official Record vol. 273 page 610, PN 0300002007.

Described as follows:

Commencing at a 5/8 inch rebar found marking the northwest corner of the southeast quarter of Section 21, thence S 88 degrees 34' 52" E 88.91 feet along the quarter section line to a 5/8 inch rebar found in the center of T.R. 177 the TRUE POINT OF BEGINNING.

thence with the following SIX (6) COURSES:

- 1) S 88 degrees 34' 52" E 395.84 feet along the quarter section line to an iron pin set;
- 2) S 25 degrees 42' 05" W 163.00 feet through the lands of said Troyer to an iron pin set;
- 3) S 65 degrees 37' 38" W 153.15 feet through the lands of said Troyer to a point in the center of T.R. 177, witnessed by an iron pin set N 65 degrees 37' 38" E 25.32 feet;
- 4) N 10 degrees 24' 33" W 12.00 feet along the centerline of T.R. 177 to a point;
- 5) N 29 degrees 49' 14" W 155.39 feet along Richard L. Lawver and Peggy A. Lawver's (O.R. 266 page 28) east line and along T.R. 177 to a point;
- 6) N 55 degrees 22' 20" W 128.92 feet along the centerline of T.R. 177 to the TRUE POINT OF BEGINNING.

This parcel contains 1.043 acres, but subject to all highways and easements of record. To go to adjoiner.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".
Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

See Holmes County Plat Book 19, page 5068 for survey.
This survey made and description prepared by Donald C. Baker, P.S. 6938.
June 16, 2023


Donald C. Baker P.S. 6938



Parcel Number: 0300002010

