

Address: 5434 TR 377, Millersburg, OH 44654 **Phone:** 330.231.0497

Description: 1.054 Acres

Being part of the Southwest Quarter of Section 25, part of the Village of Baltic, Clark Township, T-8 N, R-4 W, Holmes County, Ohio, also known as part of the lands of Albert John Gutheridge and Tammy Sue Gutheridge in Deed Vol. 270 Page 93, (PPN 0400040000).

Described as follows:

Commencing at a 5/8 inch rebar found marking the northeast corner of the southwest quarter of section 25, thence N 88 degrees 56'24" W a distance of 246.57 feet along the quarter section line and along the Village of Baltic Corporation line a 5/8 rebar found being the TRUE PLACE OF BEGINNING.

Thence with the following FOUR (4) COURSES;

- 1. S 12 degrees 20'46" W a distance of 212.73 feet along the west line of MRH Farm, LLC (O.R. Vol. 256 Page 6149) to an iron pin set;
- 2. N 88 degrees 56'24" W a distance of 220.00 feet through the lands of said Albert John Gutheridge and Tammy Sue Gutheridge to a point witnessed by an iron pin set S 88 degrees 56'24" E a distance of 22.69 feet;
- 3. N 12 degrees 20'46" E a distance of 212.73 feet along the east line of David A. Yoder and Rebecca S. Yoder (O.R. Vol. 284 Page 1608) and along the centerline of C.R. 575 (Buena Vista Street) to a railroad spike found witnessed by a 5/8 inch rebar found S 88 degrees 56'24" E a distance of 30.28 feet;
- **4.** S 88 degrees 56'24" E a distance of 220.00 feet along the quarter section line and along the Village of Baltic Corporation line to the TRUE PLACE OF BEGINNING.

This parcel contains 1.054 acres and is subject to all highways, easements, and restrictions of record.

Bearings from Grid North, Ohio State Plane Coordinate System, North Zone, NAD 83 (2011).

For survey see: Holmes County Plat Book Vol. 19 Page 5260

All iron pins set are 5/8-inch rebars 30 inches long with a plastic identification cap marked "Galbraith-8703".

This survey was made and description prepared by Caleb Jerome Galbraith P.S. 8703 on Feb. 22, 2024.

Parcel Number: 0400040002

Holmes County Map Office 4/22/2024