Description Trails Edge Estates Planned Unit Development – Phase 1 0.985 acres

Being part of Lot 950 in Pleasant View Glass Plant Addition Replat No. 1 (P. 2 page 635) in the Village of Millersburg, situated in Lot 42, First Quarter, T-9 N, R-7 W, Hardy Township, Holmes County, Ohio, also known as part of the lands conveyed to Grandview Property Holdings, LLC in Official Record vol. 284 page 2332, PN 0701668015.

Described as follows:

Commencing at a 5/8 inch rebar found marking the northwest corner of Lot 42, thence S 88 degrees 09' 46" E 411.77 feet along the lot line to a 5/8 inch rebar found, thence along a curve to the left having a delta angle of 01 degree 31' 15", R – 6625.55 feet, T – 87.94 feet, Ch. Brg. – S 03 degrees 49' 35" E, Ch. – 175.86 feet along Samuel M. Steimel and Beth E. Ladrach's (O.R. 263 page 2877) west line and along the west line of Lot 18 in Block 5 of Pleasant View Glass Plant Addition an arc distance of 175.86 feet to a 5/8 inch rebar found, thence S 88 degrees 09' 46" E 425.21 feet along said Steimel and Ladrach's south line and along Steven R. Erb and Judie D. Erb's (O.R. 229 page 2630 and O.R. 223 page 634) south line to a 5/8 inch rebar found, thence S 00 degrees 48' 20" W 285.93 feet along Robin's Terrace, Inc.'s (O.R. 206 page 2378 and O.R. 223 page 634) west line and along the west line of Lot 20 in Block 15 of Pleasant View Glass Plant Addition to a point the TRUE POINT OF BEGINNING.

thence with the following EIGHT (8) COURSES:

- 1) S 00 degrees 48' 20" W 170.00 feet along said Robin's Terrace, Inc.'s west line and along the west line of Lot 20 in Block 15 of Pleasant View Glass Plant Addition to a 5/8 inch rebar found on the north line of Sill Street;
- 2) \$ 89 degrees 56' 07" W 150.00 feet along the north line of Sill Street to a 5/8 inch rebar found;
- 3) S 00 degrees 48' 20" W 25.00 feet along the west line of Sill Street to a drill hole found in concrete:
- 4) S 89 degrees 56' 07" W 101.00 feet partly along Debra K. Kandel's (O.R. 223 page 634) north line and partly through the lands of said Grandview Property Holdings, LLC to a point;
- 5) N 00 degrees 48' 20" E 175.50 feet through the lands of said Grandview Property Holdings, LLC to a point;
- 6) N 89 degrees 56' 07" E 117.37 feet through the lands of said Grandview Property Holdings, LLC to a point;
- 7) N 00 degrees 41' 29" E 19.50 feet through the lands of said Grandview Property Holdings, LLC to a point;

8) N 89 degrees 56' 07" E 133.67 feet through the lands of said Grandview Property Holdings, LLC to the TRUE POINT OF BEGINNING.

This parcel contains 0.985 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

See Holmes County Plat Book 2 , page 644 for survey. This survey made and description prepared by Aaron L. Gerber, P.S. 8379. April 6, 2023

Aaron L. Gerber

P.S. 8379



Parcel Number: 0701668016



Holmes County Map Office 4/26/2023