Description 5.367 acre parcel

Being part of the northeast quarter of Section 23, T-8 N, R-7 W, Killbuck Township, Holmes County, Ohio, also known as part of the lands conveyed to Raye A. Pringle, Trustee in Official Record vol. 218 page 960, PN 0800158000.

Described as follows:

Commencing at a stone found marking the northwest corner of the northeast quarter of Section 23, thence S 88 degrees 33' 18" E 1328.70 feet along the section line to a 5/8 inch rebar found the TRUE POINT OF BEGINNING.

thence with the following FOUR (4) COURSES:

- 1) S 88 degrees 33' 18" E 540.21 feet along the section line and partly along T.R. 80 to a point, witnessed by an iron pin set S 01 degree 10' 34" W 18.37 feet;
- 2) S 01 degree 10' 34" W 432.77 feet through the lands of said Pringle to an iron pin
- 3) N 88 degrees 33' 18" W 540.21 feet through the lands of said Pringle to a point on Wendy Sue Gerhan's (O.R. 174 page 2358) east line and in T.R. 80, witnessed by an iron pin set S 88 degrees 33' 18" E 15.55 feet;
- 4) N 01 degree 10' 34" E 432.77 feet along said Gerhan's east line and partly along T.R. 80 to the TRUE POINT OF BEGINNING.

This parcel contains 5.367 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83 (2011 Adjustment).

See Holmes County Plat Book 19 4885 , page_ This survey made and description prepared by Donald C. Baker, P.S. 6938. November 15, 2022

P.S. 6938

DONALD
C.
BAKF
60
60 ATE OF OHIC

Parcel Number: 0800158002