Description 0.108 acre parcel

Being a part of the northeast quarter of Section 15, Killbuck Township, T-8 N, R-7 W, Holmes County, Ohio, also known as a part of the lands conveyed to Charles V. and Janet Straits in Deed vol. 200 page 566 and Deed vol. 209 page 888, PN 0800645000.

Described as follows:

Commencing at a 3/4 inch rebar found marking the northwest corner of the northeast quarter of Section 15, thence S 01 degrees 20' 18" W 293.41 feet along the quarter section line to a point, thence N 83 degrees 36' 24" E 408.77 feet along Todd A. Wengerd's (O.R. vol. 232 page 2643) north line to a 5/8 inch rebar found, S 06 degrees 23' 36" E 60.00 feet along said Wengerd's east line to an iron pin set, thence S 39 degrees 40' 01" E 98.35 feet along said Wengerd's east line to an iron pin set the TRUE POINT OF BEGINNING.

thence with the following FIVE (5) COURSES:

- 1) S 88 degrees 25' 12" E 82.43 feet through the lands of said Straits to an iron pin set;
- 2) S 66 degrees 07' 50" E 50.00 feet through the lands of said Straits to an iron pin set;
- 3) S 23 degrees 52' 10" W 33.54 feet through the lands of said Straits to an iron pin set;
- 4) N 88 degrees 25' 12" W 72.12 feet through the lands of said Straits to an iron pin set on said Wengerd's east line;
- 5) N 39 degrees 40' 01" W 66.50 feet along said Wengerd's east line to the TRUE POINT OF BEGINNING.

This parcel contains 0.108 acres, but subject to all easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83.

See Holmes County Plat Book___2___, page____579__ for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. March 18, 2019

Donald C. Baker

P.S. 6938

THE THE PARTY OF T

Parcel Number: 0800645003