Description 0.240 acre parcel

Being a part of the northeast quarter of Section 14, Killbuck Township, T-8 N, R-7 W, Holmes County, Ohio, also known as all of the lands conveyed to Samuel J. Shepler in Deed vol. 30 page 315, PN 0800897000.

Described as follows:

Commencing at a 3/4 inch rod found marking the northeast corner of the northeast quarter of Section 14, thence N 82 degrees 12' 29" W 181.50 feet along the section line to an iron pin set the TRUE POINT OF BEGINNING.

thence with the following SIX (6) COURSES:

- 1) S 07 degrees 16' 55" W 431.64 feet along Trustees of Killbuck & Mechanic Townships' (D.V. 85 page 535) west line and along Liberty Gospel's (O.R. 32 page 465) west line to a 5/8 inch rebar found;
- 2) S 82 degrees 00' 30" E 180.96 feet along Liberty Gospel's (O.R. 32 page 465 and O.R. 268 page 5899) south line and along Kenneth F. Brumme's (D.V. 278 page 1 and D.V. 278 page 4) south line and partly along C.R. 35 to a R.R. spike set on the section line:
- 3) S 07 degrees 21' 17" W 13.23 feet along the section line to a 5/8 inch rebar found;
- 4) N 81 degrees 53' 27" W 199.18 feet along Nick Pahoundis' (O.R. 242 page 2372) north line and along C.R. 35 to a 3/4 inch rod found;
- 5) N 07 degrees 16' 55" E 444.40 feet along said Pahoundis' east line to an iron pin set on the section line:
- 6) S 82 degrees 12' 29" E 18.23 feet along the section line to the TRUE POINT OF BEGINNING.

This parcel contains 0.240 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings from Plat vol. 14 page 345.

See Holmes County Plat Book_ , page 4604 This survey made and description prepared by Donald C. Baker, P.S. 6938. September 21, 2021

P.S. 6938

C. Baker

C. Baker

DONALD

C. BAKF

6°

BAKF

Parcel Number: 0800897001