Description 0.688 acre parcel

Being part of the northeast quarter of Section 20, Knox Township, T-19 N, R-15 W, Holmes County, Ohio, also known as all of the lands conveyed to Rodney Tyler Jones in Official Record vol. 286 page 4160, PN 1000109002.

Described as follows:

Commencing at a point marking the southwest corner of the northeast quarter of Section 20, thence N 86 degrees 30' 09" E 417.52 feet along the quarter section line to a point on the west line of C.R. 23 and on Holmes County Board of Commissioners' (O.R. 277 page 5981) west line, thence N 12 degrees 24' 22" E 112.06 feet along the west line of C.R. 23 and along said Holmes County Board of Commissioners' west line to a point, thence along a curve to the left having a delta angle of 02 degrees 16' 50", R – 1880.00 feet, T – 37.42 feet, Ch. Brg. – N 11 degrees 15' 57" E, Ch. – 74.83 feet along the west line of C.R. 23 and along said Holmes County Board of Commissioners' west line an arc distance of 74.83 feet to a 5/8 inch rebar found the TRUE POINT OF BEGINNING.

thence with the following SEVEN (7) COURSES:

- 1) Along a curve to the right having a delta angle of 13 degrees 14' 29", R 185.99 feet, T 21.59 feet, Ch. Brg. N 47 degrees 51' 47" W, Ch. 42.89 feet along the north line of Valley Drive and along October Hill Camplot Owners' Association's (D.V. 216 page 875) north line an arc distance of 42.98 feet to a 5/8 inch rebar found;
- 2) N 41 degrees 14' 32" W 133.49 feet along the north line of Valley Drive and along said October Hill Camplot Owners' Association's north line to a 5/8 inch rebar found;
- 3) N 50 degrees 53' 28" E 80.98 feet along Holmes County Board of Commissioners' (D.V. 227 page 297) east line to a 5/8 inch rebar found;
- 4) N 14 degrees 40' 55" E 69.40 feet along said Holmes County Board of Commissioners' east line to a 5/8 inch rebar found;
- 5) N 39 degrees 06' 32" W 121.00 feet along said Holmes County Board of Commissioners' north line to a 5/8 inch rebar found;
- 6) N 89 degrees 40' 41" E 144.95 feet along Lakeview Holdings, Ltd.'s (O.R. 204 page 2777) south line to a 5/8 inch rebar found on the west line of C.R. 23 and on Holmes County Board of Commissioners' (O.R. 277 page 5981) west line;
- 7) Along a curve to the right having a delta angle of 10 degrees 28' 40" W, R 1880.00 feet, T 172.38 feet, Ch. Brg. S 04 degrees 53' 12" W, Ch. 343.32 feet along the west line of C.R. 23 and along said Holmes County Board of Commissioners' west line an arc distance of 343.80 feet to the TRUE POINT OF BEGINNING.

This parcel contains 0.688 acres but subject to all highways and easements of record. To go to adjoiner.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

See Holmes County Plat Book______, page_____5234_____ for survey. This survey made and description prepared by Aaron L. Gerber, P.S. 8379. January 16, 2024

Aaron L. Gerber

P.S. 8379



Parcel Number: 1000109004

FILE DESCRIPTION
Holmes County Map Office

Imes County Map Offic 3/6/2024