## Description 11.125 acre parcel

Being part of the northwest quarter of Section 19, Mechanic Township, T-8 N, R-7 W, Holmes County, Ohio, also known as part of the lands conveyed to Alvin M. Wengerd and Rebecca J. Wengerd in Official Record vol. 255 page 6994, PN 1300163008.

## Described as follows:

Commencing at a stone found marking the southwest corner of the northwest quarter of Section 19, thence S 88 degrees 10' 41" E 1456.96 feet along the quarter section line to a 5/8 inch rebar found, thence N 04 degrees 06' 21" W 271.61 feet along Amanda A. Miller, Aden J. Miller, and Fannie N. Miller's (O.R. 252 page 4799) east line to an iron pin set the TRUE POINT OF BEGINNING.

thence with the following SIX (6) COURSES:

- 1) N 04 degrees 06' 21" W 894.91 feet along said Miller's east line to a 5/8 inch rebar found on Joseph R. Yoder and Anna Mae Yoder's (O.R. 252 page 4466) south line;
- 2) S 88 degrees 10' 41" E 513.82 feet along said Yoder's south line to a point in the center of C.R. 150, witnessed by a 5/8 inch rebar found N 88 degrees 10' 41" W 32.93 feet;
- 3) S 15 degrees 42' 16" E 683.97 feet along the centerline of C.R. 150 to a point, witnessed by a 5/8 inch rebar found N 89 degrees 34' 53" W 18.94 feet;
- 4) N 89 degrees 34' 53" W 90.32 feet along Robert J. Miller and Lena A. Miller's (O.R. 260 page 5720) north line to a stone found;
- 5) S 00 degrees 27' 56" W 136.00 feet along said Robert J. Miller and Lena A. Miller's west line to an iron pin set;
- 6) S 81 degrees 21' 49" W 549.42 feet through the lands of said Wengerd to the TRUE POINT OF BEGINNING.

This parcel contains 11.125 acres but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83.

See Holmes County Plat Book\_\_\_\_\_\_, page\_\_\_\_4616\_\_\_\_\_ for survey. This survey made and description prepared by Aaron L. Gerber, P.S. 8379. December 15, 2021

Aaron L. Gerber

P.S. 8379

AARON L. GERBER 8379 QUANTILITY ON AL SURING

Parcel Number: 1300163019