Description 13.701 acre parcel

Being part of the southwest quarter of Section 12, T-8 N, R-6 W, Mechanic Township, Holmes County, Ohio, also known as part of the lands conveyed to Dennis Miller Farm, LLC in Official Record vol. 266 page 4375, PN 1300536002.

Described as follows:

Commencing at a 5/8 inch rebar found marking the northeast corner of the southwest quarter of Section 12, thence N 89 degrees 43' 17" W 451.52 feet along the quarter section line to a 5/8 inch rebar found the TRUE POINT OF BEGINNING.

thence with the following FIVE (5) COURSES:

- 1) S 00 degrees 47' 59" W 880.19 feet along Andy R. Yoder and Nettie P. Yoder's (O.R. 266 page 6727) west line to a 5/8 inch rebar found;
- 2) N 89 degrees 43' 17" W 675.29 feet along said Yoder's north line to a 5/8 inch rebar found;
- 3) N 04 degrees 13' 42" E 275.97 feet through the lands of said Dennis Miller Farm, LLC to an iron pin set;
- 4) N 03 degrees 47' 58" W 606.38 feet through the lands of said Dennis Miller Farm, LLC to an iron pin set on the quarter section line;
- 5) S 89 degrees 43' 17" E 707.41 feet along the quarter section line to the TRUE POINT OF BEGINNING.

This parcel contains 13.701 acres, but subject to all highways and easements of record. To go to adjoiner.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

See Holmes County Plat Book______, page_____4846____ for survey. This survey made and description prepared by Aaron L. Gerber, P.S. 8379. August 23, 2022

Aaron L. Gerber

P.S. 8379

AARON L. GERBER 8379 OF STREET STREET

Parcel Number: 1300536006