BOUNDARY DESCRIPTION

2.670 Acres

Situated in the State of Ohio, County of Holmes, Township of Monroe in Lot 4, 2nd quarter, T-9N, R-8W, of the United States Military District.

Being part of the land described in a deed to Alvin Claus and Clara J. Claus, Trustees and Grantors of the Claus Family Trust (PPN 1400071000) recorded in official record volume 33, page 641 of the Holmes County records.

Described as follows:

Commencing at a capped pin marked "Baker 6938" found marking the northwest corner of Lot 4.

Thence S 01° 02' 58" W 488.96 feet, along the west line of Lot 4, to a point in State Route 39 and State Route 60, the Point of Beginning of the parcel herein described—witnessed by a capped reference pin set S 01° 02' 58" W 39.89 feet.

Thence with the following FIVE courses:

- S 60° 27' 17" E 125.13 feet, in State Route 39 and State Route 60, along the south line of Melinda J. 1) Eppley as described in official record volume 260, page 3141, to the southeast corner thereof witnessed by a capped reference pin marked "Baker 6938" found N 01° 02' 58" E 46.72 feet.
- S 55° 38' 45" E 115.20 feet, in State Route 39 and State Route 60, to a point witnessed by a 2) capped reference pin set S 28° 18' 15" W 30.00 feet.
- S 61° 41' 40" E 181.74 feet, in State Route 39 and State Route 60, to a point witnessed by a 3) capped reference pin set S 41° 34' 50" W 30.82 feet.
- S 41° 34' 50" W 565.98 feet to a capped pin set in a ditch on the west line of Lot 4 4) - witnessed by a capped reference pin set N 41° 34' 50" E 9.41 feet.
- N 01° 02° 58" E 636.36 feet, along the west line of Lot 4, to the Point of Beginning. 5)

This parcel contains 2.670 acres

Prior Instrument: Official record volume 33, page 641

This description was prepared by Edward A. Gasbarre, P.S. 7036, from information contained in a survey made under his direction, in January of 2022, on behalf of R.W. Gasbarre & Associates, Inc. All bearings are related and based on the west line of Lot 4 according to plat volume 12, page 469. WEYOR A OF A All capped pins, both set and found, are 5/8 inch diameter solid steel rods with identification caps marked "GASBARRE WOOSTER, OHIO" unless otherwise noted.

See plat volume 19, page 4614 for survey

Parcel Number: 1400071003

H:\ADAT4\AJOBS\2K21\job151\Claus_Legal. 2.670Ac.doc NO PESSION

FILE DESCRIPTION

Holmes County Map Office 2/7/2022

Edward A. Gasbarre, P.S. 7036