BOUNDARY DESCRIPTION

24.114 Acres

Situated in the State of Ohio, County of Holmes, Township of Monroe in Lot 4, 2nd quarter, T-9N, R-8W, of the United States Military District.

Being part of the land described in a deed to Alvin Claus and Clara J. Claus, Trustees and Grantors of the Claus Family Trust (PPN 1400071001) recorded in official record volume 33, page 641 of the Holmes County records.

Described as follows:

Beginning in a ditch at the southwest corner of Lot 4 – witnessed by a capped reference pin set S 87° 42' 54" E 23.04 feet and by a 5/8 inch diameter iron pin found N 48° 48' E 2.50 feet.

Thence with the following FIVE courses:

- 1) N 01° 02' 58" E 563.64 feet, along the west line of Lot 4, to a capped pin set in a ditch witnessed by a capped reference pin set N 41° 34' 50" E 9.41 feet.
- 2) N 41° 34′ 50″ E 565.98 feet, through the lands of Alvin Claus and Clara J. Claus, Trustees and Grantors of the Claus Family Trust recorded in official record volume 33, page 641, to a point in State Route 39 and State Route 60 witnessed by a capped reference pin set S 41° 34′ 50″ W 30.82 feet.
- 3) S 61° 41' 40" E 1139.98 feet, in State Route 39 and State Route 60, to an iron railroad spike found at a northwesterly corner of Bands Company, Inc. as described in official record volume 19, page 812 witnessed by a capped reference pin marked "Baker 6938" found S 00° 41' 25" W 33.77 feet.
- 4) S 00° 41' 25" W 501.61 feet, along a westerly line of Bands Company, Inc. to a capped pin set in a ditch on the south line of Lot 4 witnessed by a capped reference pin set N 00° 41' 25" E 20.17 feet.
- 5) N 87° 42' 54" W 1384.68 feet, along the south line of Lot 4, to the Point of Beginning.

This parcel contains 24.114 acres

Prior Instrument: Official record volume 33, page 641

This description was prepared by Edward A. Gasbarre, P.S. 7036, from information contained in a survey made under his direction, in January 2022, on behalf of R.W. Gasbarre & Associates, Inc. All bearings are related and based on the west line of Lot 4 according to plat volume 12, page 469. All capped pins, both set and found, are 5/8 inch diameter solid steel rods with identification caps marked "GASBARRE WOOSTER, OHIO" unless otherwise noted.

See Plat Volume 19, page 4614 for survey.

Parcel Number: 1400071004

Edward A. Gasbarre, P.S. 7036

H:\ADAT4\AJOBS\2K21\job151\Claus_Legal_24.114Ac.do

White the state of the state of

William Che 22

FILE DESCRIPTION

Holmes County Map Office 2/7/2022