Description 4.146 acre parcel

Being part of Lot 22, First Quarter, Monroe Township, T-9 N, R-8 W, Holmes County, Ohio.

Described as follows:

Commencing at a R.R. spike found in C.R. 320 marking the northwest corner of Lot 22, thence S 87 degrees 36' 42" E 256.86 feet along the lot line and along C.R. 320 to a 5/8 inch rebar found the TRUE POINT OF BEGINNING.

thence with the following FOUR (4) COURSES:

- 1) S 87 degrees 36' 42" E 491.13 feet along the lot line and along C.R. 320 to a point, witnessed by a 5/8 inch rebar found S 02 degrees 23' 18" W 30.00 feet;
- 2) S 02 degrees 23' 18" W 450.38 feet along L & C Rental Properties, Ltd.'s (O.R. 258 page 605) west line to a 5/8 inch rebar found;
- 3) S 82 degrees 37' 51" W 265.62 feet to an iron pin set;
- 4) N 22 degrees 27' 17" W 545.92 feet to the TRUE POINT OF BEGINNING.

This parcel contains 4.146 acres, but subject to all highways and easements of recordary

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

See Holmes County Plat Book______, page_____5075____ for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. May 31, 2023

Donald C. Baker

P.S. 6938

DONALD *

BAKER
6938

6938

C.
BONALD

C.
BONAL

C.
BONA

Parcel Number: 1400085004