Description 42.000 acre parcel

Being part of Lot 24, Third Quarter, T-9 N, R-8 W, Monroe Township, Holmes County, Ohio, also known as part of the lands conveyed to Greenup Resources, LLC in Official Record vol. 285 page 5993, PN 1400192006.

Described as follows:

Commencing at a stone found marking the southwest corner of Lot 24, thence S 87 degrees 38' 49" E 451.33 feet along the lot line to an iron pin set the TRUE POINT OF BEGINNING.

thence with the following TEN (10) COURSES:

- 1) N 03 degrees 19' 28" E 875.84 feet through the lands of said Greenup Resources, LLC to an iron pin set;
- 2) N 80 degrees 19' 30" E 1171.19 feet through the lands of said Greenup Resources, LLC to an iron pin set;
- 3) S 77 degrees 07' 24" E 322.99 feet through the lands of said Greenup Resources, LLC to an iron pin set;
- 4) S 61 degrees 00' 59" E 389.86 feet through the lands of said Greenup Resources, LLC to a point on Abraham L. Mast and Janelle R. Mast's (O.R. 215 page 3390) west line and in T.R. 257, witnessed by an iron pin set N 61 degrees 00' 59" W 29.49 feet;
- 5) S 08 degrees 05' 33" W 31.83 feet along said Mast's west line and along T.R. 257 to a R.R. spike found;
- 6) S 03 degrees 41' 11" E 134.04 feet along said Mast's (O.R. 215 page 3390 and O.R. 1 page 786) west line and along T.R. 257 to a point;
- 7) Along a curve to the left having a delta angle of 48 degrees 30' 41", R 172.56 feet, T 77.75 feet, Ch. Brg. S 27 degrees 56' 32" E, Ch. 141.78 feet along said Mast's (O.R. 1 page 786) west line and along T.R. 257 an arc distance of 146.10 feet to a 5/8 inch rebar found;
- 8) S 52 degrees 11' 52" E 92.13 feet along said Mast's (O.R. 1 page 786) south line and along T.R. 257 to a point, witnessed by a 5/8 inch rebar found S 36 degrees 54' 15" W 9.95 feet;
- 9) S 36 degrees 54' 15" W 661.98 feet along Patrick A. Shriver's (O.R. 274 page 4567) west line to a 5/8 inch rebar found on the lot line;
- 10) N 87 degrees 38' 49" W 1608.44 feet along the lot line to the TRUE POINT OF BEGINNING.

This parcel contains 42.000 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

See Holmes County Plat Book______, page_____5125____ for survey. This survey made and description prepared by Aaron L. Gerber, P.S. 8379, October 4, 2023

Aaron L. Gerber

P.S. 8379



Parcel Number: 1400192007

Holmes County Map Office 10/20/2023