Description 25.978 acre parcel

Being a part of the northeast quarter of Section 34, Paint Township, T-15 N, R-11 W, Holmes County, Ohio, also known as part of the lands conveyed to David A. Wengerd and Mary Esther Wengerd in Deed vol. 232 page 615, PN 1500994000.

Described as follows:

Beginning at a 5/8 inch rebar found marking the southeast corner of the northeast quarter of Section 34 the TRUE POINT OF BEGINNING.

thence with the following THIRTEEN (13) COURSES:

- 1) N 87 degrees 07' 42" W 1251.45 feet along the quarter section line to a 5/8 inch rebar found;
- 2) N 02 degrees 52' 18" E 369.00 feet along David Allen Wengerd and Wilma D. Hershberger's (O.R. 251 page 5758) east line to a 5/8 inch rebar found;
- 3) N 87 degrees 07' 42" W 343.37 feet along said Wengerd and Hershberger's north line to a 5/8 inch rebar found;
- 4) N 28 degrees 42' 41" W 719.15 feet along said Wengerd and Hershberger's north line to a point in the center of C.R. 186, witnessed by a 5/8 inch rebar found S 28 degrees 42' 41" E 56.84 feet;
- 5) N 06 degrees 19' 15" E 56.03 feet along the centerline of C.R. 186 to a point, witnessed by a 5/8 inch rebar found S 66 degrees 12' 58" E 19.17 feet;
- 6) S 66 degrees 12' 58" E 159.29 feet along Duane E. Shetler and Sue Ann Shetler's (O.R. 225 page 3174) south line to a 5/8 inch rebar found;
- 7) S 78 degrees 48' 07" E 188.51 feet along said Shetler's south line to a 5/8 inch rebar found:
- 8) S 09 degrees 19' 15" E 384.39 feet along said Shetler's west line to a 5/8 inch rebar found;
- 9) S 87 degrees 25' 27" E 668.13 feet along said Shetler's south line to a 5/8 inch rebar found:
- 10) N 36 degrees 37' 52" E 169.68 feet through the lands of said Wengerd to an iron pin set;
- 11) N 51 degrees 05' 06" E 70.30 feet through the lands of said Wengerd to an iron pin set;
- 12) N 79 degrees 32' 19" E 752.80 feet through the lands of said Wengerd to an iron pin set on the section line;

13) S 02 degrees 36' 48" W 942.66 feet along the section line to the TRUE POINT OF BEGINNING.

This parcel contains 25.978 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings from Plat vol. 18 page 458.

See Holmes County Plat Book_____, page____4346____ for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. January 6, 2021

Donald C. Baker

P.S. 6938



Parcel Number: 1500994011

Holmes County Map Office 3/29/2021