Description 4.535 acre parcel

Being a part of the southeast quarter of Section 17, Ripley Township, T-17 N, R-14 W, Holmes County, Ohio, also known as part of the lands conveyed to RRS Holdings, LLC in Official Record vol. 278 page 2273, PN 2300192000.

Described as follows:

Commencing at a 5/8 inch rebar found in T.R. 504 (non-maintained) marking the northeast corner of the southeast quarter of Section 17, thence S 00 degrees 24' 30" E 975.66 feet along the section line to a R.R. spike found in T.R. 503 the TRUE POINT OF BEGINNING, witnessed by a 5/8 inch rebar found N 00 degrees 24' 30" W 58.31 feet.

thence with the following EIGHT (8) COURSES:

- S 00 degrees 24' 30" E 270.90 feet along the section line and along T.R. 503 to a point, witnessed by an iron pin set N 89 degrees 04' 18" W 18.00 feet;
- 2) N 89 degrees 04' 18" W 441.31 feet through the lands of said RRS Holdings, LLC to an iron pin set;
- 3) N 00 degrees 24' 30" W 560.39 feet through the lands of said RRS Holdings, LLC to a point in the center of T.R. 503, witnessed by an iron pin set S 00 degrees 24' 30" E 31.93 feet;
- S 56 degrees 52' 59" E 38.76 feet along the centerline of T.R. 503 to a R.R. spike found;
- 5) S 64 degrees 36' 13" E 334.83 feet along the centerline of T.R. 503 to a R.R. spike found;
- 6) S 53 degrees 06' 01" E 82.19 feet along the centerline of T.R. 503 to a R.R. spike found;
- 7) S 31 degrees 46' 49" E 59.42 feet along the centerline of T.R. 503 to a R.R. spike found:
- 8) S 19 degrees 32' 21" E 33.95 feet along the centerline of T.R. 503 to the TRUE POINT OF BEGINNING.

This parcel contains 4.535 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings assumed.

See Holmes County Plat Book_______, page______4532____ for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. October 8, 2021

Donald C. Baker

P.S. 6938

DONALD

BAKER

6938

OF ONALD

C.

BAKER

6938

OF ONAL

Parcel Number: 2300192005

FILE DESCRIPTION Holmes County Map Office 10/27/2021