Description 0.286 acre parcel

Being a part of the southeast quarter of Section 5, Salt Creek Township, T-14 N, R-12 W, Holmes County, Ohio, also known as part of the lands conveyed to Arlie L. Stutzman and Ada Stutzman in Official Record vol. 57 page 352, Official Record vol. 243 page 1077 and Official Record vol. 258 page 4876, PN 2400394001.

Described as follows:

Commencing at a point marking the southwest corner of the southeast quarter of Section 5, thence S 87 degrees 00' 00" E 388.52 feet along the section line to a point, thence N 33 degrees 40' 00" W 0.71 feet along Mary Stutzman's (O.R. 258 page 3921, PN 2401059002) west line to a point, thence N 59 degrees 32' 31" E 153.19 feet along said Mary Stutzman's north line to a 5/8 inch rebar found the TRUE POINT OF BEGINNING.

thence with the following FIVE (5) COURSES:

- 1) N 60 degrees 00' 14" E 103.98 feet through the lands of said Arlie L. Stutzman and Ada Stutzman to an iron pin set;
- 2) S 84 degrees 15' 56" E 99.08 feet through the lands of said Arlie L. Stutzman and Ada Stutzman to an iron pin set;
- 3) S 15 degrees 56' 03" E 43.03 feet through the lands of said Arlie L. Stutzman and Ada Stutzman to a 5/8 inch rebar found;
- 4) S 73 degrees 50' 29" W 192.73 feet along said Mary Stutzman's north line to a 5/8 inch rebar found;
- 5) N 16 degrees 09' 31" W 55.10 feet along said Mary Stutzman's north line to the TRUE POINT OF BEGINNING.

This parcel contains 0.286 acres, but subject to all easements of record. To go to adjoiner.

The above described 0.286 acre parcel is subject to a 20 foot farm ingress and egress easement, further described as follows:

Being a part of the southeast quarter of Section 5 and northeast quarter of Section 8, Salt Creek Township, T-14 N, R-12 W, Holmes County, Ohio, also known as part of the lands conveyed to Mary Stutzman in Official Record vol. 258 page 3921, Arlie L. Stutzman and Ada Stutzman in Official Record vol. 57 page 352, Official Record vol. 243 page 1077 and Official Record vol. 258 page 4876, and Edward Stutzman and Raymond Stutzman in Official Record vol. 267 page 2999, PN 2400394006, PN 2401059002, PN 2400394001 and PN 2400394000.

Commencing at a point marking the northwest corner of the northeast quarter of Section 8, thence S 87 degrees 00' 00" E 235.00 feet along the section line to a point in the center of T.R. 604, thence S 42 degrees 57' 00" E 41.51 feet along the centerline of T.R. 604 to a point the TRUE POINT OF BEGINNING.

thence with the following FIVE (5) COURSES along the centerline of a 20 foot farm ingress and egress easement:

- 1) N 82 degrees 14' 36" E 154.66 feet through the lands of said Mary Stutzman to a point on the section line;
- 2) N 73 degrees 56' 05" E 94.23 feet (passing into the southeast quarter of Section 5) through the lands of said Mary Stutzman to a point;
- 3) N 23 degrees 14' 05" E 50.14 feet partly through the lands of said Mary Stutzman and partly through the lands of said Arlie L. Stutzman and Ada Stutzman to a point;

- 4) N 60 degrees 00' 14" E 145.44 feet through the lands of said Arlie L. Stutzman and Ada Stutzman to a point;
- 5) N 05 degrees 44' 04" E 32.64 feet partly through the lands of said Arlie L. Stutzman and Ada Stutzman and partly through the lands of said Edward Stutzman and Raymond Stutzman to a point and THERE ENDS.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings for Plat vol. 19 page 3115.

See Holmes County Plat Book______, page_____4515_____ for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938, June 29, 2021

Donald C. Baker

P.S. 6938

DONALD & BAKER 6938 6938 6938 OF THE PROPERTY OF THE PROPERTY

Parcel Number: 2400394008