## Description 5.000 acre parcel

Being part of Lot 3, Third Quarter, Salt Creek Township, T-10 N, R-6 W, Holmes County, Ohio.

Described as follows:

Commencing at a 5/8 inch rebar found marking the southwest corner of Lot 3, thence S 88 degrees 30' 36" E 76.29 feet along the lot line to a 3/4 inch pipe found, thence S 88 degrees 45' 41" E 776.75 feet along the lot line to a point, thence N 02 degrees 19' 32" E 908.51 feet along David E. Miller and Arie R. Miller's (O.R. 216 page 2767) west line to a point in a stream the TRUE POINT OF BEGINNING, witnessed by a 5/8 inch rebar found N 12 degrees 07' 03" W 30.88 feet.

thence with the following SEVEN (7) COURSES:

- 1) N 12 degrees 07' 03" W 572.99 feet along Wayne D. Troyer and Verba J. Troyer's (O.R. 223 page 21) east line to a point in the center of C.R. 189, witnessed by a 5/8 inch rebar found S 12 degrees 07' 03" E 25.13 feet;
- 2) S 77 degrees 33' 35" E 248.58 feet along the centerline of C.R. 189 to a point;
- 3) S 72 degrees 38' 43" E 173.48 feet along the centerline of C.R. 189 to a point;
- 4) S 64 degrees 06' 43" E 100.00 feet along the centerline of C.R. 189 to a point;
- 5) S 60 degrees 33' 56" E 31.71 feet along the centerline of C.R. 189 to a point, witnessed by an iron pin set S 18 degrees 29' 39" W 27.86 feet;
- 6) S 18 degrees 29' 39" W 559.77 feet to a point on said Miller's north line and in a stream, witnessed by an iron pin set N 18 degrees 29' 39" E 39.75 feet;
- 7) N 59 degrees 20' 35" W 265.12 feet along said Miller's north line and along a stream to the TRUE POINT OF BEGINNING.

This parcel contains 5.000 acres but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

Aaron L. Gerber

P.S. 8379

AARON L. AAR

Parcel Number: 2400567016