Description 1.000 acre parcel

Being part of Lot 13, First Quarter, T-9 N, R-5 W, Walnut Creek Township, Holmes County, Ohio, also known as part of the lands conveyed to Allen J. Schrock and Betty Schrock in Deed vol. 259 page 127, PN 2600777000.

Described as follows:

Commencing at a stone found marking the northeast corner of Lot 13, thence S 01 degrees 07' 52" W 868.10 feet along the lot line to a 5/8 inch rebar found, thence N 88 degrees 51' 00" W 373.86 feet along Raymond A. Troyer and Esta A. Troyer's (O.R. 104 page 700) north line to a 5/8 inch rebar found, thence S 01 degrees 06' 18" W 103.60 feet along said Troyer's west line to a 5/8 inch rebar found, thence S 81 degrees 29' 22" W 371.51 feet along Paul W. Hershberger and Marilyn R. Hershberger's (O.R. 256 page 738) north line to a 5/8 inch rebar found, thence S 04 degrees 16' 49" W 123.72 feet along said Hershberger's west line to a R.R. spike found in the center of C.R. 168, thence N 82 degrees 45' 13" W 50.25 feet along the centerline of C.R. 168 to a point the TRUE POINT OF BEGINNING, witnessed by an iron pin set N 01 degrees 34' 52" E 18.47 feet.

thence with the following FOUR (4) COURSES:

- 1) N 82 degrees 45' 13" W 167.00 feet along the centerline of C.R. 168 to a point, witnessed by an iron pin set N 01 degrees 34' 52" E 18.78 feet;
- 2) N 01 degrees 34' 52" E 253.40 feet through the lands of said Schrock to an iron pin
- 3) S 88 degrees 44' 45" E 166.19 feet through the lands of said Schrock to an iron pin
- 4) S 01 degrees 34' 52" W 270.84 feet through the lands of said Schrock to the TRUE POINT OF BEGINNING.

This parcel contains 1.000 acres, but subject to all highways and easements of recordary

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83 (2011 Adjustment).

See Holmes County Plat Book page 4750 for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. March 14, 2022

P.S. 6938

DONALD
C.
BAKER
6938

BAKER
6938

CONAL SI

Parcel Number: 2600777008