Description 2.784 acre parcel

Being a part of the northeast quarter of Section 21, T-9 N, R-5 W, Walnut Creek Township, Holmes County, Ohio, also known as part of the lands conveyed to Mark P. Yoder and Betty Yoder, Co-Trustees in Official Record vol. 38 page 356, PN 2601055000.

Described as follows:

Commencing at a R.R. spike found in C.R. 144 marking the northeast corner of the northeast quarter of Section 21, thence N 89 degrees 06' 52" W 165.55 feet along the section line to a point the TRUE POINT OF BEGINNING, witnessed by a 5/8 inch rebar found S 01 degrees 16' 05" W 23.53 feet.

thence with the following SIX (6) COURSES:

- 1) S 01 degrees 16' 05" W 565.36 feet along Joel Beachy and Diana Beachy's (O.R. 260 page 6041) west line to an iron pin set;
- N 89 degrees 10' 09" W 218.56 feet through the lands of said Yoder to an iron pin set;
- 3) N 01 degrees 16' 05" E 430.87 feet through the lands of said Yoder to an iron pin set:
- 4) N 26 degrees 00' 02" E 50.89 feet through the lands of said Yoder to an iron pin set;
- 5) N 00 degrees 01' 03" W 88.63 feet through the lands of said Yoder to a point on the section line and in C.R. 144, witnessed by an iron pin set S 00 degrees 01' 03" E 14.15 feet:
- 6) S 89 degrees 06' 52" E 199.25 feet along the section line to the TRUE POINT OF BEGINNING.

This parcel contains 2.784 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83.

See Holmes County Plat Book______, page____4706____ for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. February 10, 2021

Donald C. Baker

P.S. 6938

DONALD ***

BAKER 6938

ONALD ***

BOUND TO THE PROPERTY OF TH

Parcel Number: 2601055003