Description 0.215 acre parcel

Being part of the Village of Walnut Creek, situated in the northwest guarter of Section 20, T-9 N, R-5 W, Walnut Creek Township, Holmes County, Ohio, also known as part of the lands conveyed to Walnut Hills Retirement Communities, Inc. in Official Record vol. 224 page 601, PN 2601253000.

Described as follows:

Commencing at a 5/8 inch rebar found marking the southeast corner of the northwest quarter of Section 20, thence N 88 degrees 27 31" W 1338.43 feet along the quarter section line to a point, thence N 00 degrees 14' 21" W 465.12 feet along the east line of Outlot 1 in the Village of Walnut Creek and along Marilyn K. Shrock, Ashley J. Shrock, and John Alex Shrock (O.R. 278 page 2119), Marilyn K. Shrock (O.R. 231 page 193), and Aaron Jamin Yoder and Carrie Anne Yoder's (O.R. 241 page 1543) east line to a point in the center of T.R. 444 aka Walnut Street, thence N 61 degrees 52' 43" E 61.65 feet along the centerline of T.R. 444 aka Walnut Street to a point the TRUE POINT OF BEGINNING, witnessed by an iron pin set S 21 degrees 06' 07" E 27.78 feet.

thence with the following FOUR (4) COURSES:

- 1) N 57 degrees 35' 44" E 65.40 feet along the centerline of T.R. 444 aka Walnut Street to a point, witnessed by an iron pin set S 18 degrees 25' 10" E 27.44 feet;
- 2) S 18 degrees 25' 10" E 153.00 feet along Katie R. Miller's (O.R. 262 page 3186) west line to a 5/8 inch rebar found;
- 3) S 50 degrees 23' 45" W 60.08 feet through the lands of said Walnut Hills Retirement Communities, Inc. to a 5/8 inch rebar found;
- 4) N 21 degrees 06' 07" W 159.08 feet along said Walnut Hills Retirement Communities, Inc.'s (PN 2600316000) east line to the TRUE POINT OF BEGINNING.

This parcel contains 0.215 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

19 See Holmes County Plat Book 5181 , page for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. November 29, 2023

P.S. 6938

J C. Baker

J C. Baker

DONALF

C.

BAV

BAV

Parcel Number: 2601253001