## Description 1.052 acre parcel

Being part of the southwest quarter of Section 20, Walnut Creek Township, T-9 N, R-5 W, Holmes County, Ohio.

## Described as follows:

Commencing at a 1/2 inch pipe found marking the southwest corner of the southwest quarter of Section 20, thence N 01 degree 16' 35" E 1202.18 feet along the section line to a 5/8 inch rebar found, thence N 76 degrees 27' 32" E 433.27 feet along Living Waters Fellowship Church's (O.R. 284 page 5191) south line to a 5/8 inch rebar found the TRUE POINT OF BEGINNING.

thence with the following SIX (6) COURSES:

- 1) N 76 degrees 27' 32" E 197.50 feet along said Living Waters Fellowship Church's south line to a point in the center of S.R. 39, witnessed by a 1/2 inch pipe found S 76 degrees 27' 32" W 95.06 feet;
- 2) S 09 degrees 35' 01" E 221.10 feet along the centerline of S.R. 39 to a point;
- 3) S 52 degrees 19' 51" W 36.02 feet to an iron pin set;
- 4) S 72 degrees 44' 21" W 64.07 feet to an iron pin set;
- 5) S 87 degrees 04' 44" W 102.45 feet to a 5/8 inch rebar found;
- 6) N 09 degrees 35' 01" W 221.10 feet along Matthew I. Miller and Laurita L. Miller's (O.R. 280 page 1593) east line to the TRUE POINT OF BEGINNING.

This parcel contains 1.052 acres but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

See Holmes County Plat Book 19 5130 for survey. , page\_ This survey made and description prepared by Aaron L. Gerber, P.S. 8379. April 21, 2023

Aaron L. Gerber

P.S. 8379

AARON L.

GERBER
8379

OISTERED

Parcel Number: 2601342002