JASON J. LINGENFELTER, P.S.

PROFESSIONAL LAND SURVEYOR

Boundary description of a 5.000 acre (Tract A) parcel

23-043

Situated in the State of Ohio, County of Holmes, Township of Washington and known as being a part of the Southwest Quarter of Section 15, T-19N; R-15W;

Also known as being a part of lands conveyed to David J. Carroll by Deed Volume 173, Page 677, (PPN. 2700050000), of Holmes County Records and further bound and described as follows:

Beginning at a 3/4 inch rebar found in Township Road 453 witnessed by a 5/8 inch rebar with I.D. cap "Baker" found S 01° 18' 43" E, 24.00 feet and known as being the northwest corner of the Southwest Quarter of Section 15, Washington Township;

THENCE WITH THE FOLLOWING SEVEN (7) COURSES:

- S 87° 45' 46" E, 60.12 feet along the quarter section line, the Grantor's northerly line and with Township Road 453 to a point witnessed by a capped rebar set S 01° 18' 43" E, 25.00 feet;
- 2) S 01° 18' 43" E, 666.30 feet through the Grantor's lands to a capped rebar set;
- 3) S 37° 00'42" E, 233.46 feet through the Grantor's lands to a capped rebar set;
- 4) S 87° 45' 46" E, 236.22 feet through the Grantor's lands to a capped rebar set;
- 5) S 01° 18' 43" E, 357.91 feet through the Grantor's lands to a capped rebar set;
- 6) N 87° 45' 46" W, 432.83 feet through the Grantor's lands to a capped rebar set on the section line and the Grantor's westerly line;
- 7) N 01° 18' 43" W, 1205.35 feet along the section line and the Grantor's westerly line to the principal place of beginning and containing within said bounds 5.000 acres of land more or less, and subject to all legal highways and easements of record.

Continued on Page 2

Page 2 (Description of 5.000 ac.)

This description was prepared from a survey made by Jason J. Lingenfelter, P.S. #8499 in January of 2024.

All rebars set are 5/8" diameter by 30" long with plastic cap stamped "LINGENFELTER".

Basis of bearing: The bearings as shown hereon are relative to GRID NORTH of the OHIO STATE PLANE COORDINATE SYSTEM, NAD 83 (2011) DATUM.

See Holmes County Plat Book Volume 19; Page 5263 for survey.

Jason J. Lingenfelter, P.

Pebruary 1, 2024

Parcel Number: 2700050002

FILE DESCRIPTION

Holmes County Map Office 4/23/2024