

8. Gum 14 N 61 W 10 S Elm 12 S 43 E 36  
 9. Poplar 8 S 32½ E 36 8  
 10. Beech 10 S 31½ W 15 S B. O 20. N 5 W 11 } Gate Post  
 12. W. Oak 5 S 26½ W 9 S Do 4 N 21 E 13  
 12

## Remarks

Section 6 on the preceding page was surveyed in Nov. 1849 by the agreement of the landholders in 5<sup>th</sup> Section. The N.E. Corner of 5<sup>th</sup> Section was in some dispute on account of the surplus in 5<sup>th</sup> Section. I considered the corner good; the original Witness Trees are standing though ruined. The old lines lead to this point. The remaining corners were placed by the lines. The South q<sup>r</sup>. Corner could not be found by any reliable evidence, it was therefore placed according to Law that is 40 Chains West from the S.E. corner of 5<sup>th</sup> Section. Section 5 was Surveyed by Agreement.

All the Original Witness <sup>Trees</sup> to the Corners of 5<sup>th</sup> Section were found excepting the S. W. & N. E. but there are well blazed lines leading to the Township & Range lines by which the corners were made. The North q<sup>r</sup>. corner stands 40 near the East line by 50 links, while the South q<sup>r</sup>. corner stands 2 chains west of the returned distance.

Section 4 was Surveyed by Agreement.

All the Original Witness Trees to the corners of 5<sup>th</sup> Section were found, excepting the N. W. corner which was named in the above; this section is too small on the west side, but it cannot be remedied as there is a good section line between sections 4 and 5.

The East line of Sec. 4 is a plainly marked line commencing at the N.E. corner and running a short distance in the direction of the S.E. corner, then bearing to the west considerable

J. Silcott Co. S. H. Co.