10 PAGE 344 ! VOL 145255 VILLAGE OF KILLBUCK HOLMES COUNTY, OHIO SW QTR. SECTION 6, T-8N, R-7W Scale In Feet 1"=60' I.P. Fd James E. Duncan's Addition To Killbuck This on to it had been to be R.R. Spk Fd we country. Plat Yol 1, Pg 288 Waltman's 1.P. Set - 5/8 Bar The book of the strategy Survey Record 3, Pg 171 Addition N/Cap. Lot 120 Lot 121 Reference: Plats & Deeds Shown VOI 127, Pg 163 Bearings: Arbitrary Alley Henry J. & Vicki L. 140' meas 165.73 1º42'36"W, tree on corner Yoder 0.21 6. Delmar P. Nicholas A Lannutti & Alder man 101 194, Pg 244 & others LOIS R. LANNUTTI on line (I was told he died this spring, but the estate must Deed Vol. 194, Pg 342 2' Alley Vacated By Ord 2-1959 Except for Right To Maintain Utilities É not be settled) Kuess, 0.910 Acres I.P. Fed I.ZO' West Of Cor. Used To Define E-W Line 80.07 meas. 139.90 meas. 164.32 140' rec. 51º42'36"E School St. BUCY DRIVE 49.5' The Description On The Lannutti Deed Uses The SW Corner Of Lot 119 As The Means To Locate The Parcel. From Original Plat Records & Evidence Found, This Places The Entire Lannutti Parcel 12 Feet North Of The Lines Presently Occupied. However, I Believe The Iron Pins Found Between Lannuth & Alderman Represent The Intent Of The Parties Subdividing The Original 1.79 Acre Parcel And Must Be Respected As Such.

Most Early Maps Of Killbuck Show An Alley From Railroad St. To T.R. 89 (Formerly 294) Which Would Have Been The South 12 Feet Of The Parcel Presently Occupied by Lannutti. I believe The Original Subdivider, Mr. James E: Duncan Intended To Leave A 12 Foot Alley There Although It Was Not Shown On The Original Plats. Since It Was Not Platted, It is Questionable Whether The Strip Was Legally A Public Alley. Any Rights The Yillage May Have Had Were Extinguished In 1959 by Ordinance 2-1959 Which Vacates The Alley, Except For The Right To Maintain The Utilities Located There. Since The Entire Alley Was A Part Of James E. Duncan's Land Originally, When vacated, It Reverts To The Assigns Of James E. Duncan, In This Case Mr. Lannutti

The 12 Foot Strip to The Public Road Mentioned in Lanutti's Deed Dates Back To The Orig. 1906 Transfer. My Guess Is The Road Coming Up The Hill Was Farther East Then. Go The 12' Strip Was For Access

I Certify This Survey To Be Correct To The Best Of My Knowledge

William H. Long Sept. 10, 1984

145255

William H. Long R.S. 4505 13301 T.R.503 Big Prairie, Ohio 44611

Rec'd. DEC 5 1984 AT2:33 O'CLOCK PM Recorded Dec le 1984 Holmes Co. Ohio Fee: Pg. 344 Recorder Pither Vol. 10 Deed Vol. 225-Pg. 647 Mtg. Vol. 143-Pg604