



NOTES

- ALL MAIN FLOOR WALLS OF UNITS WITH BASEMENTS ARE @ 5'-1 1/8" OFF OF SUBFLOOR UNLESS OTHERWISE NOTED ON PLAN
- ALL INTERIOR DOOR HEADER HEIGHTS ARE @ 82 3/4" OFF OF SUBFLOOR UNLESS OTHERWISE NOTED ON PLAN (THIS IS DUE TO THE 1/2" THERMITE SHIELD)
- ALL ANGLED HALLS IF ANY ARE @ 45° UNLESS NOTED OTHERWISE ON PLAN
- FRAME ALL WALLS THAT BUT INTO A FIRE MALL IN SUCH A WAY THAT THE DRYWALL THAT IS ATTACHED TO THE FIRE SEPARATION WALL CAN RUN STRAIGHT THROUGH
- DOORS BETWEEN GARAGE AND LIVING AREA TO BE 1-3/4" HONEYCOMB CORE STEEL DOOR WITH SILL RAISED NOT LESS THAN 4"
- ABOVE THE GARAGE FLOOR
- GARAGES WILL BE COMPLETELY SEPARATED FROM THE ADJACENT INTERIOR SPACES AND THE ATTIC AREA BY MEANS OF 1/2" GYPSUM BRD. OR EQUIVALENT APPLIED TO THE GARAGE SIDE
- DASHED LINE DENOTES 4" BRICK VENEER
- DOTTED LINE DENOTES FIRE SEPARATION WALL EXTENDING TO THE UNDERSIDE OF THE ROOF SHEATHING

200300027474
 Filed for Record in
 HOLMES COUNTY, OH
 SALLY MILLER
 11-19-2003 At 09:55 am
 SMALL PLAT 40.00
 DR Book 18 Page 807 - 807

200300027474
 JOHN T
 KEATING ATTY
 WOOSTER, OH

PICKET PLACE---BERLIN, OH---FOUR UNIT CONDO #254
 MAIN FLOOR PLAN---SCALE: 1/4"=1'
 WEAVER CUSTOM HOMES---WOOSTER, OHIO 44691---(330) 264-5444

