



Estimated Quantities
 Excavation 1456 cy.
 Gravel paving 13" center 9" sides 898 sq. yd.

Typical Section
 This plan contemplates placing 13" of loose gravel on center and 9" loose gravel on edge and it is assumed that the center will compact to 10" and the edge to 7" and will be accepted as such. Plank 3" wide shall be staked along the edge of pavement with a clearance of 1/4" and the top edge 4" below profile grade. No blocking of planks permitted. Any ruts in subgrade shall be leveled off before placing gravel. Gravel shall be placed between plank 13" in center being 2" above profile grade and 9" on the side, being 4" below profile grade, and shall have a true parabolic crown of 1/8". Side plank shall remain in place until berm is dressed up and gravel carefully leveled up. berms shall be built up or dressed off 2" below top edge of plank. The contractor shall provide a suitable template with the above crown.

