SHAFFER, JOHNSTON, LICHTENWALTER & ASSOCIATES, INC. ENGINEERS & SURVEYORS



BOUNDARY DESCRIPTION OF 2.161 AC. PARCEL

EW-2419CB

Situated in the Township of Berlin, T-9N; R-5W, Northeast Quarter of Section 15, County of Holmes and State of Ohio:

Known as being a part of lands conveyed to Laner Corporation in O.R. 0229; Page 0493 of Holmes County Official Records (PPN 0100091004) and further bounded and described as follows:

Commencing at a stone found at the northwest corner of the Northeast Quarter of Section 15, also being in T.R. 366;

Thence S 89° 25' 24" E, 763.59 feet along the section line and in T.R. 366 to a point at the northwest corner of lands conveyed to The Holmes County Board of Commissioners in O.R. 0272; Page 2563 of Holmes County Official Records ~ witnessed by a capped pin marked "S.J.L., INC." found S 16° 48' 52" W, 31.25 feet;

Thence S 16° 48' 52" W, 287.20 feet along a westerly line of lands conveyed to said Holmes County Board of Commissioners and along a westerly line of Lot 1 in EMB Allotment 1 as recorded in Volume 019; Page 4076 of Holmes County Plat Records and being lands conveyed to Northridge EMB, LLC in O.R. 0272; Page 2576 of Holmes County Official records to capped pin marked "S.J.L., INC." found;

Thence S 03° 13' 33" W, 380.14 feet along a westerly line of said Lot 1 to a capped pin marked "S.J.L., INC." found;

Thence S 17° 35' 11" W, 112.18 feet along a westerly line of said Lot 1 to a capped pin marked "S.J.L., INC." found;

Thence S 29° 47′ 18″ W, 233.96 feet along a westerly line of said Lot 1 to a capped pin marked "S.J.L., INC." found at the southwesterly corner thereof;

Thence S 86° 10′ 53″ E, 424.47 feet along the southerly line of said Lot 1 to capped pin marked "S.J.L., INC." found at the southeast corner and the principal place of beginning of the parcel herein described;

THENCE THE FOLLOWING TWENTY FOUR (24) COURSES:

Continued on Page 2

3477 Commerce Parkway, Suite C □ Wooster, Ohio 44691 Ph. (330) 345-6377 □ Fax (330) 345-6725 □ Email: sjl@sjl-inc.com

Page 2 (2.161 ac.)

- 1) S 86° 10' 53" E, 50.05 feet along the south line of lands conveyed to Laner Corporation in O.R. 0272; Page 2568 of Holmes County Official Records to a point on a west line of lands conveyed to Berlin Township Board of Trustees in O.R. 0253; Page 3420 of Holmes County Official Records ~ witnessed by a capped pin marked "S.J.L., INC." found S 01° 21' 53" W, 52.57 feet;
- 2) S 01° 21' 53" W, 107.02 feet along a west line of Berlin Township Board of Trustees lands and its westerly prolongation to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set at a point of curvature;
- southwesterly 203.99 feet along the arc of a curve deflecting to the right, said curve having a radius of 325.00 feet, a central angle of 35° 57' 46" and a chord which bears S 19° 20' 46" W, 200.66 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set;
- 4) S 37° 19' 39" W, 265.00 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set at a point of curvature;
- southwesterly **251.28** feet along the arc of a curve deflecting to the left, said curve having a radius of 275.00 feet, a central angle of 52° 21' 15" and a chord which bears S 11° 09' 01" W, 242.63 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set;
- 6) S 15° 01' 36" E, 253.24 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set at a point of curvature;
- 7) southwesterly 337.06 feet along the arc of a curve deflecting to the right, said curve having a radius of 275.00 feet, a central angle of 70° 13′ 30″ and a chord which bears S 20° 05′ 09″ W, 316.35 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set;
- 8) S 55° 11' 54" W, 45.16 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set at a point of curvature;
- 9) southwesterly **38.84** feet along the arc of a curve deflecting to the left, said curve having a radius of 25.00 feet, a central angle of 89° 01' 20" and a chord which bears S 10° 41' 14" W, 35.05 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set at a reverse curve and a northerly right-of-way line of S.R. 39;
- southeasterly, along a northerly right-of-way line of said S.R. 39, 12.71 feet along the arc of a curve deflecting to the right, said curve having a radius of 2904.80 feet, a central angle of 00° 15′ 03" and a chord which bears S 33° 41′ 55" E, 12.71 feet to a point ~ witnessed by a right-of-way monument found N 65° 54′ 19" E, 0.29 feet;

Continued on Page 3

Page 3 (2.161 ac.)

- 11) S 33° 34 '53" E, 304.22 feet along a northerly right-of-way line of said S.R. 39 to a point on a northerly line of Lot 4 in Ingram Subdivision Replat No. 1 as recorded in Volume 019 Page 4082 of Holmes County Plat Records and being lands conveyed to Holmes Ingram Group, LTD. in O.R. 0272; Page 3225 of Holmes County Official Records ~ witnessed by a 5/8" rebar found S 88° 57' 49" E, 28.26 feet;
- 12) N 88° 57' 49" W, 48.61 feet along a northerly line of said Lot 4 to a point in said S.R. 39 ~ witnessed by a capped pin with I.D. cap marked "BAKER" found S 88° 57' 49" E, 41.60 feet;
- 13) N 33° 34′ 53″ W, 277.03 feet in S.R. 39 to a point of curvature ~ witnessed by a right-of-way monument found S 56° 04′ 00″ W, 40.24 feet;
- northwesterly **223.19** feet along the arc of a curve deflecting to the left, said curve having a radius of 2864.80 feet, a central angle of 04° 27' 50" and a chord which bears N 35° 48' 48" W, 223.14 feet to a point in aforesaid S.R. 39 at a southeasterly corner of lands conveyed to Carl Swartzentruber & Judi Swartzentruber as recorded in Volume 228; Page 959 of Holmes County Deed records;
- N 50° 54' 13" E, 40.01 feet along a southeasterly line of said Carl Swartzentruber & Judi Swartzentruber lands to a point on a northerly right-of-way line of aforesaid S.R. 39 ~ witnessed by a 5/8" rebar found N 50° 54' 13" E, 13.57 feet;
- southeasterly, along a northerly right-of-way line of said S.R. 39, 115.60 feet along the arc of a curve deflecting to the right, said curve having a radius of 2904.80 feet, a central angle of 02° 16′ 49" and a chord which bears S 36° 55′ 10" E, 115.60 to a point of a reverse curve;
- southeasterly 38.84 feet along the arc of a curve deflecting to the left, said curve having a radius of 25.00 feet, a central angle of 89° 01' 20", and a chord which bears S 80° 17' 26" E, 35.05 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set;
- 18) N 55° 11' 54" E, 45.16 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set at a point of curvature;
- northeasterly 275.77 feet along the arc of a curve deflecting to the left, said curve having a radius of 225.00 feet, a central angle of 70° 13′ 30″, and a chord which bears N 20° 05′ 09″ E, 258.83 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set;
- 20) N 15° 01' 36" W, 253.24 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set at a point of curvature;

Continued on Page 4

Page 4 (2.161 ac.)

- 21) northeasterly **296.97** feet along the arc of a curve deflecting to the right, said curve having a radius of 325.00 feet, a central angle of 52° 21' 15" and a chord which bears N 11° 09' 01" E, 286.75 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set;
- 22) N 37° 19' 39" E, 265.00 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set at a point of curvature;
- northeasterly 172.61 feet along the arc of a curve deflecting to the left, said curve having a radius of 275.00 feet, a central angle of 35° 57' 46" and a chord which bears N 19° 20' 46" E, 169.79 feet to a 5/8" rebar with I.D. cap marked "S.J.L., INC." set;
- N 01° 21' 53" E, 109.16 feet to the principal place of beginning and containing within said bounds 2.161 acres of land, more or less, and subject to all legal highways and easements of record.

This description was prepared from a survey made by Mark E. Purdy, P.S. #7307 of Shaffer, Johnston, Lichtenwalter & Associates, Inc. in July of 2020.

Basis of bearing: The bearings as shown hereon are relative to GRID NORTH of the OHIO STATE PLANE COORDINATE SYSTEM, NAD 83 DATUM.

PURDY

See Plat Vol. 19; Page 4219 for survey.

Mark E. Purdy, P.S. #7307

Parcel Number: 0100091027

FILE DESCRIPTION

Holmes County Map Office 11/12/2020

3477 Commerce Parkway, Suite C □ Wooster, Ohio 44691 Ph. (330) 345-6377 □ Fax (330) 345-6725 □ Email: sjl@sjl-inc.com

4 of 4