Description 2.936 acre parcel

Being a part of Lot 13 of the First Quarter, Berlin Township, T-9 N, R-6 W, Holmes County, Ohio, also being a part of Lot 5 of Victoria Estates II Replatting of Victoria Estates and Additional Lands (P. 17- 217) also known as a part of the lands conveyed to Michael Conn, Rebecca Conn, Thomas Lee and Dawn Lee in Official Record vol. 251 page 4918, PN 0100247009.

Described as follows:

Commencing at a point marking the southwest corner of said Lot 13, thence N 00 degrees 36' 20" E 462.00 feet along the lot line to a R.R. spike found in the center of C.R. 203, thence S 84 degrees 33' 39" E 50.18 feet along the centerline of C.R. 203 to a point the TRUE POINT OF BEGINNING.

thence with the following ELEVEN (11) COURSES:

- 1) N 00 degrees 36' 20" E 335.00 feet along Thomas C. Lee and Dawn L. Lee's (O.R. vol. 44 page 310) east line to an iron pin set;
- 2) S 89 degrees 23' 40" E 137.94 feet along Sandra M. Conn's (O.R. vol. 44 page 315) south line to an iron pin set;
- 3) S 48 degrees 23' 00" E 54.04 feet through the lands of said Conn and Lee to an iron pin set on said Sandra M. Conn's southerly line;
- 4) S 00 degrees 36' 20" W 127.54 feet along said Sandra M. Conn's southerly line to a 5/8 inch rebar found;
- 5) S 49 degrees 08' 04" E 45.82 feet along said Sandra M. Conn's south line to a 5/8 inch rebar found;
- 6) N 71 degrees 30' 01" E 68.83 feet along said Sandra M. Conn's south line to a 5/8 inch rebar found;
- 7) N 62 degrees 34' 00" E 90.90 feet through the lands of said Conn and Lee to an iron pin set:
- 8) N 58 degrees 46' 41" E 145.62 feet through the lands of said Conn and Lee to an iron pin set on Michael W. Conn and Rebecca R. Conn's (O.R. vol. 255 page 6172) west line and on the west line of P.R. 5516 (a 50 foot private road);
- 9) S 01 degrees 32' 58" W 314.90 feet along said Michael W. Conn and Rebecca R. Conn's west line and along the west line of P.R. 5516 to a R.R. spike found in the center of C.R. 203, witnessed by a 5/8 inch rebar found N 01 degrees 32' 58" E 30.01 feet;
- 10) N 87 degrees 05' 07" W 225.44 feet along the centerline of C.R. 203 to a R.R. spike found;
- 11) N 84 degrees 33' 39" W 253.13 feet along the centerline of C.R. 203 to the TRUE POINT OF BEGINNING.

This parcel contains 2.936 acres, but subject to all highways and easements of record. To go to adjoiner.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83.

See Holmes County Plat Book 2, page 582 for survey. This survey made and description prepared by Aaron L. Gerber, P.S. 8379. April 23, 2019

Aaron L. Gerber

P.S. 8379



Parcel Number: 0100247052

Holmes County Map Office 6/21/2019