## Description 0.285 acre parcel

Being part of Lot 28, Third Quarter, T-9 N, R-5 W, Berlin Township, Holmes County, Ohio, also known as part of the lands conveyed to Reuben I. Mast and Amanda M. Mast in Official Record vol. 276 page 1829, PN 0100309002.

## Described as follows:

Commencing at a 5/8 inch rebar found marking the northeast corner of Lot 28, thence N 88 degrees 56' 30" W 774.01 feet along the lot line to a point in T.R. 367, thence S 37 degrees 42' 56" W 85.05 feet along Leon M. Mullet and Laura Mullet's (O.R. 246 page 4240) west line and along T.R. 367 to a point the TRUE POINT OF BEGINNING, witnessed by a 5/8 inch rebar found S 66 degrees 33' 20" E 2.63 feet.

thence with the following FIVE (5) COURSES:

- 1) S 66 degrees 33' 20" E 84.76 feet along said Mullet's south line to a 5/8 inch rebar found;
- 2) S 29 degrees 09' 03" W 143.94 feet along said Mullet's west line to a 5/8 inch rebar found:
- 3) N 57 degrees 10' 23" W 90.76 feet through the lands of said Mast to a point on Marvin E. Miller and Miriam Miller's (O.R. 287 page 5152) east line and in T.R. 367, witnessed by an iron pin set S 57 degrees 10' 23" E 17.47 feet;
- 4) N 25 degrees 23' 44" E 61.64 feet along said Miller's east line and along T.R. 367 to a point;
- 5) N 37 degrees 42' 56" E 68.95 feet along said Miller's east line and along T.R. 367 to the TRUE POINT OF BEGINNING.

This parcel contains 0.285 acres, but subject to all highways and easements of record. To go to adjoiner.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

See Holmes County Plat Book\_\_\_\_\_\_\_\_, page\_\_\_\_\_5331\_\_\_\_\_\_ for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. March 27, 2024

Donald C. Baker

P.S. 6938



Parcel Number: 0100309007