## Description 0.928 acre parcel (Road Dedication) (Hawk's Landing Subdivision Phase 4, P. 2 – 552)

Being a part of Lot 1 of the Fourth Quarter, Berlin Township, T-9 N, R-6 W, Holmes County, Ohio, also known as a part of the lands conveyed to East Holmes Development, Ltd. in Official Record vol. 178 page 1310, PN 0101319105.

## Described as follows:

Beginning at a 5/8 inch rebar found marking the southeast corner of Lot 61 of said Hawk's Landing Subdivision Phase 4 and marking the northwest corner of Falcon Drive (19-2365) the TRUE POINT OF BEGINNING.

thence with the following EIGHTEEN (18) COURSES:

- 1) S 26 degrees 07' 59" E 50.00 feet along the west line of said Falcon Drive to a 5/8 inch rebar found on the north line of Lot 63 of said Hawk's Landing Subdivision Phase 4;
- 2) S 63 degrees 52' 01" W 38.20 feet along the north line of said Lot 63 to a 5/8 inch rebar found:
- 3) Along a curve to the left having a delta angle of 90 degrees 00' 00", R 20.00 feet, T 20.00 feet, Ch. Brg. S 18 degrees 52' 01" W, Ch. 28.28 feet along the north line of said Lot 63 an arc distance of 31.42 feet to a 5/8 inch rebar found;
- 4) S 26 degrees 07' 59" E 88.46 feet along the west line of Lots 63 and 64 of said Hawk's Landing Subdivision Phase 4 to a 5/8 inch rebar found;
- 5) Along a curve to the right having a delta angle of 106 degrees 17' 25", R 60.00 feet, T 80.04 feet, Ch. Brg. S 38 degrees 21' 49" E, Ch. 96.02 feet along the west line of Lots 64 and 65 of said Hawk's Landing Subdivision Phase 4 an arc distance of 111.31 feet to a 5/8 inch rebar found:
- 6) Along a curve to the right having a delta angle of 82 degrees 38' 34", R 60.00 feet, T 52.75 feet, Ch. Brg. S 56 degrees 06' 10" W, Ch. 79.23 feet along the north line of Lots 66 and 67 of said Hawk's Landing Subdivision Phase 4 an arc distance of 86.54 feet to a 5/8 inch rebar found;
- 7) S 63 degrees 52' 01" W 266.83 feet along the north line of Lots 67, 68, 69 and 70 of said Hawk's Landing Subdivision Phase 4 and along the south line of Lot 54 of Hawk's Landing Subdivision Phase 3 (P.V. 19-2403) to a 5/8 inch rebar found;
- 8) N 26 degrees 07' 59" W 50.00 feet through the lands of said East Holmes Development, Ltd. to a 5/8 inch rebar found;
- 9) N 63 degrees 52' 01" E 255.00 feet through the lands of said East Holmes Development, Ltd. and along the south line of Lots 71 and 72 of said Hawk's Landing Subdivision Phase 4 to a 5/8 inch rebar found;
- 10) Along a curve to the left having a delta angle of 90 degrees 00' 00", R 20.00 feet, T 20.00 feet, Ch. Brg. N 18 degrees 52' 01" E, Ch. 28.28 feet along the south line of said Lot 72 an arc distance of 31.42 feet to a 5/8 inch rebar found;
- 11) N 26 degrees 07' 59" W 123.31 feet along the east line of Lots 72 and 73 of said Hawk's Landing Subdivision Phase 4 to a 5/8 inch rebar found;

- 12) Along a curve to the left having a delta angle of 87 degrees 23' 17", R 20.00 feet, T 19.11 feet, Ch. Brg. N 69 degrees 49' 38" W, Ch. 27.63 feet along the east line of said Lot 73 an arc distance of 30.50 feet to a 5/8 inch rebar found;
- 13) Along a curve to the right having a delta angle of 23 degrees 56' 42", R 274.11 feet, T 58.13 feet, Ch. Brg. S 78 degrees 27' 05" W, Ch. 113.72 feet along the north line of Lots 73 and 74 of said Hawk's Landing Subdivision Phase 4 an arc distance of 114.56 feet to a 5/8 inch rebar found;
- 14) N 89 degrees 34' 34" W 22.05 feet along the north line of said Lot 74 to a 5/8 inch rebar found:
- 15) N 00 degrees 25' 26" E 50.00 feet through the lands of said East Holmes Development, Ltd. to a 5/8 inch rebar found;
- 16) S 89 degrees 34' 34" E 22.05 feet through the lands of said East Holmes Development, Ltd. to a 5/8 inch rebar found;
- 17) Along a curve to the left having a delta angle of 26 degrees 33' 25", R 224.11 feet, T 52.89 feet, Ch. Brg. N 77 degrees 08' 44" E, Ch. 102.95 feet along the south line of Lot 62 of said Hawk's Landing Subdivision Phase 4 an arc distance of 103.88 feet to a 5/8 inch rebar found;
- 18) N 63 degrees 52' 01" E 114.79 feet along the south line of Lots 62 and 61 of said Hawk's Landing Subdivision Phase 4 to the TRUE POINT OF BEGINNING.

This parcel contains 0.928 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Bearings from Plat vol. 2 page 552.

See Holmes County Plat Book 2, page 580 for survey.

This survey made and description prepared by Donald C. Baker, P.S. 6938.

March 8, 2019

Donald C. Baker

P.S. 6938



Parcel Number: 0101319106

FILE DESCRIPTION

Holmes County Map Office 5/23/2019