Description 2.210 acre parcel

Being part of the northeast quarter of Section 12, Clark Township, T-8 N, R-5 W, Holmes County, Ohio, also known as part of the lands conveyed to Betty Miller in Deed vol. 254 page 132 and to Betty C. Miller in Official Record vol. 246 page 5067, PN 0200207000, PN 0200208000.

Described as follows:

Commencing at a 5/8 inch rebar found marking the southwest corner of the northeast quarter of Section 12, thence S 88 degrees 48' 35" E 1433.49 feet along the quarter section line to a point, thence N 33 degrees 03' 47" E 741.88 feet along Fender's Fish Hatchery, LLC's (O.R. vol. 258 page 782 and O.R. vol. 258 page 786) west line to a 3/4 inch pipe found, thence N 32 degrees 21' 33" E 187.50 feet along said Fender's Fish Hatchery, LLC's west line to an iron pin set the TRUE POINT OF BEGINNING.

thence with the following NINE (9) COURSES:

- 1) N 48 degrees 42' 25" W 464.84 feet through the lands of said Miller to a point in the center of S.R. 557, witnessed by an iron pin set S 48 degrees 42' 25" E 27.66 feet;
- 2) N 51 degrees 41' 02" E 57.81 feet along the centerline of S.R. 557 to a point;
- 3) N 47 degrees 21' 06" E 92.03 feet along the centerline of S.R. 557 to a point, witnessed by an iron pin set S 47 degrees 45' 00" E 27.25 feet;
- 4) S 47 degrees 45' 00" E 205.69 feet along John F. Jorg and Deborah K. Jorg's (Deed vol. 213 page 79) south line to a 3/4 inch rebar found;
- 5) N 61 degrees 15' 16" E 52.90 feet along said Jorg's east line to a 3/4 inch pipe found:
- 6) S 47 degrees 44' 46" E 300.68 feet along Roy E. Barkman, Mary A. Barkman and Marie Ann Barkman's (O.R. vol. 274 page 1979) south line to a 3/4 inch rebar found on Paul A. Miller's (O.R. vol. 250 page 3694) west line;
- 7) S 28 degrees 55' 23" W 51.38 feet along said Paul A. Miller's west line to a 1/2 inch pipe found;
- 8) S 28 degrees 31' 37" W 142.56 feet along said Paul A. Miller's west line to a 3/4 inch rebar found:
- 9) N 48 degrees 53' 39" W 122.17 feet along said Fender's Fish Hatchery, LLC's north line to the TRUE POINT OF BEGINNING.


This parcel contains 2.210 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83.

19 See Holmes County Plat Book , page for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. May 25, 2021

P.S. 8379



Parcel Number: 0200207001

FILE DESCRIPTION

Holmes County Map Office 6/30/2021

2 of 2