## **DESCRIPTION OF A 2.693 ACRE PARCEL**

Situated in the Township of Clark, County of Holmes and State of Ohio, being part of the Northwest Quarter of Section 17, in Township 8 North, Range 4 West of the United States Military District and being the same parcel conveyed to Timothy P. Troyer and Shawna M. Troyer (P.N. 02-00459.000) and recorded in O.R. Vol. 280, Pg. 1714 of the Holmes County Official Records, and more fully bounded and described as follows:

**Beginning** at a 5/8" iron pin found at the southwest corner of said Northwest Quarter of Section 17; Thence S 88°18'49" E, along the southerly line of said Northwest Quarter of Section 17, passing a 5/8" iron pin found at a distance of 34.96 feet, a total distance of 787.97 feet to an iron pin set, said point being the **True Place of Beginning** for the parcel of land herein described;

Course No. 1; Thence along a southeasterly line of a parcel conveyed to Ohio Central Railroad, Inc. and recorded in Deed Volume 240, Page 204 of the Holmes County Deed Records along the arc of a non-tangent curve to the right having a radius of 2831.93 feet, a delta angle of 02°23'11", a chord length of 117.94 feet, and a chord bearing of N 52°21'36" E, the arc length of 117.95 feet to an iron pin set;

Course No. 2; Thence N 53°33'11" E, along a southeasterly line of said parcel conveyed to Ohio Central Railroad, Inc., a distance of 747.59 feet to an iron pin set;

Course No. 3; Thence S 29°13'59" E, along a southwesterly line of a parcel conveyed to Timothy P. Troyer and Shawna M. Troyer and recorded in O.R. Vol. 280, Pg. 1714 of the Holmes County Official Records, passing a bent 5/8" iron pin found at a distance of 177.30 feet, a total distance of 227.28 feet to a point;

Course No. 4; Thence S 67°33'00" W, along a northwesterly line of a parcel conveyed to Countryside Chapel of Baltic, Ohio and recorded in Deed Volume 277, Page 187 of the Holmes County Deed Records and along a northwesterly line of a parcel conveyed to Miriam Hershberger, Marvin Ray Hershberger and Anna Jean Hershberger and recorded in O.R. Volume 275, Page 6522; O.R. Volume 232, Page 1068; O.R. Volume 228, Page 1950 of the Holmes County Official Records and being a centerline of State Route 93 (variable width right-of-way), a distance of 97.00 feet to a point;

Course No. 5; Thence S 66°48'39" W, along a northwesterly line of said parcel conveyed to Miriam Hershberger, Marvin Ray Hershberger and Anna Jean Hershberger and being a centerline of said State Route 93, a distance of 64.47 feet to a point;

Course No. 6; Thence S 66°01'13" W, along a northwesterly line of said parcel conveyed to Miriam Hershberger, Marvin Ray Hershberger and Anna Jean Hershberger and being a centerline of said State Route 93, a distance of 134.81 feet to a point;

Course No. 7; Thence S 64°23'05" W, along a northwesterly line of said parcel conveyed to Miriam Hershberger, Marvin Ray Hershberger and Anna Jean Hershberger and along a northwesterly line of said



parcel conveyed to Countryside Chapel of Baltic, Ohio and being a centerline of said State Route 93, a distance of 102.85 feet to a point;

Course No. 8; Thence S 62°39'02" W, along a northwesterly line of said parcel conveyed to Countryside Chapel of Baltic, Ohio and being a centerline of said State Route 93, a distance of 88.79 feet to a point;

Course No. 9; Thence S 60°38'04" W, along a northwesterly line of said parcel conveyed to Countryside Chapel of Baltic, Ohio and being a centerline of said State Route 93, a distance of 117.27 feet to a point;

Course No. 10; Thence S 58°23'38" W, along a northwesterly line of said parcel conveyed to Countryside Chapel of Baltic, Ohio and being a centerline of said State Route 93, a distance of 119.25 feet to a point;

Course No. 11; Thence N 88°18'49" W, along said southerly line of the Northwest Quarter of Section 17, passing an iron pin set at a distance of 44.33 feet, a total distance of 158.37 feet to the **True Place of Beginning** and containing 2.693 acres of land, more or less, as surveyed by David J. Kroger, P.S., Ohio Registration No. S-8329, in February, 2022, but subject to all legal roads, highways, right of ways, easements and leases of record.

The Basis of Bearing is Ohio State Plane Coordinates, North Zone, NAD 1983.

All iron pins set are 30 inch X 3/4 inch round steel bars with plastic caps stamped "DIVERSIFIED ENGINEERING".

2/18/2022 S. Professional Surveyor No. S-8329 Kroger, P Date

Survey recorded in Plat Vol. <u>19</u>, Pg. <u>4655</u>.

Parcel Number: 0200459002



_		_
	FILE DESCRIPTION	
	Holmes County Map Office	
	3/25/2022	
		_

2 of 2

DEI-7549 Description 2.693 Acre Tract.docx