Description 6.926 acre parcel

Being a part of Lots 7 and 8, First Quarter, Hardy Township, T-9 N, R-7 W, Holmes County, Ohio, also known as all of the lands conveyed to Lonnie G. Cutlip in Deed vol. 205 page 819, PN 0600143000 and PN 0600144000.

Described as follows:

Commencing at a 5/8 inch rebar found marking the southwest corner of Lot 7, thence S 88 degrees 17' 01" E 115.92 feet along the lot line to a 5/8 inch rebar found the TRUE POINT OF BEGINNING.

thence with the following SIXTEEN (16) COURSES:

- 1) N 18 degrees 48' 06" E 86.43 feet along The Board of Commissioners of the Holmes County Park District's (O.R. vol. 191 page 1407) east line to a point on the lot line;
- 2) N 61 degrees 24' 18" E 0.74 feet along the lot line to a point;
- 3) N 18 degrees 48' 06" E 398.62 feet along said The Board of Commissioners of the Holmes County Park District's east line to a point;
- 4) Along a curve to the left having a delta angle of 00 degrees 19' 13", R-6416.26 feet, T-17.93 feet, Ch. Brg. – N 18 degrees 23' 24" E, Ch.-35.86 feet along said The Board of Commissioners of the Holmes County Park District's east line, an arc distance of 35.86 feet to a point on the lot line;
- 5) N 85 degrees 57' 42" W 17.54 feet along the lot line to a point;
- 6) Along a curve to the left having a delta angle of 00 degrees 45' 21", R-6399.26 feet, T-42.20 feet, Ch. Brg. N 17 degrees 53' 26" E, Ch. 84.41 feet along said The Board of Commissioners of the Holmes County Park District's east line an arc distance of 84.41 feet to a 5/8 inch rebar found;
- S 88 degrees 19' 24" E 693.12 feet along Dennis E. Schlabach and Marie D. Schlabach's (O.R. 205 page 1354) south line to a 5/8 inch rebar found on the west line of S.R. 83;
- S 13 degrees 39' 09" W 207.88 feet along said Schlabach's west line and along the west line of S.R. 83 to a 5/8 inch rebar found;
- S 08 degrees 59' 43" W 105.83 feet along said Schlabach's west line and along the west line of S.R. 83 to a 5/8 inch rebar found;
- 10) N 80 degrees 58' 00" W 95.32 feet along 4 Dawn Enterprises, LLC's (O.R. vol. 266 page 1949) north line to a 5/8 inch rebar found;



- 11) N 14 degrees 34' 41" W 86.58 feet along 4 Dawn Enterprises, LLC's north line to a 5/8 inch rebar found;
- 12) N 84 degrees 19' 07" W 217.66 feet along 4 Dawn Enterprises, LLC's north line to a 5/8 inch rebar found;
- 13) S 18 degrees 53' 20" W 173.70 feet along 4 Dawn Enterprises, LLC's west line to a 5/8 inch rebar found;
- 14) S 81 degrees 38' 11" E 87.06 feet along 4 Dawn Enterprises, LLC's south line to a 5/8 inch rebar found;
- 15) S 14 degrees 42' 05" W 211.94 feet along Holmes County Holdings, Ltd.'s (O.R. vol. 271 page 436) west line to a 5/8 inch rebar found on the lot line;
- 16) N 88 degrees 17' 01" W 447.73 feet along the lot line to the TRUE POINT OF BEGINNING.

This parcel contains 6.926 acres, but subject to all highways and easements of record.

Containing 5.311 acres in Lot 7 and 1.615 acres in Lot 8.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83.

See Holmes County Plat Book <u>19</u>, page <u>4563</u> for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. October 20, 2021

Donald C. Baker

P.S. 6938



Parcel Number: 0600143003

٢	FILE DESCRIPTION	7
	Holmes County Map Office	
Ĺ	11/29/2021	(
٦	2 of 2	