

Address: 5434 TR 377, Millersburg, OH 44654 **Phone:** 330.231.0497

Description: 1.206 Acres

Being a part of the Southwest Quarter of Section 11 and the Village of Millersburg, T-9 N, R-7 W, Hardy Township, Holmes County, Ohio, also known as the lands of Robert Lanchman and Melissa D. Morris in O.R. Vol. 252 Page 2180 (PPN 0701135000).

Described as follows:

Commencing at a point marking the Southwest corner of the Southwest Quarter of section 11, thence S 86 degrees 58'25" E a distance of 678.10 feet along the section line to a point, thence N 01 degree 14'37" E a distance of 664.64 feet along the west line of Mary L. Gindlesberger, trustee (O.R. Vol. 209 Page 2840), Green Hills, LLC (O.R. Vol. 185 Page 2699), Brittany A. Schmucker (O.R. Vol. 274 Page 2172), and Laura Augsburger and John M. Pierson (O.R. Vol. 249 Page 2792) to a point, thence S 88 degrees 25'56" E a distance of 270.12 feet along the south line of Eli A. Miller (O.R. Vol. 262 Page 4398) and along the south line of Briar Lane, Village of Millersburg (O.R. Vol. 267 Page 742) to a 5/8 inch rebar found, thence N 12 degrees 33'17" W a distance of 82.47 feet to a 5/8 inch rebar found being the TRUE PLACE OF BEGINNING;

Thence with the following FOUR (4) COURSES:

- 1. N 01 degree 06'58" E a distance of 235.25 feet along the east line of said Village of Millersburg and Briar Lane to a square rod found;
- 2. N 87 degrees 49'03" E a distance of 159.48 feet along the south line of J. Robert Morrison, trustee and Lucy V. Morrison, trustee (O.R. Vol. 186 Page 2461) to a 5/8 inch rebar found;
- 3. S 02 degrees 10'18" W a distance of 436.95 feet along the west line of Victor R. Snyder (O.R. Vol. 120 Page 375 and O.R. Vol. 269 Page 1010) to a pipe found;
- 4. N 37 degrees 01'54" W a distance of 244.72 feet along the east line of said Green Hills, LLC to the TRUE PLACE OF BEGINNING.

This parcel contains 1.206 acres, but sub of record.	oject to all highways, easements, and restrictions
All iron pins set are 5/8 inch rebars with	plastic identification "Galbraith 8703"
Basis of Bearings from Grid North, Ohio NAD 83	o State Plane Coordinate System, North Zone,
See Holmes County Plat Book19	Page 4986 for survey.
This survey was made and description properties of the properties	repared by Caleb Jerome Galbraith P.S. 8703.
Parcel Number: 0701135001	CALEB JEROME GALBRAITH S-8703 FGISTERED SSIONAL SUR

Holmes County Map Office 5/1/2023