## Description 37.920 acre parcel

Being a part of the southeast quarter of Section 20, Mechanic Township, T-8 N, R-6 W, Holmes County, Ohio, also known as part of the lands conveyed to Eli J. S. Barkman and Esther S. Barkman in Official Record vol. 178 page 3011, PN 1200035000, PN 1200035004 and PN 1200024001.

Described as follows:

Beginning at an iron pin set marking the northwest corner of the southeast quarter of Section 20 the TRUE POINT OF BEGINNING.

thence with the following SEVEN (7) COURSES:

- 1) S 85 degrees 40' 53" E 1989.26 feet along the quarter section line to a 5/8 inch rebar found;
- 2) S 04 degrees 46' 14" W 402.05 feet along Freeman S. Raber and Martha Raber's (O.R. 186 page 3283 and O.R. 224 page 596) west line to a 1/2 inch pipe found;
- 3) S 87 degrees 28' 42" W 678.05 feet through the lands of said Barkman to an iron pin set;
- S 03 degrees 07' 37" E 528.83 feet through the lands of said Barkman to a point in the center of T.R. 117, witnessed by an iron pin set N 03 degrees 07' 37" W 10.25 feet;
- 5) N 88 degrees 52' 40" W 57.01 feet along the centerline of T.R. 117 to a 5/8 inch rebar found;
- 6) N 86 degrees 00' 00" W 1332.13 feet along the centerline of T.R. 117 to an iron pin set on the quarter section line;
- 7) N 04 degrees 44' 55" E 1017.78 feet along the quarter section line to the TRUE POINT OF BEGINNING.

This parcel contains 37.920 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Bearings from Plat vol. 16 page 85.

See Holmes County Plat Book <u>19</u>, page <u>3900</u> for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. September 3, 2019

Donald C. Baker P.S. 6938



Parcel Number: 1200035007

