JASON J. LINGENFELTER, P.S.

PROFESSIONAL LAND SURVEYOR

Boundary description of a 0.500 acre parcel

Situated in the State of Ohio, County of Holmes, Township of Mechanic and known as being a part of the Southeast Ouarter of Section 1, T-8N; R-7W;

Also known as being a part of the lands conveyed to Justin T. Evans in Official Record Volume 255, Page 3083, (PPN. 1300011006), of Holmes County Official Records and further bound and described as follows:

Commencing at a 5/8 inch rebar found and known as being the northeast corner of the Southeast Quarter of Section 1, Mechanic Township;

Thence, S 01° 09' 55" W, 367.50 feet along the section line to a 5/8 inch rebar found;

Thence, S 48° 49' 50" W, 917.40 feet to a 5/8 inch rebar with ident cap "Baker" found;

Thence, S 71° 25' 50" W, 380.00 feet to a railroad spike found in County Road 58;

Thence, N 22° 18' 08" W, 513.14 feet to a point witnessed by a 5/8 inch rebar found N 70° 57' 15" E, 34.39 feet and the principal place of beginning of the parcel herein described:

THENCE WITH THE FOLLOWING FOUR (4) COURSES:

- N 22° 18' 08" W, 97.03 feet along the Grantor's southwesterly line and with County Road 58 to a point witnessed by a capped rebar set N 70° 57' 15" E, 30.00 feet;
- 2) N 70° 57' 15" E, 221.60 feet across the Grantor's lands to a capped rebar set;
- 3) **S 26° 03' 14" E, 97.60** feet across the Grantor's lands to a capped rebar set on the northwesterly line of the lands of Terry Michael Evans, (O.R. V-54, P-377, PPN 1300011007);
- 4) S 70° 57' 15" W, 228.00 feet along the Grantor's southeasterly line and the northwesterly line of said Evans lands to the principal place of beginning and containing within said bounds 0.500 acres of land more or less, and subject to all legal highways and easements of record.

Continued on Page 2



Page 2 (Description of 0.500 ac.)

This description was prepared from a survey made by Jason J. Lingenfelter, P.S. #8499 in December of 2020.

Basis of bearing: The bearings as shown hereon are relative to GRID NORTH of the OHIO STATE PLANE COORDINATE SYSTEM, NAD 83 DATUM.

See Plat Book Volume 19; Page 4313 for survey.

Jason J. Langerfelter
Professional Surveyor No. 8499
December 14, 2020

JASON J.

LINGENFELTER

8499

FEGISTERED

SONAL

MINIMARIAN

SONAL

MINIMARIAN

MINIMARIAN

SONAL

MINIMARIAN

MINIMARIAN

SONAL

MINIMARIAN

MINI

Parcel Number: 1300011008

FILE DESCRIPTION

Holmes County Map Office 2/26/2021