

Description 0.096 acre parcel

Being part of the northwest quarter of Section 1, T-8 N, R-7 W, Mechanic Township, Holmes County, Ohio, also known as part of the lands conveyed to Conrad L. Yoder and Erika J. Yoder in Official Record 268 page 1227, PN 1300158001.

Described as follows:

Commencing at a 5/8 inch rebar found marking the southeast corner of the northwest quarter of Section 1, thence N 88 degrees 23' 30" W 792.90 feet along the quarter section line to a 5/8 inch rebar found the TRUE POINT OF BEGINNING.

thence with the following FOUR (4) COURSES:

- 1) N 88 degrees 23' 30" W 144.20 feet along the quarter section line to a 5/8 inch rebar found;
- 2) N 01 degree 33' 12" E 30.00 feet along Allen V. Troyer and Pamela J. Troyer's (O.R. 269 page 4395) east line to a point in the center of T.R. 102;
- 3) S 87 degrees 38' 54" E 144.21 feet along the centerline of T.R. 102 to a point;
- 4) S 01 degree 33' 10" W 28.13 feet along John J. Hlafka and Kimberly A. Hlafka's (Deed vol. 276 page 341) west line to the TRUE POINT OF BEGINNING.

This parcel contains 0.096 acres, but subject to all highways and easements of record. To go to adjoiner.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

See Holmes County Plat Book 2, page 671 for survey.
This survey made and description prepared by Donald C. Baker, P.S. 6938.
August 21, 2025


Donald C. Baker P.S. 6938



PPN: 1300158010

