Description 58.337 acre parcel

Being a part of Lot 5 of the Fourth Quarter, Monroe Township, T-9 N, R-8 W, Holmes County, Ohio, also known as part of the lands conveyed to Mary J. Burgett, Trustee in Official Record vol. 216 page 463, PN 1400058000.

Described as follows:

Beginning at a stone found marking the southeast corner of said Lot 5 the TRUE POINT OF BEGINNING.

thence with the following SEVENTEEN (17) COURSES:

- 1) N 88 degrees 02' 39" W 1525.97 feet along the lot line to an iron pin set;
- 2) N 08 degrees 39' 18" E 344.86 feet through the lands of said Burgett to an iron pin set:
- 3) N 08 degrees 32' 31" E 312.98 feet through the lands of said Burgett to an iron pin set:
- 4) N 08 degrees 34' 14" E 770.49 feet through the lands of said Burgett to an iron pin set;
- 5) N 09 degrees 54' 25" E 246.04 feet through the lands of said Burgett to an iron pin set;
- 6) N 78 degrees 24' 07" E 149.80 feet through the lands of said Burgett to an iron pin set:
- 7) N 08 degrees 03' 48" E 707.34 feet through the lands of said Burgett to an iron pin set;
- 8) S 87 degrees 47' 39" E 498.13 feet through the lands of said Burgett to an iron pin set;
- 9) S 04 degrees 23' 03" W 791.27 feet through the lands of said Burgett to an iron pin set:
- 10) S 05 degrees 38' 57" W 231.12 feet through the lands of said Burgett to a point, witnessed by an iron pin set N 05 degrees 38' 57" E 8.96 feet;
- 11) S 77 degrees 20' 25" E 109.11 feet through the lands of said Burgett to an iron pin set;
- 12) S 87 degrees 14' 32" E 210.02 feet through the lands of said Burgett to an iron pin set;
- 13) S 69 degrees 08' 39" E 149.08 feet through the lands of said Burgett to a point in the center of T.R. 260, witnessed by a R.R. spike set N 69 degrees 08' 39" W 7.35 feet;
- 14) S 03 degrees 27' 08" E 14.95 feet along T.R. 260 and along Jon T. Mast and Leslee Mast's (D.V. 242 page 291) west line to a point;
- 15) S 51 degrees 57' 21" E 195.87 feet along T.R. 260 and along said Mast's south line to a point;
- 16) S 25 degrees 47' 12" E 111.15 feet along T.R. 260 and along said Mast's west line to a point on the lot line, witnessed by an iron pin set S 02 degrees 39' 33" W 23.46 feet;
- 17) S 02 degrees 39' 33" W 1077.46 feet along the lot line to the TRUE POINT OF BEGINNING.

This parcel contains 58.337 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Bearings assumed.

See Holmes County Plat Book____2____, page____595____ for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. December 17, 2019

Donald C. Baker P.S. 6938



Parcel Number: 1400058004

Holmes County Map Office 3/2/2020