

Address: 5434 TR 377, Millersburg, OH 44654 **Phone:** 330.231.0497

Description: 0.085 Acres

Being part of the Fourth Quarter Lot 23, Monroe Township, T-9N, R-8 W, Holmes County, Ohio, also known as part of the lands of Toro Investments, LLC in O.R. Vol. 271 Page 2881 (PPN 1400081003).

Described as follows:

Commencing at a 5/8 inch rebar found marking the southeast corner of Lot 23, thence N 88 degrees 06'24" W a distance of 382.20 feet along the Killbuck Township line and lot line to a 5/8 inch rebar found capped "Baker" being the TRUE PLACE OF BEGINNING.

Thence with the following FOUR (4) COURSES;

- 1. N 88 degrees 06'24" W a distance of 98.89 feet along the Killbuck Township line and lot line to a point;
- 2. N 19 degrees 41'51" E a distance of 70.37 feet through the lands of said Toro Investments, LLC to an iron pin set;
- 3. S 59 degrees 41'37" E a distance of 33.49 feet along the south line of Lot 1 of JT Subdivision recorded in Plat Vol. 19 Page 2830 of Jared T. Cline and Tennille Cline (O.R. Vol. 253 Page 7378) to a 5/8 inch rebar found;
- **4. S 41 degrees 17'31" E a distance of 70.02 feet** along the south line of said Lot 1 of JT Subdivision recorded in Plat Vol. 19 Page 2830 of said Jared T. Cline and Tennille Cline to the TRUE PLACE OF BEGINNING.

This parcel contains 0.085 acres and is subject to all highways, easements, and restrictions of record.

Bearings from Grid North, Ohio State Plane Coordinate System, North Zone, NAD 83.				
For survey see:	Plat Book Vol	19	_Page	4198
All iron pins set are 5/8-inch rebars 30 inches long with a plastic identification cap marked "Galbraith 8703".				
This survey was August 4, 2020.	s made and descript	ion prepared		Jerome Galbraith P.S. 8703. on CALEB JEROME
Parcel Numb	er: 1400081013		;	GALBRAITH S-8703 FEGISTERED STONAL SURVIVIO

FILE DESCRIPTION

Holmes County Map Office 10/22/2020