Description 12.708 acre parcel

Being a part of Lot 12, Fourth Quarter, Monroe Township, T-9 N, R-8 W, Holmes County, Ohio, also known as part of the lands conveyed to Shelar Properties IV, LLC in Official Record vol. 274 page 6029, PN 1400095002.

Described as follows:

Commencing at a 5/8 inch rebar found marking the northwest corner of Lot 12, thence S 87 degrees 38' 33" E 1248.89 feet along the lot line and partly along T.R. 269 to a point the TRUE POINT OF BEGINNING, witnessed by an iron pin set S 02 degrees 01' 41" W 4.69 feet.

thence with the following EIGHT (8) COURSES:

- 1) S 87 degrees 38' 33" E 50.00 feet along the lot line and along T.R. 269 to a point, witnessed by an iron pin set S 02 degrees 01' 41" W 6.50 feet;
- 2) S 02 degrees 01' 41" W 816.74 feet through the lands of said Shelar Properties IV, LLC to an iron pin set;
- 3) S 87 degrees 38' 33" E 124.81 feet through the lands of said Shelar Properties IV, LLC to an iron pin set;
- 4) S 02 degrees 01' 41" W 1012.23 feet through the lands of said Shelar Properties IV, LLC to an iron pin set;
- 5) N 87 degrees 38' 33" W 506.52 feet through the lands of said Shelar Properties IV, LLC to a point, witnessed by an iron pin set N 02 degrees 01' 41" E 40.22 feet;
- 6) N 02 degrees 01' 41" E 1012.23 feet through the lands of said Shelar Properties IV, LLC to an iron pin set;
- 7) S 87 degrees 38' 33" E 331.71 feet through the lands of said Shelar Properties IV, LLC to an iron pin set;
- 8) N 02 degrees 01' 41" E 816.74 feet through the lands of said Shelar Properties IV, LLC to the TRUE POINT OF BEGINNING.

This parcel contains 12.708 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings from Plat vol. 19 page 4140.

See Holmes County Plat Book 19 page 4314 for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. January 13, 2021

Donald C. Baker

P.S. 6938

DONALD

C.

BAKER
6938

6938

ONAL SURFINIA

Parcel Number: 1400095012