

Address: 5434 TR 377, Millersburg, OH 44654 **Phone:** 330.231.0497

Description: 6.294 Acres

Being part the Lot 5 of the First Quarter, T-9 N, R-8 W, Monroe Township, Holmes County, Ohio, also known as part of the lands conveyed to Joan M. Miller in Deed Vol. 263 Page 167, PPN 1400317000.

Described as follows:

Commencing at a 5/8 inch rebar found marking the southwest corner of Lot 5, thence N 1 degrees 09'37"E a distance of 377.77 feet along the Lot Line and the centerline of Township Road 266 to a railroad spike found being the TRUE PLACE OF BEGINNING;

Thence with the following TWELVE (12) COURSES;

- 1. N 01 degrees09'37" E a distance of 1266.31 feet leaving said road and along the Lot Line to a stone found marking the northwest corner of Lot 5 passing through a 5/8 inch rebar found capped "Baker" at a distance of 72.05 feet;
- 2. S 87 degrees 43'43" E a distance of 103.95 feet along the Lot Line to an iron pin set;
- 3. S 03 degrees 55'43" E a distance of 187.34 feet leaving said Lot Line and through the lands of said Joan M. Miller to an iron pin set;
- 4. S 48 degrees07'22" E a distance of 83.41 feet through the lands of said Joan M. Miller to an iron pin set;
- 5. S 03 degrees 59'12" W a distance of 132.71 feet through the lands of said Joan M. Miller to an iron pin set;
- 6. S 15 degrees 06'33" E a distance of 413.89 feet through the lands of said Joan M. Miller to an iron pin set;
- 7. S 10 degrees10'56" E a distance of 337.02 feet through the lands of said Joan M. Miller to an iron pin set on the west line of Betsy Joan Miller (O.R. Vol. 166 Page 76);

- 8. S 08 degrees19'38" W a distance of 47.28 feet along the west line of said Betsy Joan Miller to a railroad spike found in the centerline of said road witnessed by a 5/8 inch rebar found capped "Baker" N 08 degrees 19'38" E a distance of 23.32 feet;
- 9. N 87 degrees26'30" W a distance of 175.18 feet along the centerline of said road and through the lands of said Joan M. Miller to a railroad spike found;
- 10. S 84 degrees17'29" W a distance of 109.00 feet along the centerline of said road and through the lands of said Joan M. Miller to a railroad spike found;
- 11. S 53 degrees 57'52" W a distance of 62.51 feet along the centerline of said road and through the lands of said Joan M. Miller to a railroad spike found;
- 12. S 17 degrees32'02" W a distance of 72.45 feet along the centerline of said road and through the lands of said Joan M. Miller to the TRUE PLACE OF BEGINNING.

This parcel contains 6.294 acres and is subject to all highways, easements, and restrictions of record.

To go to adjoiner.

Bearings from Grid North, Ohio State Plane Coordinate System, North Zone, NAD 83.

For survey see: Plat Book Vol. _____19 ____ Page ____3966

All iron pins set are 5/8 inch rebars, 30 inches long with a plastic identification cap marked "Galbraith 8703".

This survey was made and description prepared by Caleb Jerome Galbraith P.S. 8703. on October 24, 2019.

GALBRAITH

Parcel Number: 1400317003

W- Hote

FILE DESCRIPTION

Holmes County Map Office 1/3/2020

2 of 2