## JASON J. LINGENFELTER, P.S. PROFESSIONAL LAND SURVEYOR

Boundary description of a 6.029 acre parcel

Situated in the State of Ohio, County of Holmes, Township of Monroe and known as being a part of the 1<sup>st</sup> Quarter of Lot 17, T-9N; R-8W;

Also known as being the lands conveyed to Adam Campbell & Linda Campbell in Official Record Volume 262, Page 4523, (PPN. 1400362000 & PPN. 1400363000), of Holmes County Official Records and further bound and described as follows:

Commencing at a 5/8 inch rebar found and known as being the southwest corner of Lot 17, 1<sup>st</sup> Quarter, Monroe Township;

Thence, S 88° 02' 54" E, 369.64 feet along the lot line to a 5/8 inch rebar with ident cap "Baker" found and the principal place of beginning of the parcel herein described:

THENCE WITH THE FOLLOWING THIRTEEN (13) COURSES:

- 1) N 03° 26' 12" E, 249.73 feet along the Grantor's westerly line and the easterly line of the lands conveyed to Clayton A. Armstrong, (O.R. V-258, P-4724 & O.R. V-264, P-1581, PPN:1400332001), to a capped rebar set;
- 2) **S 86° 06' 40'' E, 115.00** feet to a capped rebar set;
- 3) N 03° 37' 08" E, 138.66 feet to a capped rebar set on a southeasterly line of State Route 39, (Variable right of way), the Grantor's northwesterly line and the southeasterly line of the lands conveyed to Martin J. Weaver & Laura Beth Weaver, (O.R. V-259, P-1415, PPN:1400020005);
- 4) **N 59° 34' 10" E, 83.52** feet along the southeasterly right of way line of State Route 39, the Grantor's northwesterly line and the southeasterly line of said Weaver lands to a capped rebar set;

٠,

- 5) S 31° 30' 29" E, 45.59 feet to a capped rebar set;
- 6) **S 69° 17' 07" E, 236.00** feet to a capped rebar set;
- 7) **S 29° 11' 59" E, 51.11** feet to a capped rebar set;

Continued on Page 2



P.O. BOX 2 SHREVE, OHIO 44676 Ph. (330) 231-3957 Page 2 (Description of 6.029 ac.)

- 8) S 15° 17' 53" W, 215.00 feet to a capped rebar set;
- 9) **S 87° 05' 00'' E, 280.00** feet to a capped rebar set;
- 10) **N 06° 45' 28" E, 175.00** feet to a capped rebar set on the southwesterly line of State Route 39, (variable right of way), the Grantor's northeasterly line and the southwesterly line of the lands conveyed to Mindy Eppley, (D. V-265, P-703 & D. V-265, P-706, PPN. 1400020004);
- 11) S 72° 56' 51" E, 687.83 feet along the southwesterly right of way line of State Route 39, the Grantor's northeasterly line, the southwesterly line of said Eppley lands and the southwesterly line of the lands conveyed to Kenneth Allen Asher, (D. V-265, P-713, PPN. 1400020003, to a 5/8 inch rebar found;
- 12) **S 41° 49' 11" E, 72.96** feet along the southwesterly right of way line of State Route 39, the Grantor's northeasterly line and the southwesterly line of said Asher lands to a capped rebar set on the lot line witnessed by a <sup>3</sup>/<sub>4</sub> inch rebar found N 88° 02' 54" W, 59.61 feet;
- 13) **N 88° 02' 54" W, 1430.55** feet along the lot line and the Grantor's southerly line to the principal place of beginning and containing within said bounds **6.029** acres of land more or less, of which 3.712 acres are contained in PPN. 1400362000 and 2.317 acres are contained in PPN. 1400363000, but as one, and subject to all legal highways and easements of record.

This description was prepared from a survey made by Jason J. Lingenfelter, P.S. #8499 in January of 2021.

All rebars set are 5/8" diameter by 30" long with plastic cap stamped "LINGENFELTER".

Basis of bearing: The bearings as shown hereon are relative to GRID NORTH of the OHIO STATE PLANE COORDINATE SYSTEM, NAD 83 DATUM.

See Plat Book Volume <u>19</u>; Page <u>450</u>7 for survey.

Parcel Number: 1400362002

Jason J. Kingenfelter Professional Surveyor No. 8499 February 4, 2021



Г	FILE DESCRIPTION	
	Holmes County Map Office	
	10/1/2021	
7		

2 of 2

P.O. BOX 2 SHREVE, OHIO 44676 Ph. (330) 231-3957