Description 6.328 acre parcel

Being a part of Fractional Section 3, T-14 N, R-11 W, Paint Township, Holmes County, Ohio, also known as part of the lands conveyed to Pauline R. Kasserman, Trustee in Official Record vol. 226 page 2361, PN 1500153000.

Described as follows;

Commencing at a 5/8 inch rebar found marking the northwest corner of Fractional Section 3, thence S 89 degrees 36' 29" E 2061.80 feet along the section line to a 5/8 inch rebar found, thence S 00 degrees 14' 41" E 1376.93 feet along Kathy D. Schneider, Trustee's (O.R. 204 page 2945 and O.R. 263 page 2779) east line to a point in the center of T.R. 670, thence N 85 degrees 36' 33" E 358.88 feet along the centerline of T.R. 670 to a mag nail set, thence N 81 degrees 54' 36" E 98.12 feet along the centerline of T.R. 670 to a R.R. spike set, thence N 75 degrees 29' 37" E 92.20 feet along the centerline of T.R. 670 to a point the TRUE POINT OF BEGINNING, witnessed by an iron pin set S 00 degrees 55' 35" E 22.79 feet.

thence with the following EIGHT (8) COURSES:

- 1) N 72 degrees 44' 11" E 54.60 feet along the centerline of T.R. 670 to a mag nail set;
- 2) N 73 degrees 54' 09" E 61.09 feet along the centerline of T.R. 670 to a mag nail set;
- N 81 degrees 49' 08" E 128.76 feet along the centerline of T.R. 670 to a mag nail set;
- 4) N 86 degrees 14' 36" E 110.84 feet along the centerline of T.R. 670 to a point;
- 5) N 86 degrees 34' 44" E 25.56 feet along the centerline of T.R. 670 to a 5/8 inch rebar found, witnessed by an iron pin set S 00 degrees 55' 35" E 39.10 feet;
- 6) S 00 degrees 55' 35" E 751.96 feet through the lands of said Kasserman to an iron pin set;
- 7) S 89 degrees 04' 25" W 375.32 feet through the lands of said Kasserman to an iron pin set;
- 8) N 00 degrees 55' 35" W 697.77 feet through the lands of said Kasserman to the TRUE POINT OF BEGINNING.

This parcel contains 6.328 acres, but subject to all highways and easements of record.


All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83.



19 4241 See Holmes County Plat Book____ , page for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. October 5, 2020

P.S. 6938



Parcel Number: 1500153004

